


Update of AOC-06 Per- and Polyfluoroalkyl Substances (PFAS) Supplemental Site Inspection

**Presented by:
Tetra Tech, Inc
NAVFAC Mid-Atlantic
06 December 2023**

AOC-06 at Former NWIRP Calverton



PFAS Area of Concern

AOC-06 Aircraft Development Systems Building and Hangars 5, 6, 7, and 8




- **AOC-06 Overview:**


- Hangars equipped with AFFF fire suppression systems.
- AFFF stored in ADSB Building.
- Groundwater flow is expected to Northeast.

- **Previous Site Inspection Results:**

- PFAS concentrations in soil less than screening levels.
- PFAS concentrations in groundwater slightly greater than screening levels.
 - PFOA
 - PFOS
 - PFNA




AOC-06 Real Estate Access



2023 Supplemental Site Inspection at AOC-06




- Fieldwork conducted August 14 – 30, 2023
- Soil Investigation:
 - Soil samples from four new locations:
 - Three upgradient and one within south-eastward drainage pathway to evaluate potential runoff.
 - Sampled three depth intervals below ground surface (bgs):
 - Surface Soil (0-2 inches bgs).
 - Shallow Surface Soil (2-24 inches bgs).
 - Subsurface Soil (24-48 inches bgs).



2023 Supplemental Site Inspection at AOC-06



- **Groundwater Investigation:**
 - Thirteen new permanent piezometers installed and developed for groundwater sampling.
 - Sixteen total piezometers sampled (13 new and 3 existing).
 - Water level measurements at piezometers used to refine understanding of groundwater flow.



Utility Clearance



- Subcontractor (Ground Penetrating Radar Systems – GPRS):
 - Cleared 10 ft x 10 ft area for piezometers on 08/14/23.
 - Identified anomalies (stormwater lines, manholes, pipes, etc.) that need to be avoided.
 - Piezometer locations were adjusted within the cleared area based on locations of utilities.
- Contacted NY Call Before You Dig and had utility company mark outs.



Utility Clearance



- Air Knifing
 - Delivers pressurized airflow into soil to break it up without risking damage to underground utilities.
 - Driller (Unitech) conducted air knifing to 6 feet at each location.
- Hand Auger
 - Soil borings for sampling were cleared using a hand auger.



Stock Image:

<https://static1.squarespace.com/static/57b5f31e579fb32986dbeab9/t/57c86cb4bebabf4a07d4b8e7/1472752835659/>

Drilling and Soil Boring



- **Direct Push Technology (DPT)**
 - Collected continuous cores to identify soil layers at four piezometer locations.
- **Hollow Stem Augers**
 - Used to install piezometers.
- **Hand Augering**
 - Used for soil sampling.



Soil Sampling




- Tetra Tech collected all soil samples by hand augering.
- Decontaminated equipment before and between uses.
 - Removed excess soil.
 - Scrubbed with water and Alconox.
 - Rinsed with PFAS-free water.
- Soil samples collected from three depth intervals bgs at each location.
- Samples sent to Battelle for laboratory analysis for PFAS by Method 1633.



Piezometer Installation


Typical Monitoring Well Construction Details



- Careful consideration of materials to avoid cross contamination of PFAS


Piezometer Development

- Tetra Tech developed wells via purging to remove:
 - stagnant water.
 - fine soil particles from water and well screen.
- Development complete when:
 - Minimum purge volume met.
 - Water quality parameters stabilized within 10%.
 - Turbidity below 10 NTUs.



Piezometer Sampling

- Tetra Tech sampled groundwater from the 16 piezometers.
- Wells purged to remove stagnant water and stabilize the chemistry of the water prior to collecting a representative sample.
 - pH
 - specific conductivity
 - temperature
 - dissolved oxygen
 - turbidity
 - oxidation reduction potential
- Samples shipped to Battelle for laboratory analysis for PFAS by Method 1633.



Decontamination Procedures

- Decontamination of equipment done before any work done on site and before drilling at each piezometer location.
 - Augers were decontaminated using a steam cleaner and rinsed with PFAS-free water.



IDW Management



- Investigation Derived Waste (IDW):
 - Consisted of soil removed during drilling and water from piezometer development/purging.
 - Stored at dedicated staging area for short-term until characterization completed.
 - Thirty-four 55-gallon drums of soil.
 - Approximately 300 gallons of aqueous waste.
- Waste characterization samples
 - Organics, inorganics, corrosivity, ignitability, reactive cyanide and sulfide, PCBs, and PFAS.
- Transportation and Disposal
 - Solid IDW transported offsite for disposal (Dale Transfer Corporation).
 - Liquid IDW transported offsite for disposal (Bergen Point Wastewater Treatment Plant).



Surveying



- Borbas Surveying and Mapping, LLC surveyed the new piezometers and soil boring locations on August 29, 2023.
 - Provided location information (horizontal coordinates and vertical elevation data) for each piezometer and soil boring.



QUESTIONS?