

DISCLAIMER: These Standard Operating Procedures (SOP's) are for the exclusive use of Navy Public Works Center (PWC) Norfolk. They are promulgated as guidance for their NAVFAC Commands. If intended to be used by other activities, they must be tailored to each activity's particular requirements and must be reviewed/approved by the activity's safety professionals prior to use.

**NAVY PUBLIC WORKS CENTER
NORFOLK, VIRGINIA
UTILITIES DEPARTMENT**

STANDARD OPERATING PROCEDURE / JOB HAZARD ANALYSIS

TITLE

INSTALL BLADE SWITCHES - OVERHEAD

PROCEDURE NUMBER

WC 624 HVE 027

DISTR:

601A

610

620

WC 624

SIGNED:_____
(DATE)

APPROVED:_____
(DATE)

SAFETY PROFESSIONAL:_____
(DATE)

MANAGEMENT OFFICIAL:_____
(DATE)

DATE:_____

REVISION DATE:_____

INSTALL BLADE SWITCHES - OVERHEAD

Purpose:

Procedure to install overhead blade switches.

Potential Energy Sources:

1. Energized circuits in close proximity of work.
2. Deenergized circuits which are not included in the work and have not been grounded.
3. Generators supplying temporary power to facilities which have had their normal power switched off due to this work.

Tools and PPE:

Tools: Bucket truck, rubber hoses, rubber blankets, rubber insulator hoods, cutters, hand tools, hydraulic drill, pneumatic drill, brace and bit, hand line, high voltage tester. PPE: Nomex coveralls, Nomex hood, insulating rubber gloves, insulating rubber sleeves, hard hat, safety shoes, work gloves, safety glasses, orange vest, safety harness, and back brace if required by back injury prevention and control program. The class of rubber gloves and sleeves will depend on the exposure voltage as per the following: Class 0 - up to 1,000 volts, Class 1 - up to 7,500 volts, Class 2 - up to 17,000 volts, Class 3 - up to 26,500 volts, Class 4 - up to 36,000 volts.

References:

1. PWC Occupational Safety and Health Program Manual, PWCNORVAINST 5100.33E
2. SOP WC 624 HVE 001, Set Up and Secure Bucket/Auger Truck
3. Occupational Safety and Health Standards for General Industry (29 CFR PART 1910): Subpart I, Personnel Protective Equipment; Subpart R, Electrical Power Generation / Transmission / Distribution; Subpart S, Electrical
4. NFPA 70 E approach distances to exposed, energized, electrical conductors and circuit parts.
5. ANSI C2-1987 National Electrical Safety Code
6. Electrical Transmission and Distribution Safety Manual, P-1060
7. The Lineman's and Cableman's Handbook, 5th ED
8. SOP WC 622 HVE 013, Deenergization, Lockout, Tagout
9. SOP WC 622 HVE 007, Switchout and Switchback Energized Circuit

Procedures:

1. Set up bucket truck. Refer to SOP WC 624 HVE 001, Set Up and Secure Bucket/Auger truck for details.

INSTALL BLADE SWITCHES - OVERHEAD

2. When operating a bucket truck the following safety rules will be followed.

- a) Only an authorized person, one with a current government license to operate an aerial lift, will operate the bucket.
- b) Do not use the bucket truck if winds exceed the truck manufacture's specified limit.
- c) Do not perform energized work in wet weather.

d) Personnel in bucket will wear a safety harness with a lanyard attached to the boom or bucket.
e) Do not exceed the bucket's weight limitations.
f) Stand firmly on the floor of the bucket with both feet.
Do not sit on the bucket's edge or use planks, ladders, or other such devices.

3. If the blades are being installed on an existing circuit, WC 622 personnel will deenergize the circuit as per the following SOPs:

WC 622 HVE 007, Switchout and Switchback Energized Circuit

WC 622 HVE 013, Deenergization, Lockout, Tagout

If the blades are being installed on a new circuit, or a new lateral off an existing circuit, the conductors are already deenergized.

4. Insulate energized conductors within 3 feet of the work area. Insulate deenergized overhead circuits within 3 feet of the work area which are not included in the work and have not been grounded as per Lockout and Tagout procedures. Personnel in the bucket shall wear Nomex coveralls, Nomex hood, safety glasses, safety shoes, insulating rubber gloves and sleeves, and hard hat.

5. If WC 622 deenergizes a circuit, test the circuit, using a high voltage tester test the circuit to be worked on to verify it is deenergized. Before the circuit conductors are checked, test the high voltage tester on a known energized circuit to verify the tester is working. Test each deenergized circuit conductors separately, taking care not to cross phase during test. If voltage is detected, stop the test and (a) notify WC 622 personnel that the circuit is still energized, (b) wait for WC 622 personnel to correct the problem, (c) perform the deenergization verification test once again after WC 622 personnel finish switching operations and declare the circuit deenergized. If no voltage is indicated, retest the high voltage tester to re-verify it is working properly. Wear listed Nomex coveralls, Nomex hood, safety glasses, safety shoes, insulating rubber gloves and sleeves, and hard hat.

INSTALL BLADE SWITCHES - OVERHEAD

6. The following rules will apply to job.

a) Bucket personnel working poles which have energized circuits or circuits which have not been properly grounded will wear Nomex coveralls, safety glasses, safety shoes, hard hat, safety harness, insulating rubber gloves insulating rubber sleeves, and a back brace if required to wear. The circuits in question have been insulated per Step 4.
b) Bucket personnel working on poles which have all other high voltage

circuits deenergized and properly grounded, or which have no other circuits on the poles, will wear hard hats, work gloves, safety shoes, safety harness, safety glasses when required, and a back brace if required to wear

- c) Personnel in the bucket will carry a hand line aloft with them.
- d) Personnel in bucket will wear ear protection and safety glasses when drilling.
- e) Ground personnel will wear hard hats, safety shoes, work gloves, and safety glasses.
- f) Ground personnel will wear orange vests if working adjacent to a road or in a parking lot.
- g) Ground personnel not involved with the work will watch the personnel working aloft.
- h) Ground personnel will stay clear of area underneath the bucket unless the work dictates.
- i) If ground personnel are present, then at least one of them will have been trained to operate the bucket in an emergency situation where the bucket personnel are no longer able to operate the bucket controls.

7. Drill hole(s) in pole if necessary. Use hydraulic, pneumatic, or brace and bit to drill hole(s). Avoid using an extension cord when working near energized conductors over 600 volts.

8. Hang two sets of crossarms. The crossarms will be double arms made up with DA bolts. Attach arms to pole and have ground personnel level them. After the arms are leveled secure them in position with hard head or bolt. Refer to attached LANTDIVENGCOM Pole Line Plates for further information concerning equipment and installation.

9. Drill holes in the arms in order to mount the switches. Measure the bolt holes on the switches to obtain the correct cross arm hole pattern, and to insure proper switch clearances. Use hydraulic, pneumatic, or brace and bit to drill hole(s).

INSTALL BLADE SWITCHES - OVERHEAD

Avoid using an extension cord when working near energized conductors over 600 volts.

10. Mount new blade switches. Switches will be pulled aloft by ground personnel using a hand line. Secure the switches using 1/2" by 6" long bolts. The blades will be in the open position.

11. Connect jumpers from the switches' loadside to the circuit or equipment being fed from the blades. The jumper should be sized to handle the anticipated maximum load. Position jumper to meet required clearances

12. Connect jumpers from the line side of the blade switches to the circuit that will feed the cutouts. Insure that proper clearances are met. If necessary, attach jumper to the pole or crossarm using an insulator and tie wire. The jumper should be sized to handle the anticipated maximum load.

13. Remove insulation placed on energized conductors. Remove insulation placed on conductors which are not included in the work and have not been grounded as per Lockout and Tagout procedures. Personnel in the bucket shall wear Nomex coveralls, Nomex hood, safety glasses, safety shoes, insulating rubber gloves and sleeves, and hard hat. Remove insulation in reverse order that it was placed.

14. Secure bucket truck. Refer to SOP WC 624 HVE 001, Set Up and Secure Bucket/Auger Truck, for details.

15. WC 622 personnel will energize the circuit, or equipment, as per the following SOPs:

WC 622 HVE 007, Switchout and Switchback Energized Circuit

WC 622 HVE 013, Deenergization, Lockout, Tagout