

Per- and Polyfluoroalkyl Substances (PFAS) Overview

NAVAL WEAPONS STATION (NWS) YORKTOWN, VIRGINIA

Presented by:
Tetra Tech, Inc
NAVFAC Mid-Atlantic
1 June 2022

Overview



- Project Scope
- Work Completed
- Next Steps

Project Scope



- Information Research
- Preparation of a Preliminary Assessment (PA)
 Report
- Preparation of a Sampling and Analysis Plan (SAP) for the PFAS Site Inspection (SI)
- Field Investigation
- SI Reporting


Work Completed



- October 2021: Final PA Report
 - Out of 75 areas screened, 9 Areas of Interest recommended for additional investigation through an SI
- March 2022: Final SI SAP for soil and groundwater
- March to May 2022: Field Investigation
 - Installation of 35 monitoring wells
 - Collected 78 soil samples and 40 groundwater samples

Work Completed






Site 1 – Dudley Road Landfill



- Basis of SI
 Recommendation: Reported disposal of oily wastewater containing AFFF pumped from fire training pits at SSA 3
- Previous Cleanup: 1999 soil/debris removal action
- Media: Groundwater only
- Completed: Sampled 5
 existing wells (GW024
 sampled in lieu of new well
 and GW004 in lieu of GW005)



Site 4 – Burn Pad Residue Landfill and Site 22 – Burn Pad




· Site 4

- Basis of SI
 Recommendation: Main
 landfill for Site 22 and during
 timeframe of PFAS use
- -Several removal actions
- -Media: GW only
- -Completed: 4 new wells installed/sampled

• Site 22

- Basis of SI
 Recommendation: 2017
 groundwater samples:
 elevated concentrations of PFOS
- -Media: Soil and GW
- Completed: 3 new wells installed/sampled, 10 soil locations sampled near previous exceedances, 20 soil samples



SSA 3 – Fire Training Pits and Vicinity and Building 461 Fire Station No. 14



•SSA 3

-Basis of SI Recommendation:

Documented use of AFFF for firefighter training activities at the former fire training pits


-1996 removal of concrete pits, tanker trailer, and burnt soil

Bldg 461

Basis of SI Recommendation:
 Presumed historical handling,
 storage, and potential release
 of AFFF at Building 461

• Media: GW and soil

 Completed: installed/samples 8 new wells, 18 soil samples



Building 24 Betty Warehouse Fire



Basis of SI Recommendation:

Documented use of AFFF to extinguish the Building 24 fire

- Media: GW and soil
- Completed: Installed/sampled 5 New wells, 10 soil samples



Building 27 Fire



Basis of SI
 Recommendation: Use of

 AFFF to extinguish the
 Building 27 fire

• Media: GW and soil


Completed:
 Installed/sampled 5 new wells, 10 soil samples



Building 71 Former Fire Station



- Basis of SI
 Recommendation: use as a fire station and assumption of handling and storage of AFFF
- Media: GW and soil
- Completed: installed/sampled 4 new wells, 8 soil samples




Building 703 Main Fire Station No. 13



Basis of SI
 Recommendation:
 presumed handling,
 storage, and potential
 release of AFFF

Media: GW and soil

•Completed: installed/sampled 6 new wells, 12 soil samples



Next Steps



- Summer 2022: Data analysis and validation
- Late Summer 2022: Data evaluation and initial recommendation
- Fall 2022 2023: SI Report, which will summarize data collected and recommendation for a path forward for each AOI
 - Draft SI Report April 2023
 - Draft Final SI Report June 2023
 - Final SI Report August 2023

Questions or Comments?



For additional information regarding the ERP at Naval Weapons Station (NWS) Yorktown, please contact:

Cecilia Landin – Navy's ERP Manager for NWS Yorktown (757) 341-2014 or cecilia.a.landin.civ@us.navy.mil

Jeff Kissler – Environmental Director for NWS Yorktown (757) 887-4086 or John.j.kissler1@navy.mil

NWS Yorktown Publics Affair Officer (757) 887-4939

Visit NWS Yorktown's ERP Public Web Page at: http://go.usa.gov/xfP6h