



## **Officer in Charge of Construction Marine Corps Installations East**



### **MP Working Dog Kennel Relocation**

CONTRACTOR:	THR Enterprises, Inc.
AWARD DATE:	01 September 2010
COMPLETION DATE:	05 August 2012
PERCENT COMPLETE:	95% (as of 20 May 12)
CONTRACT VALUE:	\$4,791,894

#### **PROJECT DESCRIPTION:**

Design-bid-build contract to construct a 14,000 square-foot, single-story working dog kennel constructed of structural steel framing, reinforced Concrete Masonry Unit (CMU) walls with brick veneer, and standing seam metal roof. Floor plan includes kennel, kitchen, waiting, sleeping, administration, maintenance, training/briefing, locker/shower, storage and general purpose areas. An emergency back-up generator and parking area are included. Work will also include an energy saving electronic monitoring and control system (EMCS). Sustainable design features will be included in the design, development, and construction of this facility in accordance with the Energy Policy Act of 2005.