RR-00039-03.13-04/01/88

SUPPLEMENTAL APPENDIX OF LABORATORY DATA-- EVALUATION OF DATA FROM FIRST AND SECOND ROUNDS OF VERIFICATION SAMPLE COLLECTION AND ANALYSIS

CONFIRMATION STUDY TO DETERMINE POSSIBLE DISPERSION AND MIGRATION OF SPECIFIC CHEMICALS-- U.S. NAVAL STATION ROOSEVELT ROADS, PUERTO RICO AND U.S. NAVAL AMMUNITION FACILITY, VIEQUES

Contract No. N62470-85B-7972

Prepared for:

Atlantic Division, Naval Facilities
Engineering Command, Norfolk, Virginia

Prepared by:

Environmental Science and Engineering, Inc.
Sacramento, California

April 1988

APPENDIX A

LABORATORY DATA FOR ROUND 1 OF VERIFICATION SAMPLING AND ANALYSIS

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW4 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	IGW1	IGW2	IGW3
UNITS	METHOD	PRGW1	PRGW1	PRGW1
		1	2	3
DATE		03/10/86	03/24/86	03/10/86
TIME		12:45	12:20	12:30
PH,FIELD	400	7.04	7.16	6.92
STD UNITS	0			
BENZENE	34030	<0.27	<0.28	<0.27
UG/L	10			
BROMODICHLOROMETHANE	32101	<0.56	<0.65	<0.55
UG/L	10			
BROMOFORM	32104	<1.3	<1.5	<1.3
UG/L	10			
BROMOMETHANE	34413	<1.3	<0.99	<1.2
UG/L	10			
CARBON TETRACHLORIDE	32102	<0.97	<1.0	<0.95
UG/L	10			
CHLOROBENZENE	34301	<0.47	<0.44	<0.46
UG/L	10			
CHLOROETHANE	34311	<1.6	<1.3	<1.6
UG/L	10			
2-CHL'ETH'VINYLETHER	34576	<1.1	<1.2	<0.98
UG/L	10			
CHLOROFORM	32106	<0.50	2.6	<0.49
UG/L	10			
CHLOROMETHANE	34418	<1.7	<2.4	<1.7
UG/L	10			
DIBROMOCHLOROMETHANE	32105	<1.01	<1.01	<0.990
UG/L	10			
1,1-DICHLOROETHANE	34496	<0.44	<0.46	<0.43
UG/L	10			
1,2-DICHLOROETHANE	34531	<0.84	<0.91	<0.83
UG/L	10			
1,1-DICHLOROETHYLENE	34501	<1.1	<1.1	<1.1
UG/L	10			
T-1,2-DICHLOROETHENE	34546	<0.95	<1.1	<0.94
UG/L	10			
1,2-DICHLOROPROPANE	34541	<0.59	<0.60	<0.58
UG/L	10			
CIS-1,3-DICH'PROPENE	34704	<0.42	<0.45	<0.41
UG/L	10			
T-1,3-DICHL'PROPENE	34699	<1.2	<1.3	<1.1
UG/L	10			
ETHYLBENZENE	34371	<0.95	<1.1	<0.94
UG/L	10			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW4 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	IGW1 PRGW1 1	IGW2 PRGW1 2	IGW3 PRGW1 3
UNITS	METHOD			
DATE		03/10/86	03/24/86	03/10/86
TIME		12:45	12:20	12:30
METHYLENE CHLORIDE	34423	<0.65	<0.70	<0.65
UG/L	10			
1,1,2,2-TE'CH'ETHANE	34516	<0.53	<0.63	1.0
UG/L	10			
TOLUENE	34010	<0.40	<0.44	<0.40
UG/L	10			
1,1,1-TRICHL'ETHANE	34506	<0.90	<1.0	<0.88
UG/L	10			
1,1,2-TRICHL'ETHANE	34511	<1.0	<1.1	<1.0
UG/L	10			
TRICHLOROETHENE	39180	<1.1	<1.1	<1.1
UG/L	10			
TRICHL'FLUOROMETHANE	34488	<0.90	<0.91	<0.88
UG/L	10			
VINYL CHLORIDE	39175	<1.1	<0.98	<1.1
UG/L	10			
M-XYLENE	98553	<0.73	<0.78	<0.72
UG/L	10			
LEAD,TOTAL	1051	<24.0	<50.0	<24.0
UG/L	0			
METHYL ETHYL KETONE	81595	<4.2	<8.3	<4.2
UG/L	10			
METHYL ISOBUT'KETONE	81596	<0.61	<0.77	2.5
UG/L	10			
O-AND/OR-P XYLENE	98554	<0.73	<0.80	<0.72
UG/L	10			
DICHLOROBENZENE,T.	81524	<0.7	<0.8	<0.7
UG/L	10			
TETRACHLOROETHENE	34475	<1.6	<1.6	<1.5
UG/L	10			
CHROMIUM,(+6)	1032	<20.0	<20.0	<20.0
UG/L	0			
CHROMIUM,TOTAL	1034	286	303	309
UG/L	0			
1,2-DIBR'ETHANE(EDB)	77651	<0.020	0.0	<0.020
UG/L	0			
OIL&GR,IR	560	0.4	0.6	0.4
MG/L	0			

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS4 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	ISE1 PRSE1 1	ISE2 PRSE1 2	ISE3 PRSE1 3
DATE			01/10/86	01/10/86	01/10/86
TIME			10:15	10:30	10:45
BENZENE	UG/G-DRY	98699 10	<0.11	<0.05	<0.05
BROMODICHLOROMETHANE	UG/G-DRY	98783 10	<0.10	<0.10	<0.10
BROMOFORM	UG/G-DRY	98784 10	<0.22	<0.22	<0.22
BROMOMETHANE	UG/G-DRY	98785 10	<0.20	<0.20	<0.20
CARBON TETRACHLORIDE	UG/G-DRY	98680 10	<0.18	<0.18	<0.18
CHLOROBENZENE	UG/G-DRY	98681 10	<0.07	<0.07	<0.07
CHLOROETHANE	UG/G-DRY	98786 10	<0.26	<0.27	<0.26
2-CHLOROETHYLVINYLETHER	UG/G-DRY	98796 10	<0.21	<0.22	<0.21
CHLOROFORM	UG/G-DRY	98682 10	<0.086	<0.088	<0.085
CHLOROMETHANE	UG/G-DRY	98787 10	<0.22	<0.23	<0.22
DIBROMOCHLOROMETHANE	UG/G-DRY	98788 10	<0.17	<0.17	<0.17
1,1-DICHLOROETHANE	UG/G-DRY	98683 10	<0.13	<0.13	<0.13
1,2-DICHLOROETHANE	UG/G-DRY	98684 10	<0.15	<0.15	<0.15
1,1-DICHLOROETHENE	UG/G-DRY	98789 10	<0.17	<0.17	<0.17
TRANS-1,2-DICHLOROETENE	UG/G-DRY	98687 10	<0.16	<0.16	<0.16
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.11	<0.11	<0.10
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.07	<0.07	<0.07
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.19	<0.20	<0.19
ETHYLBENZENE	UG/G-DRY	98688 10	<0.16	<0.16	<0.15
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.14	<0.14	<0.14

A-3

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS4 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	ISE1 PRSE1 1	ISE2 PRSE1 2	ISE3 PRSE1 3
DATE			01/10/86	01/10/86	01/10/86
TIME			10:15	10:30	10:45
1,1,2,2-TETRACHLOROE THANE	UG/G-DRY	98793 10	<0.09	<0.09	<0.09
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.24	<0.25	<0.24
TOLUENE	UG/G-DRY	98691 10	<0.13	<0.13	<0.13
1,1,1-TRICHLOROETHAN E	UG/G-DRY	98692 10	<0.16	<0.16	<0.16
1,1,2-TRICHLOROETHAN E	UG/G-DRY	98693 10	<0.17	<0.18	<0.17
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.17	<0.17	<0.17
TRICHLOROFLUOROMETHA NE	UG/G-DRY	98794 10	<0.15	<0.15	<0.15
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.16	<0.16	<0.16
PH,SOIL		99218 0	7.6	7.2	7.6
1,2-DIBROMOETHANE (E DB)	MG/KG-DRY	98798 0	<0.002	<0.002	<0.002
M-XYLENE	MG/KG-DRY	98799 10	<0.12	<0.12	<0.12
O,P-XYLENE	MG/KG-DRY	98800 10	<0.12	<0.13	<0.12
OIL&GR,IR,SED	UG/G- DRY	561 0	63	86	120
LEAD,SED	UG/G-DRY	1052 0	<2.31	<2.80	<2.86
MOISTURE	%WET WT	70320 0	5.9	6.6	6.2
METHYL ETHYL KETONE	UG/G-DRY	98801 10	<5.8	<6.2	<4.5
MIBK	UG/G-DRY	98696 10	<0.21	<0.21	<0.21
DICHLOROBENZENE,TOTA L	UG/G-DRY	98803 10	<0.11	<0.11	<0.11
CHROMIUM	XXXX	99739 0	NA	NA	NA
CHROMIUM,SED	UG/G- DRY	1029 0	6.48	4.48	4.48

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING · 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
PRS4 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	IS1A PRS01 1	IS2A PRS01 2	IS3A PRS01 3	IS4A PRS01 4	IS5A PRS01 5	IS6A PRS01 6
UNITS	METHOD						
DATE		01/10/86	01/10/86	01/10/86	01/10/86	01/10/86	01/10/86
TIME		11:00	11:15	11:30	11:45	12:00	12:15
BENZENE	98699	<0.05	<0.08	<0.10	<0.08	<0.14	<0.09
UG/G-DRY	10						
BROMODICHLOROMETHANE	98783	<0.11	<0.15	<0.11	<0.17	<0.10	<0.10
UG/G-DRY	10						
BROMOFORM	98784	<0.24	<0.32	<0.24	<0.36	<0.23	<0.23
UG/G-DRY	10						
BROMOMETHANE	98785	<0.22	<0.30	<0.22	<0.34	<0.21	<0.21
UG/G-DRY	10						
CARBON TETRACHLORIDE	98600	<0.19	<0.25	<0.19	<0.28	<0.19	<0.19
UG/G-DRY	10						
CHLOROBENZENE	98681	<0.08	<0.12	<0.08	<0.13	<0.07	<0.07
UG/G-DRY	10						
CHLOROETHANE	98786	<0.28	<0.40	<0.29	<0.45	<0.28	<0.27
UG/G-DRY	10						
2-CHLOROETHYLVINYLETHER	98796	<0.23	<0.32	<0.23	<0.36	<0.22	<0.22
UG/G-DRY	10						
CHLOROFORM	98682	<0.093	<0.131	<0.094	<0.148	<0.091	<0.090
UG/G-DRY	10						
CHLOROMETHANE	98787	<0.24	<0.24	<0.24	<0.28	<0.23	<0.23
UG/G-DRY	10						
DIBROMOCHLOROMETHANE	98788	<0.18	<0.25	<0.18	<0.28	<0.18	<0.17
UG/G-DRY	10						
1,1-DICHLOROETHANE	98683	<0.14	<0.13	<0.14	<0.13	<0.14	<0.13
UG/G-DRY	10						
1,2-DICHLOROETHANE	98684	<0.16	<0.23	<0.16	<0.26	<0.16	<0.16
UG/G-DRY	10						
1,1-DICHLOROETHENE	98789	<0.19	<0.26	<0.19	<0.29	<0.18	<0.18
UG/G-DRY	10						
TRANS-1,2-DICHLOROETHENE	98687	<0.17	<0.24	<0.17	<0.27	<0.17	<0.16
UG/G-DRY	10						
1,2-DICHLOROPROPANE	98790	<0.11	<0.16	<0.12	<0.18	<0.11	<0.11
UG/G-DRY	10						
CIS-1,3-DICHLOROPROPENE	98791	<0.08	<0.11	<0.08	<0.12	<0.08	<0.07
UG/G-DRY	10						
TRANS-1,3-DICHLOROPROPENE	98792	<0.21	<0.29	<0.21	<0.33	<0.21	<0.20
UG/G-DRY	10						
ETHYLBENZENE	98688	<0.17	<0.26	<0.17	<0.30	<0.17	<0.16
UG/G-DRY	10						
METHYLENE CHLORIDE	98689	<0.16	<0.26	<0.16	<0.28	<0.15	<0.15
UG/G-DRY	10						

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
PRS4 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	1S1A PRS01 1	1S2A PRS01 2	1S3A PRS01 3	1S4A PRS01 4	1S5A PRS01 5	1S6A PRS01 6
DATE		01/10/86	01/10/86	01/10/86	01/10/86	01/10/86	01/10/86
TIME		11:00	11:15	11:30	11:45	12:00	12:15
1,1,2,2-TETRACHLOROETHANE UG/G-DRY	98793 10	<0.10	<0.14	<0.10	<0.16	<0.10	<0.10
TETRACHLOROETHENE UG/G-DRY	98690 10	<0.26	<0.38	<0.26	<0.43	<0.26	<0.25
TOLUENE UG/G-DRY	98691 10	<0.14	<0.13	<0.14	<0.14	<0.14	<0.13
1,1,1-TRICHLOROETHANE UG/G-DRY	98692 10	<0.18	<0.24	<0.18	<0.28	<0.17	<0.17
1,1,2-TRICHLOROETHANE UG/G-DRY	98693 10	<0.19	<0.27	<0.19	<0.31	<0.19	<0.18
TRICHLOROETHENE UG/G-DRY	98694 10	<0.18	<0.26	<0.18	<0.29	<0.18	<0.18
TRICHLOROFLUOROMETHANE UG/G-DRY	98794 10	<0.16	<0.21	<0.16	<0.24	<0.16	<0.15
VINYL CHLORIDE UG/G-DRY	98795 10	<0.17	<0.24	<0.17	<0.28	<0.17	<0.16
PH,SOIL	99218 0	6.8	6.8	6.7	6.7	6.8	7.5
1,2-DIBROMOETHANE (EDB) MG/KG-DRY	98798 0	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002
M-XYLENE MG/KG-DRY	98799 10	<0.13	<0.20	<0.13	<0.23	<0.13	<0.12
O,P-XYLENE MG/KG-DRY	98800 10	<0.13	<0.21	<0.13	<0.23	<0.13	<0.13
OIL&GR,IR,SED UG/G- DRY	561 0	189	201	226	195	180	88
LEAD,SED UG/G-DRY	1052 0	<3.21	<2.59	<3.50	<3.50	<3.22	<3.13
MOISTURE %WET WT	70320 0	14.6	8.2	16.1	16.0	12.2	9.8
METHYL ETHYL KETONE UG/G-DRY	98801 10	<7.4	<4.9	<6.1	<3.5	<8.3	<6.1
MIBK UG/G-DRY	98696 10	<0.23	<0.33	<0.24	<0.36	<0.31	<0.22
DICHLOROBENZENE,TOTAL UG/G-DRY	98803 10	<0.12	<0.19	<0.12	<0.22	<0.12	<0.11
CHROMIUM XXXX	99739 0	NA	NA	NA	NA	NA	NA
CHROMIUM,SED UG/G- DRY	1029 0	26.3	18.5	26.8	24.8	25.0	25.2

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
PRW3 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	2SW1 PRSW1	2SW2 PRSW1	2SW3 PRSW1	2SW4 PRSW1	2SW5 PRSW1
UNITS	METHOD	1	2	3	4	5
DATE		01/15/86	01/15/86	01/15/86	01/15/86	01/15/86
TIME		09:30	10:00	10:30	11:00	11:30
PH,FIELD	400	7.72	7.81	7.81	7.75	7.47
STD UNITS	0					
BENZENE	34030	<0.26	<0.30	<0.27	<0.29	<0.29
UG/L	10					
BROMODICHLOROMETHANE	32101	<0.58	<0.66	<0.60	<0.63	<0.64
UG/L	10					
BROMOFORM	32104	<1.2	<1.3	<1.2	<1.3	<1.3
UG/L	10					
BROMOMETHANE	34413	<1.1	<1.3	<1.1	<1.2	<1.2
UG/L	10					
CARBON TETRACHLORIDE	32102	<0.90	<1.0	<0.93	<0.99	<1.0
UG/L	10					
CHLOROBENZENE	34301	<0.41	<0.47	<0.43	<0.45	<0.46
UG/L	10					
CHLOROETHANE	34311	<1.5	<1.7	<1.5	<1.6	<1.6
UG/L	10					
2-CHL'ETH'VINYLETHER	34576	<1.0	<1.2	<1.1	<1.1	<1.2
UG/L	10					
CHLOROFORM	32106	<0.47	<0.53	<0.48	<0.51	<0.52
UG/L	10					
CHLOROMETHANE	34418	<3.5	<4.0	<3.6	<3.8	<3.9
UG/L	10					
DIBROMOCHLOROMETHANE	32105	<0.832	<0.950	<0.861	<0.910	<0.923
UG/L	10					
1,1-DICHLOROETHANE	34496	<0.32	<0.32	<0.32	<0.32	<0.32
UG/L	10					
1,2-DICHLOROETHANE	34531	<0.86	<0.98	<0.89	<0.94	<0.95
UG/L	10					
1,1-DICHLOROETHYLENE	34501	<0.95	<1.1	<0.99	<1.0	<1.1
UG/L	10					
T-1,2-DICHLOROETHENE	34546	<0.95	<1.1	<0.99	<1.0	<1.1
UG/L	10					
1,2-DICHLOROPROPANE	34541	<0.54	<0.62	<0.56	<0.59	<0.60
UG/L	10					
CIS-1,3-DICH'PROPENE	34704	<0.39	<0.45	<0.41	<0.43	<0.44
UG/L	10					
T-1,3-DICHL'PROPENE	34699	<1.1	<1.3	<1.2	<1.2	<1.2
UG/L	10					
ETHYLBENZENE	34371	<1.0	<1.2	<1.1	<1.1	<1.1
UG/L	10					

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 2

PROJECT NUMBER 85275 3000
FIELD GROUP PRSWI
PRW3

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	2SW1	2SW2	2SW3	2SW4	2SW5
		PRSWI	PRSWI	PRSWI	PRSWI	PRSWI
UNITS	METHOD	1	2	3	4	5
DATE		01/15/86	01/15/86	01/15/86	01/15/86	01/15/86
TIME		09:30	10:00	10:30	11:00	11:30
METHYLENE CHLORIDE	34423	<0.60	<0.79	<0.60	<0.76	<0.60
UG/L	10					
1,1,2,2-TE'CH'ETHANE	34516	<0.50	<0.57	<0.52	<0.55	<0.55
UG/L	10					
TOLUENE	34010	<0.38	<0.38	<0.50	<0.38	<0.50
UG/L	10					
1,1,1-TRICHL'ETHANE	34506	<0.98	<1.1	<1.0	<1.1	<1.1
UG/L	10					
1,1,2-TRICHL'ETHANE	34511	<0.92	<1.1	<0.96	<1.0	<1.0
UG/L	10					
TRICHLOROETHENE	39180	<0.95	<1.1	<0.98	<1.0	<1.1
UG/L	10					
TRICHL'FLUOROMETHANE	34488	<0.83	<0.91	<0.83	<0.88	<0.89
UG/L	10					
VINYL CHLORIDE	39175	<0.97	<1.1	<1.0	<1.1	<1.1
UG/L	10					
M-XYLENE	98553	<0.73	<0.83	<0.75	<0.80	<0.81
UG/L	10					
LEAD,TOTAL	1051	<24.0	<24.0	<24.0	<24.0	<24.0
UG/L	0					
METHYL ETHYL KETONE	81595	<4.0	<4.6	<4.2	<4.4	<4.5
UG/L	10					
METHYL ISOBUT'KETONE	81596	<0.47	<0.60	<0.47	<0.47	<0.60
UG/L	10					
O-AND/OR-P XYLENE	98554	<0.76	<0.87	<0.79	<0.83	<0.85
UG/L	10					
DICHLOROBENZENE,T.	81524	<0.6	<0.7	<0.6	<0.7	<0.7
UG/L	10					
TETRACHLOROETHENE	34475	<1.4	<1.6	<1.4	<1.5	<1.5
UG/L	10					
CHROMIUM,(+6)	1032	<20.0	<20.0	<20.0	<20.0	<20.0
UG/L	0					
CHROMIUM,TOTAL	1034	3.00	4.00	3.00	3.00	3.00
UG/L	0					

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000
FIELD GROUP PRSE1
PRS5

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	2SE1 PRSE1 4	2SE2 PRSE1 5	2SE3 PRSE1 6	2SE4 PRSE1 7	2SE5 PRSE1 8
DATE			01/15/86	01/15/86	01/15/86	01/15/86	01/15/86
TIME			09:30	10:00	10:30	11:00	11:30
BENZENE		98699	<0.09	<0.11	<0.12	<0.07	<0.20
	UG/G-DRY	10					
BROMODICHLOROMETHANE		98783	<0.19	<0.22	<0.24	<0.14	<0.41
	UG/G-DRY	10					
BROMOFORM		98784	<0.40	<0.47	<0.52	<0.30	<0.88
	UG/G-DRY	10					
BROMOMETHANE		98785	<0.33	<0.38	<0.43	<0.25	<0.73
	UG/G-DRY	10					
CARBON TETRACHLORIDE		98680	<0.33	<0.39	<0.43	<0.25	<0.73
	UG/G-DRY	10					
CHLOROBENZENE		98681	<0.14	<0.16	<0.18	<0.11	<0.31
	UG/G-DRY	10					
CHLOROETHANE		98786	<0.49	<0.57	<0.63	<0.37	<1.1
	UG/G-DRY	10					
2-CHLOROETHYLVINYLET		98796	<0.44	<0.52	<0.57	<0.34	<0.98
HER	UG/G-DRY	10					
CHLOROFORM		98682	<0.163	<0.190	<0.212	<0.124	<0.361
	UG/G-DRY	10					
CHLOROMETHANE		98787	<0.45	<0.53	<0.59	<0.34	<1.0
	UG/G-DRY	10					
DIBROMOCHLOROMETHANE		98788	<0.31	<0.36	<0.40	<0.23	<0.68
	UG/G-DRY	10					
1,1-DICHLOROETHANE		98683	<0.15	<0.17	<0.20	<0.11	<0.33
	UG/G-DRY	10					
1,2-DICHLOROETHANE		98684	<0.30	<0.35	<0.39	<0.23	<0.67
	UG/G-DRY	10					
1,1-DICHLOROETHENE		98789	<0.32	<0.37	<0.41	<0.24	<0.70
	UG/G-DRY	10					
TRANS-1,2-DICHLOROET		98687	<0.28	<0.33	<0.37	<0.22	<0.63
ENE	UG/G-DRY	10					
1,2-DICHLOROPROPANE		98790	<0.21	<0.24	<0.27	<0.16	<0.46
	UG/G-DRY	10					
CIS-1,3-DICHLOROPROP		98791	<0.14	<0.17	<0.19	<0.11	<0.32
ENE	UG/G-DRY	10					
TRANS-1,3-DICHLOROPR		98792	<0.40	<0.46	<0.51	<0.30	<0.87
OPENE	UG/G-DRY	10					
ETHYLBENZENE		98688	<0.31	<0.36	<0.40	<0.23	<0.68
	UG/G-DRY	10					
METHYLENE CHLORIDE		98689	<0.22	<0.64	<0.27	<0.29	<1.1
	UG/G-DRY	10					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS5 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	2SE1 PRSE1 4	2SE2 PRSE1 5	2SE3 PRSE1 6	2SE4 PRSE1 7	2SE5 PRSE1 8
DATE			01/15/86	01/15/86	01/15/86	01/15/86	01/15/86
TIME			09:30	10:00	10:30	11:00	11:30
1,1,2,2-TETRACHLOROE THANE	UG/G-DRY	98793 10	<0.19	<0.22	<0.24	<0.14	<0.42
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.45	<0.52	<0.58	<0.34	<0.99
TOLUENE	UG/G-DRY	98691 10	<0.15	<0.17	<0.18	<0.11	<0.31
1,1,1-TRICHLOROETHAN E	UG/G-DRY	98692 10	<0.30	<0.35	<0.38	<0.23	<0.66
1,1,2-TRICHLOROETHAN E	UG/G-DRY	98693 10	<0.34	<0.39	<0.44	<0.26	<0.75
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.32	<0.37	<0.41	<0.24	<0.70
TRICHLOROFLUOROMETHA NE	UG/G-DRY	98794 10	<0.29	<0.34	<0.38	<0.22	<0.65
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.33	<0.38	<0.42	<0.25	<0.72
PH,SOIL		99218 0	7.8	7.7	7.6	7.3	7.6
M-XYLENE	MG/KG-DRY	98799 10	<0.23	<0.27	<0.30	<0.18	<0.51
O,P-XYLENE	MG/KG-DRY	98800 10	<0.24	<0.28	<0.31	<0.18	<0.52
LEAD,SED	UG/G-DRY	1052 0	<2.99	<4.27	53.2	16.9	63.9
MOISTURE	%WET WT	70320 0	30.0	37.9	42.8	6.4	67.0
METHYL ETHYL KETONE	UG/G-DRY	98801 10	<2.2	<2.6	<2.8	<1.7	<4.9
MIBK	UG/G-DRY	98696 10	<0.35	<0.40	<0.44	<0.26	<0.75
DICHLOROBENZENE,TOTA L	UG/G-DRY	98803 10	<0.20	<0.23	<0.26	<0.15	<0.44
CHROMIUM	XXXX	99739 0	NA	NA	NA	NA	NA
CHROMIUM,SED	UG/G- DRY	1029 0	12.6	32.9	88.4	5.28	16.2

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
PRS5 LAB COORDINATOR LISA BARE

PARAMETERS	UNITS	STORET # METHOD	SAMPLE ID/# 2S1N PRS01 7	2S2N PRS01 8	2S3N PRS01 9	2S4N PRS01 10	2S5N PRS01 11	2S6N PRS01 12	2S7N PRS01 13	2S8N PRS01 14
DATE			01/15/86	01/15/86	01/15/86	01/15/86	01/15/86	01/15/86	01/15/86	01/15/86
TIME			09:30	10:00	10:30	11:00	11:30	12:00	12:30	13:00
BENZENE	UG/G-DRY	98699 10	<0.07	<0.07	<0.06	<0.06	<0.06	<0.05	<0.06	<0.08
BROMODICHLOROMETHANE	UG/G-DRY	98783 10	<0.14	<0.14	<0.12	<0.13	<0.13	<0.11	<0.12	<0.16
BROMOFORM	UG/G-DRY	98784 10	<0.31	<0.32	<0.27	<0.28	<0.29	<0.25	<0.28	<0.34
BROMOMETHANE	UG/G-DRY	98785 10	<0.28	<0.29	<0.25	<0.26	<0.27	<0.22	<0.25	<0.28
CARBON TETRACHLORIDE	UG/G-DRY	98680 10	<0.25	<0.25	<0.22	<0.22	<0.23	<0.20	<0.22	<0.28
CHLOROBENZENE	UG/G-DRY	98681 10	<0.11	<0.11	<0.09	<0.10	<0.10	<0.09	<0.10	<0.12
CHLOROETHANE	UG/G-DRY	98786 10	<0.39	<0.40	<0.34	<0.36	<0.37	<0.31	<0.35	<0.41
2-CHLOROETHYLVINYLETHER	UG/G-DRY	98796 10	<0.31	<0.31	<0.27	<0.28	<0.29	<0.24	<0.28	<0.37
CHLOROFORM	UG/G-DRY	98682 10	<0.125	<0.127	<0.109	<0.112	<0.117	<0.098	<0.111	<0.138
CHLOROMETHANE	UG/G-DRY	98787 10	<0.29	<0.30	<0.26	<0.27	<0.28	<0.23	<0.26	<0.38
DIBROMOCHLOROMETHANE	UG/G-DRY	98788 10	<0.24	<0.24	<0.21	<0.21	<0.22	<0.19	<0.21	<0.26
1,1-DICHLOROETHANE	UG/G-DRY	98683 10	<0.10	<0.11	<0.09	<0.09	<0.09	<0.08	<0.09	<0.13
1,2-DICHLOROETHANE	UG/G-DRY	98684 10	<0.22	<0.22	<0.19	<0.20	<0.20	<0.17	<0.19	<0.26
1,1-DICHLOROETHENE	UG/G-DRY	98789 10	<0.25	<0.25	<0.22	<0.22	<0.23	<0.19	<0.22	<0.27
TRANS-1,2-DICHLOROETENE	UG/G-DRY	98687 10	<0.22	<0.22	<0.19	<0.19	<0.20	<0.17	<0.19	<0.24
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.16	<0.16	<0.14	<0.14	<0.15	<0.12	<0.14	<0.18
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.10	<0.11	<0.09	<0.09	<0.10	<0.08	<0.09	<0.12
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.29	<0.29	<0.25	<0.26	<0.27	<0.23	<0.26	<0.33
ETHYLBENZENE	UG/G-DRY	98688 10	<0.24	<0.24	<0.21	<0.21	<0.22	<0.19	<0.21	<0.26
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.12	<0.56	<2.8	<0.11	<0.64	<0.53	<0.62	<0.19

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
PRS5 LAB COORDINATOR LISA BARE

PARAMETERS	UNITS	STORET # METHOD	2S1N PRS01 7	2S2N PRS01 8	2S3N PRS01 9	2S4N PRS01 10	2S5N PRS01 11	2S6N PRS01 12	2S7N PRS01 13	2S8N PRS01 14
			SAMPLE ID/#							
DATE			01/15/86	01/15/86	01/15/86	01/15/86	01/15/86	01/15/86	01/15/86	01/15/86
TIME			09:30	10:00	10:30	11:00	11:30	12:00	12:30	13:00
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.13	<0.13	<0.11	<0.12	<0.12	<0.10	<0.12	<0.16
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.37	<0.38	<0.33	<0.34	<0.35	<0.29	<0.33	<0.38
TOLUENE	UG/G-DRY	98691 10	<0.07	<0.07	<0.06	<0.06	<0.06	<0.05	<0.06	<0.13
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.23	<0.23	<0.20	<0.20	<0.21	<0.18	<0.20	<0.25
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.24	<0.25	<0.21	<0.22	<0.23	<0.19	<0.22	<0.28
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.25	<0.25	<0.22	<0.22	<0.23	<0.19	<0.22	<0.27
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.21	<0.22	<0.18	<0.19	<0.20	<0.17	<0.19	<0.25
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.27	<0.28	<0.24	<0.25	<0.25	<0.21	<0.24	<0.28
PH,SOIL		99218 0	8.3	7.9	8.5	8.4	8.2	8.2	8.2	8.4
M-XYLENE	MG/KG-DRY	98799 10	<0.18	<0.18	<0.16	<0.16	<0.17	<0.14	<0.16	<0.20
O,P-XYLENE	MG/KG-DRY	98800 10	<0.18	<0.19	<0.16	<0.17	<0.17	<0.15	<0.16	<0.20
LEAD,SED	UG/G-DRY	1052 0	232	<3.86	10.2	345	<3.53	6.42	<3.30	<2.97
MOISTURE	%WET WT	70320 0	24.2	28.0	17.7	15.5	16.0	5.8	13.5	18.1
METHYL ETHYL KETONE	UG/G-DRY	98801 10	<1.5	<1.5	<1.1	<0.24	<1.4	<1.2	<1.3	<1.9
MIBK	UG/G-DRY	98696 10	<0.20	<0.21	<0.19	<0.18	<0.18	<0.16	<0.18	<0.29
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.16	<0.16	<0.14	<0.14	<0.15	<0.12	<0.14	<0.17
CHROMIUM	XXXX	99739 0	NA	NA	NA	NA	NA	NA	NA	NA
CHROMIUM,SED	UG/G- DRY	1029 0	9.00	3.73	46.4	20.4	33.6	36.9	48.2	24.2

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	5GW1	5GW2	5GW3	5GW4	5GW5
UNITS	METHOD	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1
		5	6	7	8	9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
1,2-DIBR'ETHANE(EDB)	77651	<0.020	<0.020	<0.020	<0.020	<0.020
UG/L	0					
PH,FIELD	400	6.93	7.70	6.46	6.70	6.60
STD UNITS	0					
CHROMIUM,(+6)	1032	<20.0	<20.0	22.0	<20.0	34.6
UG/L	0					
METHYL ETHYL KETONE	81595	<4.7	<4.7	<4.7	<4.7	<4.2
UG/L	10					
METHYL ISOBUT'KETONE	81596	<0.60	<0.60	<0.60	<0.60	<0.61
UG/L	10					
BENZENE	34030	<0.23	<0.23	<0.25	<0.24	<0.26
UG/L	10					
BROMODICHLOROMETHANE	32101	<0.49	<0.49	<0.52	<0.51	<0.54
UG/L	10					
BROMOFORM	32104	<1.2	<1.2	<1.2	<1.2	<1.2
UG/L	10					
BROMOMETHANE	34413	<1.1	<1.1	<1.1	<1.1	<1.2
UG/L	10					
CARBON TETRACHLORIDE	32102	<0.87	<0.87	<0.92	<0.91	<0.93
UG/L	10					
CHLOROBENZENE	34301	<0.40	<0.40	<0.43	<0.42	<0.45
UG/L	10					
CHLOROETHANE	34311	<1.4	<1.4	<1.5	<1.4	<1.5
UG/L	10					
2-CHL'ETH'VINYLETHER	34576	<1.0	<1.0	<1.1	<1.1	<1.1
UG/L	10					
CHLOROFORM	32106	0.54	<0.43	<0.46	<0.46	<0.48
UG/L	10					
CHLOROMETHANE	34418	<1.0	<1.0	<1.1	<1.1	<1.6
UG/L	10					
DIBROMOCHLOROMETHANE	32105	<0.879	<0.879	<0.930	<0.923	<0.970
UG/L	10					
1,1-DICHLOROETHANE	34496	<0.35	<0.35	<0.40	<0.40	<0.42
UG/L	10					
1,2-DICHLOROETHANE	34531	<0.75	<0.75	<0.79	<0.79	<0.81
UG/L	10					
1,1-DICHLOROETHYLENE	34501	<0.98	<0.98	<1.0	<1.0	<1.1
UG/L	10					
T-1,2-DICHLOROETHENE	34546	<0.84	<0.84	<0.88	<0.88	<0.92
UG/L	10					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000
FIELD GROUP PRGWI
NAVMXW

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5GW1 PRGWI 5	5GW2 PRGWI 6	5GW3 PRGWI 7	5GW4 PRGWI 8	5GW5 PRGWI 9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
1,2-DICHLOROPROPANE	34541	<0.51	<0.51	<0.54	<0.54	<0.57
UG/L	10					
CIS-1,3-DICH'PROPENE	34704	<0.36	<0.36	<0.38	<0.38	<0.40
UG/L	10					
T-1,3-DICHL'PROPENE	34699	<1.0	<1.0	<1.1	<1.1	<1.1
UG/L	10					
ETHYLBENZENE	34371	<0.83	<0.83	<0.88	<0.87	<0.92
UG/L	10					
METHYLENE CHLORIDE	34423	<0.60	<0.60	<0.60	<0.60	<0.65
UG/L	10					
1,1,2,2-TE'CH'ETHANE	34516	1.1	<0.49	<0.52	<0.51	<0.51
UG/L	10					
TOLUENE	34010	<0.60	<0.35	<0.35	<0.36	<0.40
UG/L	10					
1,1,1-TRICHL'ETHANE	34506	<0.82	<0.82	<0.87	<0.86	<0.86
UG/L	10					
1,1,2-TRICHL'ETHANE	34511	<0.93	<0.93	<0.98	<0.97	<1.00
UG/L	10					
TRICHLOROETHENE	39180	<0.95	<0.95	<1.0	<1.0	<1.1
UG/L	10					
TRICHL'FLUOROMETHANE	34488	<0.77	<0.77	<0.82	<0.81	<0.87
UG/L	10					
VINYL CHLORIDE	39175	<0.94	<0.94	<0.99	<0.98	<1.1
UG/L	10					
DICHLOROBENZENE,T.	81524	<0.6	<0.6	<0.7	<0.6	<0.7
UG/L	10					
4-CHL'-3-METH'PHENOL	34452	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10					
2-CHLOROPHENOL	34586	<1.7	<1.7	<1.7	<1.7	<1.7
UG/L	10					
2,4-DICHLOROPHENOL	34601	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10					
2,4-DIMETHYLPHENOL	34606	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10					
2,4-DINITROPHENOL	34616	<30	<30	<30	<30	<30
UG/L	10					
2-MET'-4,6-DN'PHENOL	34657	<5.0	<5.0	<5.0	<5.0	<5.0
UG/L	10					
2-NITROPHENOL	34591	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000
FIELD GROUP PRGW1
NAVMXW

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5GW1 PRGW1 5	5GW2 PRGW1 6	5GW3 PRGW1 7	5GW4 PRGW1 8	5GW5 PRGW1 9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
4-NITROPHENOL	34646	<5.0	<5.0	<5.0	<5.0	<5.0
UG/L	10					
PENTACHLOROPHENOL	39032	22	11	12	25	<10
UG/L	10					
PHENOL	34694	<1.3	<1.3	<1.3	<1.3	<1.3
UG/L	10					
2,4,6-TRICHL'PHENOL	34621	<1.8	<1.8	<1.8	<1.8	<1.8
UG/L	10					
ACENAPHTHENE	34205	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					
ACENAPHTHYLENE	34200	<1	<1	<1	<1	<1
UG/L	0					
ANTHRACENE	34220	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					
BENZO(A)ANTHRACENE	34526	<1	<1	<1	<1	<1
UG/L	0					
BENZO(B)FLUORANTHENE	34230	<1.50	<1.50	<1.50	<1.50	<1.50
UG/L	0					
BENZO(K)FLUORANTHENE	34242	<2	<2	<2	<2	<2
UG/L	0					
BENZO(A)PYRENE	34247	<2	<2	<2	<2	<2
UG/L	0					
BENZO(GHI)PERYLENE	34521	<2	<2	<2	<2	<2
UG/L	0					
BUTYL BENZ'PHTHALATE	34292	<1	<1	<1	<1	<1
UG/L	0					
BIS(2-CHL'ETH')ETHER	34273	<1	<1	<1	<1	<1
UG/L	0					
BIS(2-CHL'ETHOX)MTHN	34278	<1	<1	<1	<1	<1
UG/L	0					
BIS(2-ETH'HEX')PHTH.	39100	*TO.7	*TO.4	<1	1	2
UG/L	0					
BIS(2-CHL'ISOPR)ETHR	34283	<1	<1	<1	<1	<1
UG/L	0					
4-BRO'PHEN'PHEN'ETHR	34636	<1	<1	<1	<1	<1
UG/L	0					
2-CHLORONAPHTHALENE	34581	<1	<1	<1	<1	<1
UG/L	0					
4-CHL'PHEN'PHEN'ETHR	34641	<1	<1	<1	<1	<1
UG/L	0					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000
FIELD GROUP PRGW1
NAVMXW

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	SGW1 PRGW1 5	SGW2 PRGW1 6	SGW3 PRGW1 7	SGW4 PRGW1 8	SGW5 PRGW1 9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
CHRYSENE	34320	<1	<1	<1	<1	<1
UG/L	0					
DIBEN'(A,H)ANTH'CENE	34556	<2	<2	<2	<2	<2
UG/L	0					
DI-N-BUTYLPHTHALATE	39110	<1	<1	<1	<1	<1
UG/L	0					
1,3,DICHLOROBENZENE	34566	<1	<1	<1	<1	<1
UG/L	0					
1,2-DICHLOROBENZENE	34536	<1	<1	<1	<1	<1
UG/L	0					
1,4-DICHLOROBENZENE	34571	<1	<1	<1	<1	<1
UG/L	0					
3,3'-DICHL'BENZIDINE	34631	<2	<2	<2	<2	<2
UG/L	0					
DIETHYLPHTHALATE	34336	<1	<1	<1	<1	<1
UG/L	0					
DIMETHYLPTHALATE	34341	<1	<1	<1	<1	<1
UG/L	0					
2,4-DINITROTOLUENE	34611	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0					
2,6-DINITROTOLUENE	34626	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0					
DI-N-OCTYL PHTHALATE	34596	<1	<1	<1	<1	<1
UG/L	0					
FLUORANTHENE	34376	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					
FLUORENE	34381	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					
HEXACH'CYC'PEN'DIENE	34386	<2	<2	<2	<2	<2
UG/L	0					
HEXACHLOROBENZENE	39700	<1	<1	<1	<1	<1
UG/L	0					
HEXACHLOROBUTADIENE	34391	<1	<1	<1	<1	<1
UG/L	0					
HEXACHLOROETHANE	34396	<2	<2	<2	<2	<2
UG/L	0					
INDENO(1,2,3-CD)PYRN	34403	<2	<2	<2	<2	<2
UG/L	0					
ISOPHORONE	34400	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000
FIELD GROUP PRGWI
NAVMXW

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5GW1 PRGWI 5	5GW2 PRGWI 6	5GW3 PRGWI 7	5GW4 PRGWI 8	5GW5 PRGWI 9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
NAPHTHALENE	34696	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					
NITROBENZENE	34447	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0					
N-NITROSODIPRO'AMINE	34428	<1	<1	<1	<1	<1
UG/L	0					
N-NITROSODIMET'AMINE	34438	<1	<1	<1	<1	<1
UG/L	0					
N-NITROSODIPHE'AMINE	34433	<1	<1	<1	<1	<1
UG/L	0					
PHENANTHRENE	34461	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0					
PYRENE	34469	<1	<1	<1	<1	<1
UG/L	0					
1,2,4-TRICHL'BENZENE	34551	<1	<1	<1	<1	<1
UG/L	0					
ALDRIN	39330	0.045	<0.013	<0.013	<0.013	<0.014
UG/L	0					
BHC,A	39337	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
BHC,B	39338	<0.013	0.020	<0.013	<0.013	<0.014
UG/L	0					
BHC-D	34259	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
BHC,G(LINDANE)	39340	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
CHLORDANE	39350	<1.25	<1.25	<1.25	<1.25	<1.36
UG/L	0					
DDD,PP'	39310	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
DDE,PP'	39320	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
DDT,PP'	39300	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
DIELDRIN	39380	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
ENDOSULFAN,A	34361	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
ENDOSULFAN,B	34356	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000
FIELD GROUP PRGWI
NAVMXW

PROJECT NAME PUERTO RICO*CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5GW1 PRGWI 5	5GW2 PRGWI 6	5GW3 PRGWI 7	5GW4 PRGWI 8	5GW5 PRGWI 9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
ENDOSULFAN SULFATE	34351	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
ENDRIN	39390	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
ENDRIN ALDEHYDE	34366	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
HEPTACHLOR	39410	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
HEPTACHLOR EPOXIDE	39420	<0.013	<0.013	<0.013	<0.013	<0.014
UG/L	0					
TOXAPHENE	39400	<1.56	<1.56	<1.56	<1.56	<1.70
UG/L	0					
PCB-1016	34671	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
PCB-1221	39488	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
PCB-1232	39492	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
PCB-1242	39496	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
PCB 1248	39500	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
PCB-1254	39504	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
PCB-1260	39508	<1.50	<1.50	<1.50	<1.50	<1.63
UG/L	0					
ANTIMONY,TOTAL	1097	<24.0	<24.0	<24.0	<24.0	<18.0
UG/L	0					
ARSENIC,TOTAL	1002	20.5	<15.0	93.4	88.6	83.9
UG/L	0					
BERYLLIUM,T,	1012	<3.00	<3.00	<3.00	5.06	<3.00
UG/L	0					
CADMIUM,TOTAL	1027	<3.00	<3.00	<3.00	<3.00	<3.00
UG/L	0					
CHROMIUM,TOTAL	1034	3.25	6.05	18.1	26.9	28.4
UG/L	0					
COPPER,TOTAL	1042	23.9	58.2	1850	113	55.8
UG/L	0					
LEAD,TOTAL	1051	<24.0	<24.0	<24.0	<24.0	<21.0
UG/L	0					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
NAVMXH LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	SGW1 PRGW1 5	SGW2 PRGW1 6	SGW3 PRGW1 7	SGW4 PRGW1 8	SGW5 PRGW1 9
DATE		03/06/86	03/06/86	03/06/86	03/06/86	03/12/86
TIME		11:30	11:55	11:20	12:15	08:00
MERCURY,TOTAL	71900	<0.500	<0.500	<0.500	<0.500	<0.500
UG/L	0					
NICKEL,T,	1067	<3.00	4.32	46.3	48.0	12.6
UG/L	0					
SELENIUM,TOTAL	1147	<21.0	<21.0	<21.0	<21.0	<21.0
UG/L	0					
SILVER,TOTAL	1077	<3.00	<3.00	<3.00	<3.00	<3.00
UG/L	0					
THALLIUM,TOTAL	1059	10.6	9.64	4310	3860	3450
UG/L	0					
ZINC,TOTAL	1092	33.2	55.1	124	4580	76.3
UG/L	0					
M-XYLENE	98553	<0.67	<0.67	<0.70	<0.70	<0.70
UG/L	10					
O-AND/OR-P XYLENE	98554	<0.68	<0.68	<0.72	<0.72	<0.71
UG/L	10					
TETRACHLOROETHENE	34475	<1.4	<1.4	<1.5	<1.5	<1.5
UG/L	10					

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5SW1 PRSWI 6	5SW1 PRSWI 101	5SW2 PRSWI 7	5SW2 PRSWI 102	5SW3 PRSWI 8	5SW3 PRSWI 103	5SW4 PRSWI 9	5SW4 PRSWI 104	5SW5 PRSWI 10	5SW5 PRSWI 105
		SAMPLE ID/#									
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
1,2-DIBR'ETHANE(EDB)	77651	NA	<0.020	NA	<0.020	NA	<0.020	NA	<0.020	NA	<0.020
UG/L	0										
PH,FIELD	400	6.93	NRQ	8.00	NRQ	8.23	NRQ	8.07	NRQ	8.24	NRQ
STD UNITS	0										
CHROMIUM,(+6)	1032	<20.0	NRQ	31.9	NRQ	<20.0	NRQ	<20.0	NRQ	<20.0	NRQ
UG/L	0										
METHYL ETHYL KETONE	81595	<14	NRQ	<14	NRQ	<17	NRQ	<13	NRQ	<14	NRQ
UG/L	10										
METHYL ISOBUT'KETONE	81596	<1.9	NRQ	<1.8	NRQ	<2.1	NRQ	<2.1	NRQ	<1.9	NRQ
UG/L	10										
BENZENE	34030	<0.98	NRQ	<0.87	NRQ	<0.29	NRQ	<1.1	NRQ	<0.98	NRQ
UG/L	10										
BROMODICHLOROMETHANE	32101	<0.29	NRQ	<0.29	NRQ	<0.33	NRQ	<0.33	NRQ	<0.30	NRQ
UG/L	10										
BROMOFORM	32104	<0.72	NRQ	<0.70	NRQ	<0.81	NRQ	<0.80	NRQ	<0.74	NRQ
UG/L	10										
BROMOMETHANE	34413	<0.53	NRQ	<0.52	NRQ	<0.60	NRQ	<0.60	NRQ	<0.55	NRQ
UG/L	10										
CARBON TETRACHLORIDE	32102	<0.25	NRQ	<0.25	NRQ	<0.29	NRQ	<0.28	NRQ	<0.26	NRQ
UG/L	10										
CHLOROBENZENE	34301	<0.22	NRQ	<0.22	NRQ	<0.25	NRQ	<0.25	NRQ	<0.23	NRQ
UG/L	10										
CHLOROETHANE	34311	<1.3	NRQ	<1.2	NRQ	<1.4	NRQ	<1.4	NRQ	<1.3	NRQ
UG/L	10										
2-CHL'ETH'VINYLETHER	34576	<1.4	NRQ	<1.4	NRQ	<1.6	NRQ	<1.6	NRQ	<1.5	NRQ
UG/L	10										
CHLOROFORM	32106	<0.27	NRQ	<0.26	NRQ	<0.30	NRQ	<0.30	NRQ	<0.28	NRQ
UG/L	10										
CHLOROMETHANE	34418	<0.75	NRQ	<0.73	NRQ	<0.84	NRQ	<0.84	NRQ	<0.77	NRQ
UG/L	10										
DIBROMOCHLOROMETHANE	32105	<0.488	NRQ	<0.476	NRQ	<0.551	NRQ	<0.546	NRQ	<0.505	NRQ
UG/L	10										
1,1-DICHLOROETHANE'	34496	<0.44	NRQ	<0.43	NRQ	<0.50	NRQ	<0.50	NRQ	<0.46	NRQ
UG/L	10										
1,2-DICHLOROETHANE	34531	<0.34	NRQ	<0.34	NRQ	<0.39	NRQ	<0.38	NRQ	<0.36	NRQ
UG/L	10										
1,1-DICHLOROETHYLENE	34501	<0.80	NRQ	<0.79	NRQ	<0.91	NRQ	<0.90	NRQ	<0.83	NRQ
UG/L	10										
T-1,2-DICHLOROETHENE	34546	<0.70	NRQ	<0.69	NRQ	<0.80	NRQ	<0.79	NRQ	<0.73	NRQ
UG/L	10										

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 2

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSH1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5SH1 PRSH1 6	5SH1 PRSH1 101	5SH2 PRSH1 7	5SH2 PRSH1 102	5SH3 PRSH1 8	5SH3 PRSH1 103	5SH4 PRSH1 9	5SH4 PRSH1 104	5SH5 PRSH1 10	5SH5 PRSH1 105
		SAMPLE ID/#									
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
1,2-DICHLOROPROPANE	34541	<0.90	NRQ	<0.88	NRQ	<1.0	NRQ	<1.0	NRQ	<0.93	NRQ
UG/L	10										
CIS-1,3-DICH'PROPENE	34704	<0.97	NRQ	<0.29	NRQ	<0.34	NRQ	<0.34	NRQ	<0.31	NRQ
UG/L	10										
T-1,3-DICHL'PROPENE	34699	<0.30	NRQ	<0.30	NRQ	<0.34	NRQ	<0.34	NRQ	<0.31	NRQ
UG/L	10										
ETHYLBENZENE	34371	<0.46	NRQ	<0.45	NRQ	<0.52	NRQ	<0.51	NRQ	<0.47	NRQ
UG/L	10										
METHYLENE CHLORIDE	34423	<2.4	NRQ	<2.9	NRQ	<3.2	NRQ	<2.5	NRQ	<2.1	NRQ
UG/L	10										
1,1,2,2-TE'CH'ETHANE	34516	<0.91	NRQ	<0.89	NRQ	<1.0	NRQ	<1.0	NRQ	<0.95	NRQ
UG/L	10										
TOLUENE	34010	<0.32	NRQ	<0.32	NRQ	<0.37	NRQ	<0.36	NRQ	<0.34	NRQ
UG/L	10										
1,1,1-TRICHL'ETHANE	34506	<0.26	NRQ	<0.26	NRQ	<0.30	NRQ	<0.29	NRQ	<0.27	NRQ
UG/L	10										
1,1,2-TRICHL'ETHANE	34511	<0.76	NRQ	<0.74	NRQ	<0.86	NRQ	<0.85	NRQ	<0.79	NRQ
UG/L	10										
TRICHLOROETHENE	39180	<0.44	NRQ	<0.43	NRQ	<0.49	NRQ	<0.49	NRQ	<0.45	NRQ
UG/L	10										
TRICHL'FLUOROMETHANE	34488	<0.93	NRQ	<0.91	NRQ	<1.1	NRQ	<1.0	NRQ	<0.97	NRQ
UG/L	10										
VINYL CHLORIDE	39175	<0.54	NRQ	<0.53	NRQ	<0.62	NRQ	<0.61	NRQ	<0.56	NRQ
UG/L	10										
DICHLOROBENZENE,T.	81524	<0.4	NRQ	<0.4	NRQ	<0.5	NRQ	<0.5	NRQ	<0.5	NRQ
UG/L	10										
4-CHL'-3-METH'PHENOL	34452	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	10										
2-CHLOROPHENOL	34586	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	10										
2,4-DICHLOROPHENOL	34601	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	10										
2,4-DIMETHYLPHENOL	34606	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	10										
2,4-DINITROPHENOL	34616	<2.0	NRQ	<2.1	NRQ	<1.9	NRQ	<2.0	NRQ	<2.2	NRQ
UG/L	10										
2-MET'-4,6-DN'PHENOL	34657	<1.4	NRQ	<1.4	NRQ	<1.3	NRQ	<1.3	NRQ	<1.5	NRQ
UG/L	10										
2-NITROPHENOL	34591	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	10										

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SW1 PRSWI 6	5SW1 PRSWI 101	5SW2 PRSWI 7	5SW2 PRSWI 102	5SW3 PRSWI 8	5SW3 PRSWI 103	5SW4 PRSWI 9	5SW4 PRSWI 104	5SW5 PRSWI 10	5SW5 PRSWI 105
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
4-NITROPHENOL UG/L	34646 10	<1.1	NRQ	<1.2	NRQ	<1.0	NRQ	<1.1	NRQ	<1.2	NRQ
PENTACHLOROPHENOL UG/L	39032 10	<1.3	NRQ	<1.4	NRQ	<1.2	NRQ	<1.3	NRQ	<1.4	NRQ
PHENOL UG/L	34694 10	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
2,4,6-TRICHL'PHENOL UG/L	34621 10	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
ACENAPHTHENE UG/L	34205 0	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
ACENAPHTHYLENE UG/L	34200 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
ANTHRACENE UG/L	34220 0	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
BENZO(A)ANTHRACENE UG/L	34526 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BENZO(B)FLUORANTHENE UG/L	34230 0	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ
BENZO(K)FLUORANTHENE UG/L	34242 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BENZO(A)PYRENE UG/L	34247 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BENZO(GHI)PERYLENE UG/L	34521 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BUTYL BENZ'PHTHALATE UG/L	34292 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BIS(2-CHL'ETH')ETHER UG/L	34273 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BIS(2-CHL'ETHOX)MTHN UG/L	34278 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
BIS(2-ETH'HEX')PHTH. UG/L	39100 0	1	NRQ	1	NRQ	2	NRQ	<1	NRQ	1	NRQ
BIS(2-CHL'ISOPR)ETHR UG/L	34283 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
4-BRO'PHEN'PHEN'ETHR UG/L	34636 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
2-CHLORONAPHTHALENE UG/L	34581 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
4-CHL'PHEN'PHEN'ETHR UG/L	34641 0	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5SW1	5SW1	5SW2	5SW2	5SW3	5SW3	5SW4	5SW4	5SW5	5SW5
		SAMPLE ID/#									
		PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1
UNITS	METHOD	6	101	7	102	8	103	9	104	10	105
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
CHRYSENE	34320	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
DIBEN'(A,H)ANTH'CENE	34556	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
DI-N-BUTYLPHTHALATE	39110	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
1,3,DICHLOROBENZENE	34566	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
1,2-DICHLOROBENZENE	34536	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
1,4-DICHLOROBENZENE	34571	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
3,3'-DICHL'BENZIDINE	34631	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
DIETHYLPHTHALATE	34336	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
DIMETHYLPTHALATE	34341	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
2,4-DINITROTOLUENE	34611	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ
UG/L	0										
2,6-DINITROTOLUENE	34626	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ
UG/L	0										
DI-N-OCTYL PHTHALATE	34596	1	NRQ	7	NRQ	4	NRQ	<1	NRQ	2	NRQ
UG/L	0										
FLUORANTHENE	34376	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	0										
FLUORENE	34381	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	0										
HEXACH'CYC'PEN'DIENE	34386	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
HEXACHLOROBENZENE	39700	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
HEXACHLOROBUTADIENE	34391	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
HEXACHLOROETHANE	34396	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
INDENO(1,2,3-CD)PYRN	34403	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
ISOPHORONE	34408	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	0										

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SW1 PRSWI 6	5SW1 PRSWI 101	5SW2 PRSWI 7	5SW2 PRSWI 102	5SW3 PRSWI 8	5SW3 PRSWI 103	5SW4 PRSWI 9	5SW4 PRSWI 104	5SW5 PRSWI 10	5SW5 PRSWI 105
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
NAPHTHALENE	34696	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	0										
NITROBENZENE	34447	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ	<1.00	NRQ
UG/L	0										
N-NITROSODIPRO'AMINE	34428	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
N-NITROSODIMET'AMINE	34438	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
N-NITROSODIPHE'AMINE	34433	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
PHENANTHRENE	34461	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ	<1.0	NRQ
UG/L	0										
PYRENE	34469	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
1,2,4-TRICHL'BENZENE	34551	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ	<1	NRQ
UG/L	0										
ALDRIN	39330	<0.010	NRQ	<0.010	NRQ	<0.010	NRQ	<0.010	NRQ	<0.010	NRQ
UG/L	0										
BHC,A	39337	<0.007	NRQ	<0.007	NRQ	<0.007	NRQ	<0.007	NRQ	<0.007	NRQ
UG/L	0										
BHC,B	39338	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ
UG/L	0										
BHC-D	34259	<0.021	NRQ	<0.021	NRQ	<0.021	NRQ	<0.021	NRQ	<0.021	NRQ
UG/L	0										
BHC,G(LINDANE)	39340	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ
UG/L	0										
CHLORDANE	39350	<0.184	NRQ	<0.184	NRQ	<0.184	NRQ	<0.184	NRQ	<0.184	NRQ
UG/L	0										
DDD,PP'	39310	<0.208	NRQ	<0.208	NRQ	<0.208	NRQ	<0.208	NRQ	<0.208	NRQ
UG/L	0										
DDE,PP'	39320	<0.025	NRQ	<0.025	NRQ	<0.025	NRQ	<0.025	NRQ	<0.025	NRQ
UG/L	0										
DDT,PP'	39300	<0.096	NRQ	<0.096	NRQ	<0.096	NRQ	<0.096	NRQ	<0.096	NRQ
UG/L	0										
DIELDRIN	39380	<0.028	NRQ	<0.028	NRQ	<0.028	NRQ	<0.028	NRQ	<0.028	NRQ
UG/L	0										
ENDOSULFAN,A	34361	<0.025	NRQ	<0.025	NRQ	<0.025	NRQ	<0.025	NRQ	<0.025	NRQ
UG/L	0										
ENDOSULFAN,B	34356	<0.069	NRQ	<0.069	NRQ	<0.069	NRQ	<0.069	NRQ	<0.069	NRQ
UG/L	0										

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SW1 PRSWI 6	5SW1 PRSWI 101	5SW2 PRSWI 7	5SW2 PRSWI 102	5SW3 PRSWI 8	5SW3 PRSWI 103	5SW4 PRSWI 9	5SW4 PRSWI 104	5SW5 PRSWI 10	5SW5 PRSWI 105
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
ENDOSULFAN SULFATE	34351	<0.500	NRQ	<0.500	NRQ	<0.500	NRQ	<0.500	NRQ	<0.500	NRQ
UG/L	0										
ENDRIN	39390	<0.078	NRQ	<0.078	NRQ	<0.078	NRQ	<0.078	NRQ	<0.078	NRQ
UG/L	0										
ENDRIN ALDEHYDE	34366	<0.073	NRQ	<0.073	NRQ	<0.073	NRQ	<0.073	NRQ	<0.073	NRQ
UG/L	0										
HEPTACHLOR	39410	<0.009	NRQ	<0.009	NRQ	<0.009	NRQ	<0.009	NRQ	<0.009	NRQ
UG/L	0										
HEPTACHLOR EPOXIDE	39420	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ	<0.015	NRQ
UG/L	0										
TOXAPHENE	39400	<2.14	NRQ	<2.14	NRQ	<2.14	NRQ	<2.14	NRQ	<2.14	NRQ
UG/L	0										
PCB-1016	34671	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
PCB-1221	39488	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
PCB-1232	39492	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
PCB-1242	39496	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
PCB 1248	39500	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
PCB-1254	39504	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
PCB-1260	39508	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ	<0.400	NRQ
UG/L	0										
ANTIMONY,TOTAL	1097	<18.0	NRQ	<24.0	NRQ	<24.0	NRQ	<24.0	NRQ	<24.0	NRQ
UG/L	0										
ARSENIC,TOTAL	1002	102	NRQ	105	NRQ	97.0	NRQ	96.0	NRQ	104	NRQ
UG/L	0										
BERYLLIUM,T.	1012	<1.00	NRQ	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ
UG/L	0										
CADMIUM,TOTAL	1027	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ
UG/L	0										
CHROMIUM,TOTAL	1034	<3.00	NRQ	<6.00	NRQ	7.49	NRQ	6.00	NRQ	6.39	NRQ
UG/L	0										
COPPER,TOTAL	1042	2.00	NRQ	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ	<3.00	NRQ
UG/L	0										
LEAD,TOTAL	1051	<24.0	NRQ	<24.0	NRQ	<24.0	NRQ	<24.0	NRQ	<24.0	NRQ
UG/L	0										

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVHXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5SW1	5SW1	5SW2	5SW2	5SW3	5SW3	5SW4	5SW4	5SW5	5SW5
		SAMPLE ID/#									
		PRSWI	PRSWI	PRSWI	PRSWI	PRSWI	PRSWI	PRSWI	PRSWI	PRSWI	PRSWI
UNITS	METHOD	6	101	7	102	8	103	9	104	10	105
DATE		11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86	11/28/85	02/06/86
TIME		08:05	10:15	08:20	10:30	09:35	10:45	10:05	11:00	10:35	11:15
MERCURY,TOTAL	71900	<0.200	NRQ	<0.200	NRQ	<0.200	NRQ	<0.200	NRQ	<0.200	NRQ
UG/L	0										
NICKEL,T,	1067	<5.00	NRQ	<6.00	NRQ	<6.00	NRQ	<6.00	NRQ	33.6	NRQ
UG/L	0										
SELENIUM,TOTAL	1147	<39.0	NRQ	<39.0	NRQ	<39.0	NRQ	<39.0	NRQ	<39.0	NRQ
UG/L	0										
SILVER,TOTAL	1077	<6.00	NRQ	<6.00	NRQ	<6.00	NRQ	<6.00	NRQ	<6.00	NRQ
UG/L	0										
THALLIUM,TOTAL	1059	03.3	NRQ	06.7	NRQ	09.1	NRQ	116	NRQ	111	NRQ
UG/L	0										
ZINC,TOTAL	1092	15.0	NRQ	16.1	NRQ	4.31	NRQ	19.9	NRQ	5.01	NRQ
UG/L	0										
M-XYLENE	98553	<0.15	NRQ	<0.14	NRQ	<0.17	NRQ	<0.16	NRQ	<0.15	NRQ
UG/L	10										
O-AND/OR-P XYLENE	98554	<0.14	NRQ	<0.14	NRQ	<0.16	NRQ	<0.16	NRQ	<0.15	NRQ
UG/L	10										
TETRACHLOROETHENE	34475	<0.46	NRQ	<0.45	NRQ	<0.52	NRQ	<0.52	NRQ	<0.48	NRQ
UG/L	10										

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE			11/28/85	11/28/85	11/28/85	11/28/85	11/28/85
TIME			08:05	08:20	09:35	10:05	10:35
MOISTURE		70320	64.4	80.1	71.5	77.9	62.7
	%WET WT	0					
PH,SOIL		99218	7.2	7.4	7.5	7.5	7.9
		0					
CHROMIUM		99739	NA	NA	NA	NA	NA
	XXXX	0					
METHYL ETHYL KETONE		98801	<3.1	<5.6	<3.9	<5.0	<3.0
	UG/G-DRY	10					
MIBK		98696	<0.20	<0.35	<0.25	<0.32	<0.19
	UG/G-DRY	10					
BENZENE		98699	<0.08	<0.13	<0.10	<0.12	<0.07
	UG/G-DRY	10					
BROMODICHLOROMETHANE		98783	<0.17	<0.30	<0.21	<0.26	<0.16
	UG/G-DRY	10					
BROMOFORM		98784	<0.41	<0.71	<0.50	<0.62	<0.39
	UG/G-DRY	10					
BROMOMETHANE		98785	<0.36	<0.62	<0.44	<0.54	<0.34
	UG/G-DRY	10					
CARBON TETRACHLORIDE		98680	<0.37	<0.63	<0.45	<0.56	<0.35
	UG/G-DRY	10					
CHLOROBENZENE		98681	<0.13	<0.23	<0.16	<0.20	<0.12
	UG/G-DRY	10					
CHLOROETHANE		98786	<0.46	<0.80	<0.57	<0.71	<0.44
	UG/G-DRY	10					
2-CHLOROETHYLVINYLET		98796	<0.33	<0.57	<0.41	<0.50	<0.31
HER	UG/G-DRY	10					
CHLOROFORM		98682	<0.156	<0.270	<0.192	<0.238	<0.148
	UG/G-DRY	10					
CHLOROMETHANE		98787	<0.29	<0.51	<0.36	<0.45	<0.28
	UG/G-DRY	10					
DIBROMOCHLOROMETHANE		98788	<0.32	<0.56	<0.40	<0.49	<0.30
	UG/G-DRY	10					
1,1-DICHLOROETHANE		98683	<0.12	<0.21	<0.15	<0.27	<0.11
	UG/G-DRY	10					
1,2-DICHLOROETHANE		98684	<0.25	<0.44	<0.31	<0.39	<0.24
	UG/G-DRY	10					
1,1-DICHLOROETHENE		98789	<0.30	<0.52	<0.37	<0.46	<0.28
	UG/G-DRY	10					
TRANS-1,2-DICHLOROET		98687	<0.28	<0.49	<0.35	<0.43	<0.26
ENE	UG/G-DRY	10					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE			11/20/85	11/20/85	11/20/85	11/20/85	11/20/85
TIME			08:05	08:20	09:35	10:05	10:35
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.17	<0.30	<0.21	<0.26	<0.16
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.12	<0.21	<0.15	<0.19	<0.11
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.32	<0.56	<0.40	<0.49	<0.31
ETHYLBENZENE	UG/G-DRY	98688 10	<0.29	<0.50	<0.35	<0.44	<0.27
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.24	<0.42	<0.29	<0.38	<0.22
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.15	<0.27	<0.19	<0.23	<0.14
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.48	<0.84	<0.60	<0.73	<0.46
TOLUENE	UG/G-DRY	98691 10	<0.13	<0.24	<0.17	<0.22	<0.13
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.29	<0.51	<0.36	<0.45	<0.28
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.30	<0.52	<0.37	<0.46	<0.28
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.32	<0.55	<0.40	<0.49	<0.30
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.26	<0.45	<0.32	<0.39	<0.24
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.27	<0.47	<0.34	<0.42	<0.26
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.21	<0.37	<0.26	<0.32	<0.20
4-CHLORO-3-METHYLPHENOL	MG/KG-DRY	99683 10	<0.19	<0.33	<0.23	<0.30	<0.27
2-CHLOROPHENOL,SOIL	MG/KG-DRY	99497 10	<0.19	<0.33	<0.23	<0.30	<0.27
2,4-DICHLOROPHENOL,S	MG/KG-DRY	99498 10	<0.19	<0.33	<0.23	<0.30	<0.27
2,4-DIMETHYPHENOL,SO	MG/KG-DRY	99499 10	<0.19	<0.33	<0.23	<0.30	<0.27
2,4-DINITROPHENOL,SO	MG/KG-DRY	99695 10	<0.74	<1.1	<0.74	<1.00	<1.3
2-METHYL-4,6-DINITROPHENOL	MG/KG-DRY	99686 10	<0.50	<0.73	<0.50	<0.68	<0.54

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE			11/28/85	11/28/85	11/28/85	11/28/85	11/28/85
TIME			08:05	08:20	09:35	10:05	10:35
2-NITROPHENOL,SOIL	MG/KG-DRY	99495 10	<0.21	<0.33	<0.23	<0.30	<0.27
4-NITROPHENOL,SOIL	MG/KG-DRY	99496 10	<0.41	<0.60	<0.41	<0.55	<0.54
PENTACHLOROPHENOL,SO	MG/KG-DRY	99682 10	<0.48	<0.70	<0.48	<0.65	<0.54
PHENOL,SO	MG/KG-DRY	99685 10	<0.19	<0.33	<0.23	<0.30	<0.27
2,4,6-TRICHLRPHENOL, S	MG/KG-DRY	99684 10	<0.24	<0.35	<0.24	<0.32	<0.27
ACENAPHTHENE,SOIL	UG/G-DRY	99450 0	<0.2	<0.3	<0.2	<0.3	<0.2
ACENAPHTHYLENE,SOIL	MG/KG-DRY	99451 0	<0.2	<0.3	<0.2	<0.3	<0.2
ANTHRACENE,SOIL	MG/KG-DRY	99452 0	<0.2	<0.3	<0.2	<0.3	<0.2
BENZO(A)ANTHRACENE,S O	MG/KG-DRY	99453 0	<0.2	<0.3	<0.2	<0.3	<0.2
BENZO(B)FLUORANTHENE ,S	MG/KG-DRY	99454 0	<0.2	<0.3	<0.2	<0.3	<0.6
BENZO(K)FLUORANTHENE ,S	MG/KG-DRY	99455 0	<0.2	<0.3	<0.2	<0.3	<0.5
BENZO(A)PYRENE,SOIL	MG/KG-DRY	99456 0	<0.2	<0.3	<0.2	<0.3	<0.7
BENZO(G,H,I)PERYLENE ,SOIL	MG/KG-DRY	99691 0	<0.41	<0.60	<0.41	<0.55	<0.80
BUTYL BENZYL PHTHALA TE	MG/KG-DRY	99463 0	<0.2	<0.3	<0.2	<0.3	<0.3
BIS(2-CHLRETH)ETHER, SO	MG/KG-DRY	99458 0	<0.2	<0.3	<0.2	<0.3	<0.2
BIS(2-CHLETHOXY)METH ,S	MG/KG-DRY	99459 0	<0.2	<0.3	<0.2	<0.3	<0.2
BIS(2-E-H)PHTHALATE, SO	MG/KG-DRY	99460 0	0.1	<0.3	<0.2	<0.3	<0.2
BIS(2-CHLISOP)ETHER, SO	MG/KG-DRY	99461 0	<0.2	<0.3	<0.2	<0.3	<0.2
4-BROMOPHPHETHER,SOI L	MG/KG-DRY	99462 0	<0.3	<0.4	<0.3	<0.4	<0.3
2-CHLRNAPHTHALENE,SO	MG/KG-DRY	99464 0	<0.2	<0.3	<0.2	<0.3	<0.2

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000
FIELD GROUP PRSE1
NAVMXS

PROJECT NAME PUERTO RICO CONFIRMATION STUDY
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE		11/20/85	11/20/85	11/20/85	11/20/85	11/20/85
TIME		08:05	08:20	09:35	10:05	10:35
4-CHLRPHPHETHER,SOIL MG/KG-DRY	99465 0	<0.2	<0.3	<0.2	<0.3	<0.2
CHRYSENE, SOIL MG/KG-DRY	99690 0	<0.2	<0.3	<0.2	<0.3	<0.2
DIBENZO(A,H)ANTHRA,SO MG/KG-DRY	99466 0	<0.4	<0.6	<0.4	<0.5	<0.8
DI-N-BUTYL PHTHALATE MG/KG-DRY	99467 0	<0.2	<0.3	<0.2	<0.3	<0.2
1,3DICHLRBENZENE,SOIL MG/KG-DRY	99468 0	<0.2	<0.3	<0.2	<0.3	<0.2
1,2-DICHLRBENZENE,SO MG/KG-DRY	99470 0	<0.2	<0.3	<0.2	<0.3	<0.2
1,4-DICHLRBENZ ,SO MG/KG-DRY	99469 0	<0.2	<0.3	<0.2	<0.3	<0.2
3,3-DICHLRBENZIDINE,SO MG/KG-DRY	99471 0	<0.5	<0.7	<0.5	<0.6	<1.0
DIETHYLPHTHALATE,SOIL MG/KG-DRY	99472 0	<0.2	<0.3	<0.2	<0.3	<0.2
DIMETHYLPHTHALATE,SO MG/KG-DRY	99473 0	<0.2	<0.3	<0.2	<0.3	<0.2
2,4-DNT,SO MG/KG-DRY	99474 0	<0.2	<0.3	<0.2	<0.3	<0.2
2,6-DNT,SO MG/KG-DRY	99475 0	<0.3	<0.4	<0.3	<0.4	<0.3
DI-N-OCTYL PHTHALATE MG/KG-DRY	99476 0	1	4	0.5	<0.3	0.5
FLUORANTHENE,SOIL MG/KG-DRY	99689 0	<0.2	<0.3	<0.2	<0.3	<0.2
FLUORENE, SOIL MG/KG-DRY	99692 0	<0.2	<0.3	<0.2	<0.3	<0.2
HEXCHLRCYCLPENTADIEN,S MG/KG-DRY	99481 0	<0.5	<0.7	<0.5	<0.6	<0.4
HEXACHLOROBENZENE,SO MG/KG-DRY	99478 0	<0.2	<0.4	<0.2	<0.3	<0.3
HEXACHLOROBUTADIENE,S MG/KG-DRY	99479 0	<0.4	<0.5	<0.4	<0.5	<0.3
HEXACHLOROETHANE,SOIL MG/KG-DRY	99480 0	<0.3	<0.4	<0.3	<0.4	<0.2
INDENO(1,2,3-CD)PYR,SO MG/KG-DRY	99482 0	<0.4	<0.5	<0.4	<0.5	<0.8

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE		11/20/85	11/20/85	11/20/85	11/20/85	11/20/85
TIME		08:05	08:20	09:35	10:05	10:35
ISOPHORONE,SOIL	99483	<0.2	<0.3	<0.2	<0.3	<0.2
MG/KG-DRY	0					
NAPHTHALENE,SOIL	99696	<0.2	<0.3	<0.2	<0.3	<0.2
MG/KG-DRY	0					
NITROBENZENE,SOIL	99485	<0.186	<0.332	<0.231	<0.299	<0.177
UG/G-DRY	0					
N-NITROSODIPROPLAMIN	99487	<0.2	<0.3	<0.2	<0.3	<0.2
E MG/KG-DRY	0					
N-NITROSODIMETHLAMIN	99486	<0.2	<0.3	<0.2	<0.3	<0.2
E MG/KG-DRY	0					
N-NITROSODIPHENLAMIN	99488	<0.8	<1	<1	<0.8	<0.9
E MG/KG-DRY	0					
PHENANTHRENE,SOIL	99489	<0.2	<0.3	<0.2	<0.3	<0.2
MG/KG-DRY	0					
PYRENE,SO	99490	<0.2	<0.3	<0.2	<0.3	<0.2
MG/KG-DRY	0					
1,2,4-TRICHLRBENZENE	99492	<0.2	<0.3	<0.2	<0.3	<0.2
,S MG/KG-DRY	0					
ALDRIN,SED	98356	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G- DRY	0					
BHC,A,SED	98357	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
BHC,B,SED	98358	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
BHC,D,SED	98359	<0.562	1.03	<0.701	<0.907	<0.536
UG/G-DRY	0					
BHC,G,SED	98360	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
CHLORDANE,SED	98361	<4.50	<8.05	<5.61	<7.25	<4.28
UG/G- DRY	0					
DDD,PP'	98362	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
DDE,PP'	98363	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
DDT,PP'	98364	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
DIELDRIN	98365	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
ENDOSULFAN,A	98366	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G- DRY	0					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE		11/28/85	11/28/85	11/28/85	11/28/85	11/28/85
TIME		08:05	08:20	09:35	10:05	10:35
ENDOSULFAN,B	98367	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G- DRY	0					
ENDOSULFAN SULFATE	98368	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
ENDRIN	98369	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY.	0					
ENDRIN ALDEHYDE MG/K	98370	<0.562	<1.01	<0.701	<0.907	<0.536
G-DRY MG/KG-DRY	0					
HEPTACHLOR	98371	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G- DRY	0					
HEPTACHLOR EPOXIDE	98372	<0.562	<1.01	<0.701	<0.907	<0.536
UG/G-DRY	0					
TOXAPHENE	98373	<22.5	<40.2	<28.0	<36.3	<21.4
UG/G- DRY	0					
PCB 1016,SED	98140	<2.81	<5.03	<2.10	<2.72	<1.61
UG/G-DRY	0					
PCB-1221,SOIL	98351	<2.81	<5.03	<2.10	<2.72	<1.61
UG/G-DRY	0					
PCB-1232,SOIL	98352	<2.81	<5.03	<2.10	<2.72	<1.61
UG/G- DRY	0					
PCB-1242,SOIL	98353	<2.81	<5.03	<2.10	<2.72	<1.61
UG/G-DRY	0					
PCB1254-SOIL	98354	<2.81	<5.03	<2.10	<2.72	<1.61
UG/G- DRY	0					
PCB-1248 SOIL	98802	<3	<5	<2	<3	<2
UG/G-DRY	0					
PCB 1260,SED	98139	<2.81	<5.03	<2.10	<2.72	<1.61
UG/G-DRY	0					
ANTIMONY,SED	1098	3.8	5.2	5.1	24	7.3
MG/KG-DRY	0					
ARSENIC,SED	1003	14.4	<11.6	13.4	32.0	22.0
UG/G- DRY	0					
BERYLLIUM,SED	1013	<0.415	<0.776	<0.526	1.33	0.954
MG/KG-DRY	0					
CADMIUM,SED	1028	<0.623	<1.16	<0.788	<0.910	<0.595
UG/G- DRY	0					
CHROMIUM,SED	1029	21.9	28.4	29.3	54.1	33.5
UG/G- DRY	0					
COPPER,SED	1043	36.8	54.7	43.4	119	78.8
UG/G- DRY	0					

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	5SE1 PRSE1 9	5SE2 PRSE1 10	5SE3 PRSE1 11	5SE4 PRSE1 12	5SE5 PRSE1 13
DATE			11/28/85	11/28/85	11/28/85	11/28/85	11/28/85
TIME			08:05	08:20	09:35	10:05	10:35
LEAD,SED		1052	76.4	<24.4	21.0	<19.1	<12.5
	UG/G-DRY	0					
MERCURY		71921	0.109	<0.187	<0.131	<0.174	<0.100
	UG/G-DRY	0					
NICKEL,SED		1068	6.72	11.8	8.77	22.3	15.6
	UG/G- DRY	0					
SELENIUM,SED		1148	19.8	31.3	27.4	85.4	49.7
	MG/KG-DRY	0					
SILVER,SED		1078	<1.08	<1.94	<1.33	<2.03	<1.36
	MG/KG- DRY	0					
THALLIUM,SED		34480	<0.394	<0.630	<0.466	<0.618	<0.344
	MG/KG- DRY	0					
ZINC,SED		1093	25.9	42.8	32.8	72.8	50.8
	UG/G-DRY	0					
1,2-DIBROMOETHANE (E		98798	<0.006	<0.01	<0.007	<0.009	<0.005
DB)	MG/KG-DRY	0					
M-XYLENE		98799	<0.21	<0.37	<0.27	<0.33	<0.20
	MG/KG-DRY	10					
O,P-XYLENE		98800	<0.22	<0.39	<0.28	<0.34	<0.21
	MG/KG-DRY	10					

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	R6SW1 PRSW1	R6SW2 PRSW1	R6SW3 PRSW1
UNITS	METHOD	11	12	13
DATE.		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
1,2-DIBR'ETHANE(EDB)	77651	NA	NA	NA
UG/L	0			
PH,FIELD	400	8.12	7.98	7.79
STD UNITS	0			
CHROMIUM,(+6)	1032	<20.0	34.4	36.7
UG/L	0			
METHYL ETHYL KETONE	81595	<16	<16	<14
UG/L	10			
METHYL ISOBUT'KETONE	81596	<1.8	<1.8	<1.7
UG/L	10			
BENZENE	34030	<1.0	<0.29	<0.93
UG/L	10			
BROMODICHLOROMETHANE	32101	<0.36	<0.37	<0.36
UG/L	10			
BROMOFORM	32104	<0.91	<0.92	<0.90
UG/L	10			
BROMOMETHANE	34413	<0.77	<0.78	<0.76
UG/L	10			
CARBON TETRACHLORIDE	32102	<0.30	<0.31	<0.30
UG/L	10			
CHLOROBENZENE	34301	<0.25	<0.26	<0.25
UG/L	10			
CHLOROETHANE	34311	<1.6	<1.7	<1.6
UG/L	10			
2-CHL'ETH'VINYLETHER	34576	<3.1	<3.1	<3.1
UG/L	10			
CHLOROFORM	32106	<0.30	<0.30	<0.30
UG/L	10			
CHLOROMETHANE	34418	<0.98	<0.99	<0.96
UG/L	10			
DIBROMOCHLOROMETHANE	32105	<0.566	<0.572	<0.559
UG/L	10			
1,1-DICHLOROETHANE	34496	<0.50	<0.51	<0.50
UG/L	10			
1,2-DICHLOROETHANE	34531	<0.42	<0.42	<0.41
UG/L	10			
1,1-DICHLOROETHYLENE	34501	0.0	<0.85	<0.83
UG/L	10			
T-1,2-DICHLOROETHENE	34546	<0.82	<0.83	<0.81
UG/L	10			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6SW1 PRSWI 11	R6SW2 PRSWI 12	R6SW3 PRSWI 13
DATE		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
1,2-DICHLOROPROPANE	34541	<0.97	<0.98	<0.95
UG/L	10			
CIS-1,3-DICH'PROPENE	34704	<0.36	<0.37	<0.36
UG/L	10			
T-1,3-DICHL'PROPENE	34699	<0.36	<0.37	<0.36
UG/L	10			
ETHYLBENZENE	34371	<0.57	<0.57	<0.56
UG/L	10			
METHYLENE CHLORIDE	34423	<0.77	<2.5	<0.76
UG/L	10			
1,1,2,2-TE'CH'ETHANE	34516	<1.1	<1.1	<1.1
UG/L	10			
TOLUENE	34010	<0.39	<0.39	<0.38
UG/L	10			
1,1,1-TRICHL'ETHANE	34506	<0.34	<0.34	<0.33
UG/L	10			
1,1,2-TRICHL'ETHANE	34511	<0.78	<0.79	<0.77
UG/L	10			
TRICHLOROETHENE	39180	<0.48	<0.48	<0.47
UG/L	10			
TRICHL'FLUOROMETHANE	34488	<1.0	<1.0	<1.0
UG/L	10			
VINYL CHLORIDE	39175	<0.78	<0.78	<0.77
UG/L	10			
DICHLOROBENZENE,T.	81524	<0.2	<0.2	<0.2
UG/L	10			
4-CHL'-3-METH'PHENOL	34452	<0.55	<0.41	<0.41
UG/L	10			
2-CHLOROPHENOL	34586	<0.40	<0.30	<0.29
UG/L	10			
2,4-DICHLOROPHENOL	34601	<0.57	<0.42	<0.42
UG/L	10			
2,4-DIMETHYLPHENOL	34606	<0.48	<0.36	<0.35
UG/L	10			
2,4-DINITROPHENOL	34616	<2.6	<1.9	<1.9
UG/L	10			
2-MET'-4,6-DN'PHENOL	34657	<1.8	<1.3	<1.3
UG/L	10			
2-NITROPHENOL	34591	<0.73	<0.54	<0.54
UG/L	10			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	R6SW1	R6SW2	R6SW3
UNITS	METHOD	PRSW1	PRSW1	PRSW1
		11	12	13
DATE		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
4-NITROPHENOL	34646	<1.5	<1.1	<1.1
UG/L	10			
PENTACHLOROPHENOL	39032	<1.7	<1.3	<1.3
UG/L	10			
PHENOL	34694	<0.28	<0.21	<0.21
UG/L	10			
2,4,6-TRICHL'PHENOL	34621	<0.85	<0.62	<0.62
UG/L	10			
ACENAPHTHENE	34205	<0.2	<0.2	<0.2
UG/L	0			
ACENAPHTHYLENE	34200	<0.1	<0.1	<0.1
UG/L	0			
ANTHRACENE	34220	<0.2	<0.1	<0.1
UG/L	0			
BENZO(A)ANTHRACENE	34526	<0.4	<0.3	<0.3
UG/L	0			
BENZO(B)FLUORANTHENE	34230	<0.611	<0.451	<0.447
UG/L	0			
BENZO(K)FLUORANTHENE	34242	<0.6	<0.5	<0.5
UG/L	0			
BENZO(A)PYRENE	34247	<0.8	<0.6	<0.6
UG/L	0			
BENZO(GHI)PERYLENE	34521	<1	<1	<1
UG/L	0			
BUTYL BENZ'PHTHALATE	34292	<0.4	<0.3	<0.3
UG/L	0			
BIS(2-CHL'ETH')ETHER	34273	<0.3	<0.2	<0.2
UG/L	0			
BIS(2-CHL'ETHOX)MTHN	34278	<0.2	<0.2	<0.2
UG/L	0			
BIS(2-ETH'HEX')PHTH.	39100	1	1	<0.3
UG/L	0			
BIS(2-CHL'ISOPR)ETHR	34283	<0.3	<0.2	<0.2
UG/L	0			
4-BRO'PHEN'PHEN'ETHR	34636	<0.9	<0.7	<0.7
UG/L	0			
2-CHLORONAPHTHALENE	34581	<0.2	<0.2	<0.2
UG/L	0			
4-CHL'PHEN'PHEN'ETHR	34641	<0.5	<0.3	<0.3
UG/L	0			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6SW1 PRSW1 11	R6SW2 PRSW1 12	R6SW3 PRSW1 13
DATE		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
CHRYSENE	34320	<0.3	<0.3	<0.3
UG/L	0			
DIBEN'(A,H)ANTH'CENE	34556	<1	<1	<1
UG/L	0			
DI-N-BUTYLPHTHALATE	39110	<0.1	<0.1	<0.1
UG/L	0			
1,3,DICHLOROBENZENE	34566	<0.4	<0.3	<0.3
UG/L	0			
1,2-DICHLOROBENZENE	34536	<0.4	<0.3	<0.3
UG/L	0			
',4-DICHLOROBENZENE	34571	<0.4	<0.3	<0.3
UG/L	0			
3,3'-DICHL'BENZIDINE	34631	<2	<1	<1
UG/L	0			
DIETHYLPHTHALATE	34336	<0.2	<0.2	<0.2
UG/L	0			
DIMETHYLPTHALATE	34341	<0.2	<0.1	<0.1
UG/L	0			
2,4-DINITROTOLUENE	34611	<0.730	<0.539	<0.534
UG/L	0			
2,6-DINITROTOLUENE	34626	<1.01	<0.742	<0.736
UG/L	0			
DI-N-OCTYL PHTHALATE	34596	2	<0.2	2
UG/L	0			
FLUORANTHENE	34376	<0.2	<0.1	<0.1
UG/L	0			
FLUORENE	34381	<0.2	<0.1	<0.1
UG/L	0			
HEXACH'CYC'PEN'DIENE	34386	<2	<1	<1
UG/L	0			
HEXACHLOROBENZENE	39700	<0.9	<0.6	<0.6
UG/L	0			
HEXACHLOROBUTADIENE	34391	<1	<0.9	<0.9
UG/L	0			
HEXACHLOROETHANE	34396	<1.0	<0.7	<0.7
UG/L	0			
INDENO(1,2,3-CD)PYRN	34403	<1	<1.0	<1.0
UG/L	0			
ISOPHORONE	34408	<0.20	<0.15	<0.15
UG/L	0			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SW1 PRSW1 11	R6SW2 PRSW1 12	R6SW3 PRSW1 13
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
NAPHTHALENE	UG/L	34696 0	<0.1	<0.10	<0.10
NITROBENZENE	UG/L	34447 0	<0.399	<0.295	<0.292
N-NITROSODIPRO'AMINE	UG/L	34428 0	<0.5	<0.4	<0.3
N-NITROSODIMET'AMINE	UG/L	34438 0	<0.5	<0.3	<0.3
N-NITROSODIPHE'AMINE	UG/L	34433 0	<5	<3	<3
PHENANTHRENE	UG/L	34461 0	<0.2	<0.1	<0.1
PYRENE	UG/L	34469 0	<0.2	<0.1	<0.1
1,2,4-TRICHL'BENZENE	UG/L	34551 0	<0.6	<0.4	<0.4
ALDRIN	UG/L	39330 0	<0.005	<0.005	<0.005
BHC,A	UG/L	39337 0	<0.003	<0.003	<0.003
BHC,B	UG/L	39338 0	<0.007	<0.007	<0.007
BHC-D	UG/L	34259 0	<0.009	<0.009	<0.009
BHC,G(LINDANE)	UG/L	39340 0	<0.007	<0.007	<0.007
CHLORDANE	UG/L	39350 0	<0.087	<0.087	<0.087
DDD,PP'	UG/L	39310 0	<0.062	<0.062	<0.062
DDE,PP'	UG/L	39320 0	<0.011	<0.011	<0.011
DDT,PP'	UG/L	39300 0	<0.037	<0.037	<0.037
DIELDRIN	UG/L	39380 0	<0.013	<0.013	<0.013
ENDOSULFAN,A	UG/L	34361 0	<0.011	<0.011	<0.011
ENDOSULFAN,B	UG/L	34356 0	<0.028	<0.028	<0.028

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
NAVMXH LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SW1 PRSW1 11	R6SW2 PRSW1 12	R6SW3 PRSW1 13
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
ENDOSULFAN SULFATE		34351	<0.208	<0.208	<0.208
	UG/L	0			
ENDRIN		39390	<0.031	<0.031	<0.031
	UG/L	0			
ENDRIN ALDEHYDE		34366	<0.035	<0.035	<0.035
	UG/L	0			
HEPTACHLOR		39410	<0.004	<0.004	<0.004
	UG/L	0			
HEPTACHLOR EPOXIDE		39420	<0.007	<0.007	<0.007
	UG/L	0			
TOXAPHENE		39400	<1.02	<1.02	<1.02
	UG/L	0			
PCB-1016		34671	<0.200	<0.200	<0.200
	UG/L	0			
PCB-1221		39488	<0.200	<0.200	<0.200
	UG/L	0			
PCB-1232		39492	<0.200	<0.200	<0.200
	UG/L	0			
PCB-1242		39496	<0.200	<0.200	<0.200
	UG/L	0			
PCB 1248		39500	<0.200	<0.200	<0.200
	UG/L	0			
PCB-1254		39504	<0.200	<0.200	<0.200
	UG/L	0			
PCB-1260		39508	<0.200	<0.200	<0.200
	UG/L	0			
ANTIMONY,TOTAL		1097	<24.0	<24.0	<24.0
	UG/L	0			
ARSENIC,TOTAL		1002	<18.0	<18.0	<18.0
	UG/L	0			
BERYLLIUM,T.		1012	23.6	50.6	24.7
	UG/L	0			
CADMIUM,TOTAL		1027	4.42	8.40	3.35
	UG/L	0			
CHROMIUM,TOTAL		1034	318	611	339
	UG/L	0			
COPPER,TOTAL		1042	354	966	516
	UG/L	0			
LEAD,TOTAL		1051	211	526	244
	UG/L	0			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6SW1 PRSWI 11	R6SW2 PRSWI 12	R6SW3 PRSWI 13
DATE		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
MERCURY,TOTAL	71900	0.856	0.997	0.997
UG/L	0			
NICKEL,T,	1067	135	252	147
UG/L	0			
SELENIUM,TOTAL	1147	278	<39.0	549
UG/L	0			
SILVER,TOTAL	1077	<6.00	<6.00	<6.00
UG/L	0			
THALLIUM,TOTAL	1059	29.3	28.6	19.2
UG/L	0			
ZINC,TOTAL	1092	558	1310	818
UG/L	0			
M-XYLENE	98553	<0.16	<0.17	<0.16
UG/L	10			
O-AND/OR-P XYLENE	98554	<0.16	<0.16	<0.16
UG/L	10			
TETRACHLOROETHENE	34475	<0.51	<0.52	<0.51
UG/L	10			

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
MOISTURE		70320	46.3	49.6	40.7
	%WET WT	0			
PH,SOIL		99218	7.8	7.7	7.8
		0			
CHROMIUM		99739	NA	NA	NA
	XXXX	0			
METHYL ETHYL KETONE		98801	<1.5	<2.2	1.6
	UG/G-DRY	10			
MIBK		98696	<1.0	<1.5	<1.1
	UG/G-DRY	10			
BENZENE		98699	<0.15	<0.23	<0.16
	UG/G-DRY	10			
BROMODICHLOROMETHANE		98783	<0.18	<0.26	<0.18
	UG/G-DRY	10			
BROMOFORM		98784	<0.40	<0.59	<0.42
	UG/G-DRY	10			
BROMOMETHANE		98785	<0.37	<0.55	<0.39
	UG/G-DRY	10			
CARBON TETRACHLORIDE		98680	<0.14	<0.20	<0.15
	UG/G-DRY	10			
CHLOROBENZENE		98681	<0.13	<0.19	<0.13
	UG/G-DRY	10			
CHLOROETHANE		98786	<0.83	<1.2	<0.86
	UG/G-DRY	10			
2-CHLOROETHYLVINYLET		98796	<0.80	<1.2	<0.83
HER	UG/G-DRY	10			
CHLOROFORM		98682	<0.153	<0.224	<0.159
	UG/G-DRY	10			
CHLOROMETHANE		98787	<0.59	<0.87	<0.61
	UG/G-DRY	10			
DIBROMOCHLOROMETHANE		98788	<0.26	<0.38	<0.27
	UG/G-DRY	10			
1,1-DICHLOROETHANE		98683	<0.27	<0.40	<0.28
	UG/G-DRY	10			
1,2-DICHLOROETHANE		98684	<0.21	<0.32	<0.22
	UG/G-DRY	10			
1,1-DICHLOROETHENE		98789	<0.45	<0.66	<0.47
	UG/G-DRY	10			
TRANS-1,2-DICHLOROET		98687	<0.44	<0.65	<0.46
ENE	UG/G-DRY	10			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOHEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.50	<0.74	<0.52
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.18	<0.27	<0.19
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.18	<0.27	<0.19
ETHYLBENZENE	UG/G-DRY	98688 10	<0.28	<0.42	<0.29
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.39	<0.58	<0.41
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.59	<0.87	<0.62
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.25	<0.37	<0.26
TOLUENE	UG/G-DRY	98691 10	<0.20	<0.29	<0.21
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.17	<0.24	<0.17
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.38	<0.56	<0.40
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.29	<0.43	<0.30
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.54	<0.80	<0.56
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.42	<0.62	<0.44
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.11	<0.16	<0.11
4-CHLORO-3-METHYLPHENOL	MG/KG-DRY	99683 10	<0.06	<0.06	<0.12
2-CHLOROPHENOL,SOIL	MG/KG-DRY	99497 10	<0.06	<0.06	<0.08
2,4-DICHLOROPHENOL,S	MG/KG-DRY	99498 10	<0.06	<0.07	<0.12
2,4-DIMETHYPHENOL,SO	MG/KG-DRY	99499 10	<0.06	<0.06	<0.10
2,4-DINITROPHENOL,SO	MG/KG-DRY	99695 10	<0.22	<0.30	<0.97
2-METHYL-4,6-DINITROPHENOL	MG/KG-DRY	99686 10	<0.15	<0.20	<0.51

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
2-NITROPHENOL,SOIL MG/KG-DRY	99495 10	<0.06	<0.08	<0.18
4-NITROPHENOL,SOIL MG/KG-DRY	99496 10	<0.12	<0.17	<0.39
PENTACHLOROPHENOL,SO MG/KG-DRY	99682 10	<0.15	<0.20	<0.49
PHENOL,SO MG/KG-DRY	99685 10	<0.06	<0.06	<0.06
2,4,6-TRICHLRPHENOL, S MG/KG-DRY	99684 10	<0.07	<0.10	<0.18
ACENAPHTHENE,SOIL UG/G-DRY	99450 0	<0.06	<0.06	<0.06
ACENAPHTHYLENE,SOIL MG/KG-DRY	99451 0	<0.02	<0.02	<0.03
ANTHRACENE,SOIL MG/KG-DRY	99452 0	<0.06	<0.06	<0.06
BENZO(A)ANTHRACENE,S O MG/KG-DRY	99453 0	<0.06	<0.06	<0.2
BENZO(B)FLUORANTHENE ,S MG/KG-DRY	99454 0	<0.06	<0.07	<0.5
BENZO(K)FLUORANTHENE ,S MG/KG-DRY	99455 0	<0.06	<0.07	<0.4
BENZO(A)PYRENE,SOIL MG/KG-DRY	99456 0	<0.07	<0.09	<0.5
BENZO(G,H,I)PERYLENE ,SOIL MG/KG-DRY	99691 0	<0.12	<0.17	<1.2
BUTYL BENZYL PHTHALA TE MG/KG-DRY	99463 0	<0.06	<0.06	<0.1
BIS(2-CHLRETH)ETHER, SO MG/KG-DRY	99458 0	<0.06	<0.06	<0.06
BIS(2-CHLETHOXY)METH ,S MG/KG-DRY	99459 0	<0.06	<0.06	<0.06
BIS(2-E-H)PHTHALATE, SO MG/KG-DRY	99460 0	0.09	<0.06	<0.2
BIS(2-CHLISOP)ETHER, SO MG/KG-DRY	99461 0	<0.06	<0.06	<0.1
4-BROMOPHPHETHER,SOI L MG/KG-DRY	99462 0	<0.08	<0.1	<0.3
2-CHLRNAPHTHALENE,SO MG/KG-DRY	99464 0	<0.06	<0.06	<0.06

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
4-CHLRPHPHETHER,SOIL	MG/KG-DRY	99465 0	<0.06	<0.06	<0.1
CHRYSENE, SOIL	MG/KG-DRY	99690 0	<0.06	<0.06	<0.2
DIBENZO(A,H)ANTHRA,S O	MG/KG-DRY	99466 0	<0.1	<0.2	<1
DI-N-BUTYL PHTHALATE	MG/KG-DRY	99467 0	<0.06	<0.06	<0.06
1,3DICHLRBENZENE,SOI L	MG/KG-DRY	99468 0	<0.06	<0.06	<0.08
1,2-DICHLRBENZENE,SO	MG/KG-DRY	99470 0	<0.06	<0.06	<0.08
1,4-DICHLRBENZ ,SO	MG/KG-DRY	99469 0	<0.06	<0.06	<0.07
3,3-DICHLRBENZIDINE, SO	MG/KG-DRY	99471 0	<0.1	<0.2	<0.8
DIETHYLPHTHALATE,SOI L	MG/KG-DRY	99472 0	<0.06	<0.06	<0.06
DIMETHYLPHTHALATE,SO	MG/KG-DRY	99473 0	<0.06	<0.06	<0.06
2,4-DNT,SO	MG/KG-DRY	99474 0	<0.06	<0.08	<0.2
2,6-DNT,SO	MG/KG-DRY	99475 0	<0.09	<0.1	<0.2
DI-N-OCTYL PHTHALATE	MG/KG-DRY	99476 0	0.3	0.2	0.2
FLUORANTHENE,SOIL	MG/KG-DRY	99689 0	<0.06	<0.06	<0.08
FLUORENE, SOIL	MG/KG-DRY	99692 0	<0.06	<0.06	<0.06
HEXCHLRCYCLPENTADIEN ,S	MG/KG-DRY	99481 0	<0.1	<0.2	<0.3
HEXACHLOROBENZENE,SO	MG/KG-DRY	99478 0	<0.07	<0.10	<0.2
HEXACHLOROBUTADIENE, S	MG/KG-DRY	99479 0	<0.1	<0.1	<0.2
HEXACHLOROETHANE,SOI L	MG/KG-DRY	99480 0	<0.08	<0.1	<0.2
INDENO(1,2,3-CD)PYR, SO	MG/KG-DRY	99482 0	<0.1	<0.2	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
ISOPHORONE,SOIL		99483	<0.06	<0.06	<0.06
	MG/KG-DRY	0			
NAPHTHALENE,SOIL		99696	<0.06	<0.06	<0.06
	MG/KG-DRY	0			
NITROBENZENE,SOIL		99485	<0.056	<0.060	<0.085
	UG/G-DRY	0			
N-NITROSODIPROPLAMIN		99487	<0.06	<0.06	<0.1
E	MG/KG-DRY	0			
N-NITROSODIMETHLAMIN		99486	<0.06	<0.06	<0.1
E	MG/KG-DRY	0			
N-NITROSODIPHENLAMIN		99488	<0.07	<0.1	<0.1
E	MG/KG-DRY	0			
PHENANTHRENE,SOIL		99489	<0.06	<0.06	<0.06
	MG/KG-DRY	0			
PYRENE,SO		99490	<0.06	<0.06	<0.08
	MG/KG-DRY	0			
1,2,4-TRICHLRBENZENE		99492	<0.06	<0.07	<0.1
,S	MG/KG-DRY	0			
ALDRIN,SED		98356	<0.466	<0.496	<0.487
	UG/G- DRY	0			
BHC,A,SED		98357	<0.466	<0.496	<0.487
	UG/G-DRY	0			
BHC,B,SED		98358	<0.466	<0.496	<0.487
	UG/G-DRY	0			
BHC,D,SED		98359	<0.466	<0.496	<0.487
	UG/G-DRY	0			
BHC,G,SED		98360	<0.466	<0.496	<0.487
	UG/G-DRY	0			
CHLORDANE,SED		98361	<1.86	<1.98	<1.95
	UG/G- DRY	0			
DDD,PP'		98362	<0.466	<0.496	<0.487
	UG/G-DRY	0			
DDE,PP'		98363	<0.466	<0.496	<0.487
	UG/G-DRY	0			
DDT,PP'		98364	<0.466	<0.496	<0.487
	UG/G-DRY	0			
DIELDRIN		98365	<0.466	<0.496	<0.487
	UG/G-DRY	0			
ENDOSULFAN,A		98366	<0.466	<0.496	<0.487
	UG/G- DRY	0			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE		12/05/85	12/05/85	12/05/85
TIME		08:15	09:20	10:00
ENDOSULFAN,B UG/G- DRY	98367 0	<0.466	<0.496	<0.487
ENDOSULFAN SULFATE UG/G-DRY	98368 0	<0.466	<0.496	<0.487
ENDRIN UG/G-DRY.	98369 0	<0.466	<0.496	<0.487
ENDRIN ALDEHYDE MG/K G-DRY MG/KG-DRY	98370 0	<0.466	<0.496	<0.487
HEPTACHLOR UG/G- DRY	98371 0	<0.466	<0.496	<0.487
HEPTACHLOR EPOXIDE UG/G-DRY	98372 0	<0.466	<0.496	<0.487
TOXAPHENE UG/G- DRY	98373 0	<18.6	<19.8	<19.5
PCB 1016,SED UG/G-DRY	98140 0	<1.12	<1.19	<1.17
PCB-1221,SOIL UG/G-DRY	98351 0	<1.12	<1.19	<1.17
PCB-1232,SOIL UG/G- DRY	98352 0	<1.12	<1.19	<1.17
PCB-1242,SOIL UG/G-DRY	98353 0	<1.12	<1.19	<1.17
PCB1254-SOIL UG/G- DRY	98354 0	<1.12	<1.19	<1.17
PCB-1248 SOIL UG/G-DRY	98802 0	<1	<1	<1
PCB 1260,SED UG/G-DRY	98139 0	<1.12	<1.19	<1.17
ANTIMONY,SED MG/KG-DRY	1098 0	5.9	6.9	7.4
ARSENIC,SED UG/G- DRY	1003 0	7.76	15.1	16.4
BERYLLIUM,SED MG/KG-DRY	1013 0	<0.278	0.360	0.392
CADMIUM,SED UG/G- DRY	1028 0	<0.417	<0.404	<0.407
CHROMIUM,SED UG/G- DRY	1029 0	6.71	11.7	18.0
COPPER,SED UG/G- DRY	1043 0	9.10	20.4	26.4

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6SE1 PRSE1 14	R6SE2 PRSE1 15	R6SE3 PRSE1 16
DATE			12/05/85	12/05/85	12/05/85
TIME			08:15	09:20	10:00
LEAD,SED		1052	<8.75	<8.49	<8.54
	UG/G-DRY	0			
MERCURY		71921	<0.065	<0.067	0.084
	UG/G-DRY	0			
NICKEL,SED		1068	3.46	5.62	7.45
	UG/G- DRY	0			
SELENIUM,SED		1148	7.02	16.3	19.4
	MG/KG-DRY	0			
SILVER,SED		1078	<0.838	<1.05	<0.779
	MG/KG- DRY	0			
THALLIUM,SED		34480	<0.251	<0.216	<0.238
	MG/KG- DRY	0			
ZINC,SED		1093	14.1	23.3	29.8
	UG/G-DRY	0			
1,2-DIBROMOETHANE (E		98798	<0.004	<0.004	<0.004
DB)	MG/KG-DRY	0			
M-XYLENE		98799	<0.08	<0.12	<0.08
	MG/KG-DRY	10			
O,P-XYLENE		98800	<0.08	<0.11	<0.08
	MG/KG-DRY	10			

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSO1 PROJECT MANAGER R. BOWEN
NAVMXS LAB COORDINATOR LISA BARE

PARAMETERS	UNITS	STORET # METHOD	R6S1A PRSO1 15	R6S2A PRSO1 16	R6S3A PRSO1 17	R6S4A PRSO1 18	R6S5A PRSO1 19	R6S6A PRSO1 20	R6S7A PRSO1 21	R6S8A PRSO1 22	R6S9A PRSO1 23	R6S10A PRSO1 24	R6S11A PRSO1 25	R6S12A PRSO1 26	R6A13A PRSO1 27	R6S14A PRSO1 28	R6S15A PRSO1 29
			SAMPLE ID/#														
DATE			12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME			10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
MOISTURE		70320	36.8	47.3	35.5	31.3	27.7	28.5	18.8	30.2	35.0	23.4	31.3	23.4	15.0	29.4	22.7
	%WET WT	0															
PH,SOIL		99218	8.2	8.0	8.1	8.0	8.6	8.6	8.5	8.4	9.0	8.2	7.7	8.0	8.5	8.4	7.9
		0															
CHROMIUM		99739	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA
	XXXX	0															
METHYL ETHYL KETONE		98801	<1.9	<0.57	<1.0	<0.97	<0.92	<1.4	<1.7	<2.0	<1.5	<1.3	<1.0	<0.85	<2.0	<1.7	<2.6
	UG/G-DRY	10															
MIBK		98696	<0.25	<2.0	<0.28	<0.26	<0.25	<0.26	<0.24	<0.27	<0.48	<0.38	<0.60	<0.51	<0.49	<0.23	<0.38
	UG/G-DRY	10															
BENZENE		98699	<0.09	<0.04	<0.10	<0.09	<0.008	<0.08	<0.08	<0.09	<0.13	<0.11	<0.12	<0.10	<0.10	<0.08	<0.15
	UG/G-DRY	10															
BROMODICHLOROMETHANE		98783	<0.18	<0.08	<0.20	<0.17	<0.02	<0.17	<0.15	<0.17	<0.15	<0.12	<0.14	<0.12	<0.11	<0.16	<0.32
	UG/G-DRY	10															
BROMOFORM		98784	<0.35	<0.15	<0.37	<0.32	<0.03	<0.30	<0.27	<0.32	<0.30	<0.24	<0.31	<0.26	<0.26	<0.32	<0.64
	UG/G-DRY	10															
BROMOMETHANE		98785	<0.34	<0.14	<0.34	<0.29	<0.03	<0.28	<0.25	<0.29	<0.27	<0.21	<0.30	<0.25	<0.25	<0.31	<0.70
	UG/G-DRY	10															
CARBON TETRACHLORIDE		98680	<0.31	<0.13	<0.34	<0.29	<0.30	<0.30	<0.27	<0.32	<0.12	<0.10	<0.12	<0.10	<0.10	<0.28	<0.62
	UG/G-DRY	10															
CHLOROBENZENE		98681	<0.12	<0.05	<0.13	<0.11	<0.01	<0.12	<0.11	<0.12	<0.11	<0.09	<0.11	<0.09	<0.09	<0.11	<0.24
	UG/G-DRY	10															
CHLOROETHANE		98786	<0.48	<0.20	<0.54	<0.46	<0.05	<0.44	<0.39	<0.46	<0.67	<0.54	<0.65	<0.55	<0.53	<0.43	<0.97
	UG/G-DRY	10															
2-CHLOROETHYLVINYLET		98796	<0.36	<0.38	<0.39	<0.33	<0.03	<0.38	<0.35	<0.40	<1.1	<0.89	<0.66	<0.56	<0.55	<0.33	<0.62
HER	UG/G-DRY	10															
CHLOROFORM		98682	<0.146	<0.186	<0.166	<0.139	<0.149	<0.147	<0.133	<0.154	<0.131	<0.105	<0.122	<0.103	<0.100	<0.133	<0.296
	UG/G-DRY	10															
CHLOROMETHANE		98787	<0.45	<0.19	<1.0	<0.88	<0.09	<0.40	<0.36	<0.42	<0.48	<0.39	<0.39	<0.33	<0.32	<0.41	<0.69
	UG/G-DRY	10															
DIBROMOCHLOROMETHANE		98788	<0.26	<0.11	<0.29	<0.25	<0.02	<0.26	<0.24	<0.27	<0.22	<0.18	<0.21	<0.18	<0.17	<0.24	<0.52
	UG/G-DRY	10															
1,1-DICHLOROETHANE		98683	<0.13	<0.48	<0.15	<0.14	<0.13	<0.14	<0.13	<0.15	<0.22	<0.18	<0.21	<0.17	<0.17	<0.12	<0.26
	UG/G-DRY	10															
1,2-DICHLOROETHANE		98684	<0.27	<0.12	<0.30	<0.26	<0.27	<0.26	<0.23	<0.27	<0.16	<0.13	<0.15	<0.13	<0.13	<0.25	<0.48
	UG/G-DRY	10															
1,1-DICHLOROETHENE		98789	<0.28	<0.12	<0.31	<0.26	<0.03	<0.27	<0.25	<0.29	<0.40	<0.32	<0.34	<0.29	<0.28	<0.26	<0.59
	UG/G-DRY	10															
TRANS-1,2-DICHLOROET		98687	<0.28	<0.12	<0.31	<0.27	<0.03	<0.26	<0.23	<0.27	<0.37	<0.30	<0.32	<0.27	<0.27	<0.26	<0.54
ENE	UG/G-DRY	10															

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSO1 PROJECT MANAGER R. BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6S1A PRSO1 15	R6S2A PRSO1 16	R6S3A PRSO1 17	R6S4A PRSO1 18	R6S5A PRSO1 19	R6S6A PRSO1 20	R6S7A PRSO1 21	R6S8A PRSO1 22	R6S9A PRSO1 23	R6S10A PRSO1 24	R6S11A PRSO1 25	R6S12A PRSO1 26	R6A13A PRSO1 27	R6S14A PRSO1 28	R6S15A PRSO1 29
DATE		12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME		10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
1,2-DICHLOROPROPANE UG/G-DRY	98790 10	<0.19	<0.08	<0.21	<0.18	<0.02	<0.20	<0.18	<0.21	<0.43	<0.35	<0.41	<0.34	<0.33	<0.17	<0.34
CIS-1,3-DICHLOROPROPENE UG/G-DRY	98791 10	<0.13	<0.22	<0.15	<0.13	<0.01	<0.13	<0.12	<0.14	<0.14	<0.11	<0.14	<0.12	<0.12	<0.12	<0.23
TRANS-1,3-DICHLOROPROPENE UG/G-DRY	98792 10	<0.37	<0.16	<0.40	<0.34	<0.03	<0.35	<0.32	<0.37	<0.14	<0.11	<0.46	<0.39	<0.38	<0.34	<0.61
ETHYLBENZENE UG/G-DRY	98688 10	<0.29	<0.12	<0.31	<0.27	<0.03	<0.26	<0.23	<0.27	<0.24	<0.19	<0.22	<0.19	<0.18	<0.26	<0.55
METHYLENE CHLORIDE UG/G-DRY	98689 10	<0.27	<0.57	<0.25	<0.23	<0.22	<0.25	<0.23	<0.27	<0.62	<0.52	<0.29	<0.26	<2.5	<0.24	<8.2
1,1,2,2-TETRACHLOROETHANE UG/G-DRY	98793 10	<0.16	<0.07	<0.17	<0.14	<0.01	<0.15	<0.13	<0.15	<0.40	<0.32	<0.44	<0.37	<0.36	<0.15	<0.26
TETRACHLOROETHENE UG/G-DRY	98690 10	<0.39	<0.17	<0.42	<0.36	<0.04	<0.36	<0.33	<0.38	<0.22	<0.17	<0.21	<0.18	<0.17	<0.35	<0.83
TOLUENE UG/G-DRY	98691 10	<0.15	<1.3	<0.17	<0.16	<0.15	<0.13	<0.12	<0.14	<0.17	<0.14	<0.15	<0.13	<0.13	<0.13	<0.26
1,1,1-TRICHLOROETHANE UG/G-DRY	98692 10	<0.30	<0.13	<0.33	<0.28	<0.03	<0.27	<0.24	<0.28	<0.14	<0.11	<0.13	<0.11	<0.10	<0.27	<0.59
1,1,2-TRICHLOROETHANE UG/G-DRY	98693 10	<0.27	<0.11	<0.30	<0.25	<0.03	<0.27	<0.24	<0.28	<0.36	<0.28	<0.31	<0.27	<0.26	<0.24	<0.55
TRICHLOROETHENE UG/G-DRY	98694 10	<0.27	<0.12	<0.30	<0.26	<0.03	<0.26	<0.24	<0.28	<0.22	<0.17	<0.20	<0.17	<0.16	<0.25	<0.58
TRICHLOROFLUOROMETHANE UG/G-DRY	98794 10	<0.26	<0.11	<0.28	<0.24	<0.02	<0.26	<0.24	<0.27	<0.46	<0.37	<0.46	<0.39	<0.38	<0.24	<0.46
VINYL CHLORIDE UG/G-DRY	98795 10	<0.30	<0.11	<0.35	<0.30	<0.03	<0.28	<0.25	<0.29	<0.33	<0.27	<0.30	<0.25	<0.25	<0.28	<0.61
DICHLOROBENZENE,TOTAL UG/G-DRY	98803 10	<0.17	<0.08	<0.20	<0.17	<0.02	<0.16	<0.14	<0.16	<0.10	<0.08	<0.10	<0.08	<0.08	<0.16	<0.37
4-CHLORO-3-METHYLPHENOL MG/KG-DRY	99683 10	<0.07	<0.08	<0.06	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
2-CHLOROPHENOL,SOIL MG/KG-DRY	99497 10	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
2,4-DICHLOROPHENOL,S MG/KG-DRY	99498 10	<0.07	<0.08	<0.06	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
2,4-DIMETHYPHENOL,SO MG/KG-DRY	99499 10	<0.06	<0.07	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
2,4-DINITROPHENOL,SO MG/KG-DRY	99695 10	<0.31	<0.36	<0.29	<0.14	<0.11	<0.17	<0.13	<0.13	<0.24	<0.12	<0.17	<0.12	<0.12	<0.12	<0.13
2-METHYL-4,6-DINITROPHENOL MG/KG-DRY	99686 10	<0.21	<0.25	<0.20	<0.09	<0.07	<0.12	<0.09	<0.09	<0.16	<0.08	<0.11	<0.08	<0.08	<0.08	<0.09

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 3

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSOI PROJECT MANAGER R. BOWEN
NAVHXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6S1A PRSOI 15	R6S2A PRSOI 16	R6S3A PRSOI 17	R6S4A PRSOI 18	R6S5A PRSOI 19	R6S6A PRSOI 20	R6S7A PRSOI 21	R6S8A PRSOI 22	R6S9A PRSOI 23	R6S10A PRSOI 24	R6S11A PRSOI 25	R6S12A PRSOI 26	R6A13A PRSOI 27	R6S14A PRSOI 28	R6S15A PRSOI 29
DATE		12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME		10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
2-NITROPHENOL,SOIL MG/KG-DRY	99495 10	<0.09	<0.10	<0.08	<0.04	<0.04	<0.05	<0.04	<0.04	<0.07	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04
4-NITROPHENOL,SOIL MG/KG-DRY	99496 10	<0.18	<0.20	<0.16	<0.08	<0.06	<0.09	<0.07	<0.07	<0.13	<0.07	<0.09	<0.07	<0.07	<0.07	<0.07
PENTACHLOROPHENOL,SO MG/KG-DRY	99682 10	<0.21	<0.24	<0.19	<0.09	<0.07	<0.11	<0.08	<0.09	<0.16	<0.08	<0.11	<0.08	<0.08	<0.08	<0.09
PHENOL,SO MG/KG-DRY	99685 10	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
2,4,6-TRICHLRPHENOL, S MG/KG-DRY	99684 10	<0.10	<0.12	<0.10	<0.04	<0.04	<0.06	<0.04	<0.04	<0.08	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04
ACENAPHTHENE,SOIL UG/G-DRY	99450 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
ACENAPHTHYLENE,SOIL MG/KG-DRY	99451 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
ANTHRACENE,SOIL MG/KG-DRY	99452 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
BENZO(A)ANTHRACENE,S O MG/KG-DRY	99453 0	<0.05	<0.06	<0.05	<0.04	0.07	0.1	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	0.03	<0.04
BENZO(B)FLUORANTHENE ,S MG/KG-DRY	99454 0	<0.07	<0.09	<0.07	<0.04	0.06	0.2	<0.04	<0.04	<0.06	<0.04	<0.04	<0.04	<0.04	0.04	<0.04
BENZO(K)FLUORANTHENE ,S MG/KG-DRY	99455 0	<0.08	<0.09	<0.07	<0.04	0.04	0.09	<0.04	<0.04	<0.06	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
BENZO(A)PYRENE,SOIL MG/KG-DRY	99456 0	<0.10	<0.1	<0.09	<0.04	0.04	0.2	<0.04	<0.04	<0.07	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04
BENZO(G,H,I)PERYLENE ,SOIL MG/KG-DRY	99691 0	<0.18	<0.20	<0.16	<0.08	<0.06	0.08	<0.07	<0.07	<0.13	<0.07	<0.09	<0.07	<0.07	<0.07	<0.07
BUTYL BENZYL PHTHALA TE MG/KG-DRY	99463 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
BIS(2-CHLRETH)ETHER, SO MG/KG-DRY	99458 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
BIS(2-CHLETHOXY)METH ,S MG/KG-DRY	99459 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
BIS(2-E-H)PHTHALATE, SO MG/KG-DRY	99460 0	<0.05	<0.06	0.05	<0.04	0.06	0.2	0.05	<0.04	0.08	<0.04	<0.04	<0.04	<0.04	0.3	4
BIS(2-CHLISOP)ETHER, SO MG/KG-DRY	99461 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
4-BROMOPHPETHER,SOI L MG/KG-DRY	99462 0	<0.1	<0.1	<0.1	<0.05	<0.04	<0.06	<0.04	<0.05	<0.08	<0.04	<0.06	<0.04	<0.04	<0.04	<0.05
2-CHLRNAPHTHALENE,SO MG/KG-DRY	99464 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6S1A PRS01 15	R6S2A PRS01 16	R6S3A PRS01 17	R6S4A PRS01 18	R6S5A PRS01 19	R6S6A PRS01 20	R6S7A PRS01 21	R6S8A PRS01 22	R6S9A PRS01 23	R6S10A PRS01 24	R6S11A PRS01 25	R6S12A PRS01 26	R6A13A PRS01 27	R6S14A PRS01 28	R6S15A PRS01 29
DATE		12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME		10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
4-CHLRPHPHETHER,SOIL MG/KG-DRY	99465 0	<0.06	<0.07	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
CHRYSENE, SOIL MG/KG-DRY	99690 0	<0.05	<0.06	<0.05	<0.04	0.08	0.1	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	0.04	<0.04
DIBENZO(A,H)ANTHRA,SO MG/KG-DRY	99466 0	<0.2	<0.2	<0.2	<0.08	<0.06	<0.09	<0.07	<0.07	<0.1	<0.07	<0.09	<0.07	<0.06	<0.06	<0.07
DI-N-BUTYL PHTHALATE MG/KG-DRY	99467 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
1,3DICHLRBENZENE,SOIL MG/KG-DRY	99468 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
1,2-DICHLRBENZENE,SO MG/KG-DRY	99470 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
1,4-DICHLRBENZ ,SO MG/KG-DRY	99469 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
3,3-DICHLRBENZIDINE, SO MG/KG-DRY	99471 0	<0.2	<0.2	<0.2	<0.09	<0.07	<0.1	<0.08	<0.08	<0.1	<0.07	<0.1	<0.07	<0.07	<0.07	<0.08
DIETHYLPHTHALATE,SOIL MG/KG-DRY	99472 0	<0.05	<0.06	<0.05	<0.05	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
DIMETHYLPHTHALATE,SO MG/KG-DRY	99473 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
2,4-DNT,SO MG/KG-DRY	99474 0	<0.09	<0.1	<0.08	<0.04	<0.04	<0.05	<0.04	<0.04	<0.07	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04
2,6-DNT,SO MG/KG-DRY	99475 0	<0.1	<0.1	<0.1	<0.05	<0.04	<0.07	<0.05	<0.05	<0.09	<0.05	<0.07	<0.05	<0.05	<0.05	<0.05
DI-N-OCTYL PHTHALATE MG/KG-DRY	99476 0	<0.05	0.1	<0.05	<0.04	0.10	<0.04	0.1	0.2	<0.05	<0.08	<0.04	<0.04	<0.04	0.1	<0.04
FLUORANTHENE,SOIL MG/KG-DRY	99689 0	<0.05	<0.06	<0.05	<0.04	0.06	0.2	0.02	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	0.03	<0.04
FLUORENE, SOIL MG/KG-DRY	99692 0	<0.05	<0.06	<0.05	<0.04	<0.04	<0.03	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
HEXCHLRCYCLPENTADIEN ,S MG/KG-DRY	99481 0	<0.2	<0.2	<0.2	<0.09	<0.07	<0.1	<0.08	<0.08	<0.1	<0.07	<0.1	<0.07	<0.07	<0.07	<0.08
HEXACHLOROBENZENE,SO MG/KG-DRY	99478 0	<0.1	<0.1	<0.10	<0.05	<0.04	<0.06	<0.04	<0.04	<0.08	<0.04	<0.06	<0.04	<0.04	<0.04	<0.04
HEXACHLOROBUTADIENE, S MG/KG-DRY	99479 0	<0.2	<0.2	<0.1	<0.07	<0.05	<0.08	<0.06	<0.06	<0.1	<0.06	<0.08	<0.06	<0.06	<0.06	<0.06
HEXACHLOROETHANE,SOIL MG/KG-DRY	99480 0	<0.1	<0.1	<0.1	<0.05	<0.04	<0.06	<0.05	<0.05	<0.09	<0.05	<0.06	<0.04	<0.04	<0.04	<0.05
INDENO(1,2,3-CD)PYR, SO MG/KG-DRY	99482 0	<0.2	<0.2	<0.1	<0.07	<0.05	0.06	<0.06	<0.07	<0.1	<0.06	<0.09	<0.06	<0.06	<0.06	<0.07

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSO1 PROJECT MANAGER R. BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6S1A PRSO1 15	R6S2A PRSO1 16	R6S3A PRSO1 17	R6S4A PRSO1 18	R6S5A PRSO1 19	R6S6A PRSO1 20	R6S7A PRSO1 21	R6S8A PRSO1 22	R6S9A PRSO1 23	R6S10A PRSO1 24	R6S11A PRSO1 25	R6S12A PRSO1 26	R6A13A PRSO1 27	R6S14A PRSO1 28	R6S15A PRSO1 29
DATE		12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME		10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
ISOPHORONE,SOIL	99483	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
MG/KG-DRY	0															
NAPHTHALENE,SOIL	99696	<0.05	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
MG/KG-DRY	0															
NITROBENZENE,SOIL	99485	<0.048	<0.057	<0.047	<0.044	<0.042	<0.042	<0.037	<0.043	<0.046	<0.039	<0.044	<0.039	<0.035	<0.043	<0.039
UG/G-DRY	0															
N-NITROSODIPROPLAMIN	99487	<0.06	<0.07	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
E MG/KG-DRY	0															
N-NITROSODIMETHLAMIN	99486	<0.06	<0.06	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
E MG/KG-DRY	0															
N-NITROSODIPHENLAMIN	99488	<0.09	<0.1	<0.10	<0.09	<0.09	<0.08	<0.07	<0.09	<0.09	<0.08	<0.09	<0.08	<0.07	<0.09	<0.09
E MG/KG-DRY	0															
PHENANTHRENE,SOIL	99489	<0.05	<0.06	<0.05	<0.04	<0.04	0.03	<0.04	<0.04	<0.05	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04
MG/KG-DRY	0															
PYRENE,SO	99490	<0.05	<0.06	<0.05	<0.04	0.06	0.2	0.02	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	0.03	<0.04
MG/KG-DRY	0															
1,2,4-TRICHLRBENZENE	99492	<0.07	<0.08	<0.06	<0.04	<0.04	<0.04	<0.04	<0.04	<0.05	<0.04	<0.04	<0.04	<0.04	<0.04	<0.04
,S MG/KG-DRY	0															
ALDRIN,SED	98356	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G- DRY	0															
BHC,A,SED	98357	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
BHC,B,SED	98358	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
BHC,D,SED	98359	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
BHC,G,SED	98360	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
CHLORDANE,SED	98361	<1.58	<1.90	<1.55	<1.46	<1.38	<1.40	<1.23	<1.43	<1.54	<1.31	<1.45	<1.31	<1.18	<1.42	<1.29
UG/G- DRY	0															
DDD,PP'	98362	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
DDE,PP'	98363	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
DDT,PP'	98364	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
DIELDRIN	98365	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
ENDOSULFAN,A	98366	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G- DRY	0															

PROJECT NUMBER 05275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6S1A PRS01 15	R6S2A PRS01 16	R6S3A PRS01 17	R6S4A PRS01 18	R6S5A PRS01 19	R6S6A PRS01 20	R6S7A PRS01 21	R6S8A PRS01 22	R6S9A PRS01 23	R6S10A PRS01 24	R6S11A PRS01 25	R6S12A PRS01 26	R6A13A PRS01 27	R6S14A PRS01 28	R6S15A PRS01 29
DATE		12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME		10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
ENDOSULFAN,B	98367	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G- DRY	0															
ENDOSULFAN SULFATE	98368	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
ENDRIN	98369	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY.	0															
ENDRIN ALDEHYDE MG/K	98370	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
G-DRY MG/KG-DRY	0															
HEPTACHLOR	98371	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G- DRY	0															
HEPTACHLOR EPOXIDE	98372	<0.395	<0.475	<0.388	<0.364	<0.346	<0.350	<0.308	<0.358	<0.385	<0.327	<0.364	<0.326	<0.294	<0.354	<0.324
UG/G-DRY	0															
TOXAPHENE	98373	<15.8	<19.0	<15.5	<14.6	<13.8	<14.0	<12.3	<14.3	<15.4	<13.1	<14.5	<13.0	<11.8	<14.2	<12.9
UG/G- DRY	0															
PCB 1016,SED	98140	<0.949	<1.14	<0.930	<0.874	<0.829	<0.839	<0.739	<0.860	<0.924	<0.784	<0.873	<0.783	<0.706	<0.850	<0.777
UG/G-DRY	0															
PCB-1221,SOIL	98351	<0.949	<1.14	<0.930	<0.874	<0.829	<0.839	<0.739	<0.860	<0.924	<0.784	<0.873	<0.783	<0.706	<0.850	<0.777
UG/G-DRY	0															
PCB-1232,SOIL	98352	<0.949	<1.14	<0.930	<0.874	<0.829	<0.839	<0.739	<0.860	<0.924	<0.784	<0.873	<0.783	<0.706	<0.850	<0.777
UG/G- DRY	0															
PCB-1242,SOIL	98353	<0.949	<1.14	<0.930	<0.874	<0.829	<0.839	<0.739	<0.860	<0.924	<0.784	<0.873	<0.783	<0.706	<0.850	<0.777
UG/G-DRY	0															
PCB1254-SOIL	98354	<0.949	<1.14	<0.930	<0.874	<0.829	<0.839	<0.739	<0.860	<0.924	<0.784	<0.873	<0.783	<0.706	<0.850	<0.777
UG/G- DRY	0															
PCB-1248 SOIL	98802	<0.9	<1	<0.9	<0.9	<0.8	<0.8	<0.7	<0.9	<0.9	<0.8	<0.9	<0.8	<0.7	<0.8	<0.8
UG/G-DRY	0															
PCB 1260,SED	98139	<0.949	<1.14	<0.930	<0.874	<0.829	<0.839	<0.739	<0.860	<0.924	<0.784	<0.873	<0.783	<0.706	<0.850	<0.777
UG/G-DRY	0															
ANTIMONY,SED	1098	11	10	10	9.4	18	28	27	51	15	17	9.5	9.1	20	9.4	6.5
MG/KG-DRY	0															
ARSENIC,SED	1003	16.6	57.1	15.9	22.5	35.5	12.7	134	30.9	54.1	35.7	25.5	88.2	<2.63	72.4	34.9
UG/G- DRY	0															
BERYLLIUM,SED	1013	<0.221	1.01	0.276	0.623	1.11	0.289	3.31	2.18	1.17	2.52	1.59	6.14	14.9	1.61	1.39
MG/KG-DRY	0															
CADMIUM,SED	1028	<0.332	2.88	<0.361	<0.323	0.881	0.729	2.41	1.54	1.12	1.69	0.872	2.41	0.762	2.71	0.577
UG/G- DRY	0															
CHROMIUM,SED	1029	16.9	23.7	17.9	17.5	34.9	13.8	39.0	36.0	78.2	39.2	50.0	58.4	75.2	35.2	18.6
UG/G- DRY	0															
COPPER,SED	1043	22.6	50.3	20.6	26.2	380	51.0	823	163	107	383	211	527	383	332	101
UG/G- DRY	0															

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 7

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSOI PROJECT MANAGER R. BOWEN
NAVMXS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	R6S1A	R6S2A	R6S3A	R6S4A	R6S5A	R6S6A	R6S7A	R6S8A	R6S9A	R6S10A	R6S11A	R6S12A	R6A13A	R6S14A	R6S15A
UNITS	METHOD	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI	PRSOI
		15	16	17	18	19	20	21	22	23	24	25	26	27	28	29
DATE		12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85	12/05/85
TIME		10:30	10:45	11:00	11:15	11:30	11:45	12:00	12:15	12:30	12:45	13:00	13:15	13:30	13:45	14:00
LEAD,SED	1052	<6.97	<8.62	<7.59	<6.77	222	<6.13	76.5	92.8	180	3040	568	197	58.0	466	169
UG/G-DRY	0															
MERCURY	71921	0.052	<0.075	<0.061	<0.048	0.714	0.991	0.261	0.136	0.105	1.54	0.356	0.352	<0.041	0.449	0.898
UG/G-DRY	0															
NICKEL,SED	1068	6.32	12.5	6.35	6.59	14.5	5.07	30.3	22.2	56.1	33.4	17.2	68.1	165	32.3	23.3
UG/G- DRY	0															
SELENIUM,SED	1148	13.9	55.8	16.1	21.0	49.3	13.5	80.5	65.1	44.6	93.9	65.4	426	<2.63	68.5	60.0
MG/KG-DRY	0															
SILVER,SED	1078	<0.853	<0.841	<0.819	<0.739	<0.697	<0.831	<0.612	<0.656	<0.885	<0.680	<0.759	<0.629	<0.558	<0.772	<0.692
MG/KG- DRY	0															
THALLIUM,SED	34480	<0.191	<0.224	<0.184	<0.189	<0.162	<0.170	<0.162	<0.191	<0.205	<0.155	<0.191	<0.154	<0.155	<0.178	<0.161
MG/KG- DRY	0															
ZINC,SED	1093	28.3	71.7	31.9	48.2	329	81.5	439	520	339	758	475	949	181	426	210
UG/G-DRY	0															
1,2-DIBROMOETHANE (E	98798	<0.003	<0.004	<0.003	<0.003	<0.003	<0.003	<0.003	<0.003	<0.003	<0.003	<0.003	<0.003	<0.002	<0.003	<0.003
DB) MG/KG-DRY	0															
M-XYLENE	98799	<0.24	<0.04	<0.22	<0.19	<0.02	<0.23	<0.21	<0.24	<0.07	<0.05	<0.06	<0.05	<0.05	<0.22	<0.50
MG/KG-DRY	10															
O,P-XYLENE	98800	<0.10	<0.04	<0.23	<0.19	<0.02	<0.10	<0.09	<0.10	<0.07	<0.05	<0.06	<0.05	<0.05	<0.09	<0.40
MG/KG-DRY	10															

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	R7GW1 PRGW1 10	R7GW2 PRGW1 11	R7GW3 PRGW1 12	R7GW4 PRGW1 13	R7GW5 PRGW1 14	R7GW6 PRGW1 15	R7GW7 PRGW1 16	R7GW8 PRGW1 17
		SAMPLE ID/#							
DATE		02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME		10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
4-CHL'-3-METH'PHENOL	34452	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
2-CHLOROPHENOL	34586	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7
UG/L	10								
2,4-DICHLOROPHENOL	34601	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
2,4-DIMETHYLPHENOL	34606	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
2,4-DINITROPHENOL	34616	<30	<30	<30	<30	<30	<30	<30	<30
UG/L	10								
2-MET'-4,6-DN'PHENOL	34657	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
UG/L	10								
2-NITROPHENOL	34591	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
4-NITROPHENOL	34646	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
UG/L	10								
PENTACHLOROPHENOL	39032	<10	<10	<10	<10	<10	<10	<10	<10
UG/L	10								
PHENOL	34694	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3
UG/L	10								
2,4,6-TRICHL'PHENOL	34621	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8
UG/L	10								
BENZENE	34030	<0.20	<0.20	<0.91	<0.20	<0.20	<0.20	<0.20	<0.20
UG/L	10								
BROMODICHLOROMETHANE	32101	<0.18	<0.19	<0.23	<0.21	<0.21	<0.25	<0.18	<0.19
UG/L	10								
BROMOFORM	32104	<0.53	<0.55	<0.71	<0.63	<0.63	<0.73	<0.55	<0.59
UG/L	10								
BROMOMETHANE	34413	<0.50	<0.52	<0.61	<0.63	<0.59	<0.69	<0.55	<0.59
UG/L	10								
CARBON TETRACHLORIDE	32102	<0.22	<0.23	<0.27	<0.27	<0.26	<0.30	<0.23	<0.25
UG/L	10								
CHLOROBENZENE	34301	<0.13	<0.42	<0.16	<0.15	<0.15	<0.17	89	<0.13
UG/L	10								
CHLOROETHANE	34311	<0.98	<1.0	<1.3	<1.4	<1.2	<1.4	<1.2	<1.3
UG/L	10								
2-CHL'ETH'VINYLETHER	34576	<1.6	<1.7	<2.2	<1.1	<1.9	<2.2	<0.92	<0.99
UG/L	10								
CHLOROFORM	32106	<0.15	<0.15	<0.21	<0.18	<0.18	<0.21	<0.15	<0.16
UG/L	10								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	R7GW1	R7GW2	R7GW3	R7GW4	R7GW5	R7GW6	R7GW7	R7GW8
		SAMPLE ID/#							
UNITS	METHOD	PRGW1 10	PRGW1 11	PRGW1 12	PRGW1 13	PRGW1 14	PRGW1 15	PRGW1 16	PRGW1 17
DATE		02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME		10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
CHLOROMETHANE	34418	<0.32	<0.34	<0.44	<0.40	<0.38	<0.45	<0.35	<0.37
UG/L	10								
DIBROMOCHLOROMETHANE	32105	<0.400	<0.350	<0.442	<0.404	<0.398	<0.465	<0.349	<0.375
UG/L	10								
1,1-DICHLOROETHANE	34496	<0.19	<0.20	<0.28	2.3	<0.23	<0.26	<0.19	<0.21
UG/L	10								
1,2-DICHLOROETHANE	34531	<0.19	<0.19	<0.26	<0.24	<0.22	<0.26	<0.20	<0.22
UG/L	10								
1,1-DICHLOROETHYLENE	34501	<0.42	<0.43	<0.62	<0.48	<0.49	<0.58	<0.42	<0.45
UG/L	10								
T-1,2-DICHLOROETHENE	34546	<0.38	<0.39	<0.55	1.5	<0.44	<0.52	<0.38	<0.41
UG/L	10								
1,2-DICHLOROPROPANE	34541	<0.35	<0.37	<0.50	<0.44	<0.42	<0.49	<0.38	<0.41
UG/L	10								
CIS-1,3-DICH'PROPENE	34704	<0.18	<0.19	<0.84	<0.23	<0.30	<0.25	<0.20	<0.21
UG/L	10								
T-1,3-DICHL'PROPENE	34699	<0.19	<0.20	<0.25	<0.25	<0.23	<0.26	<0.22	<0.23
UG/L	10								
ETHYLBENZENE	34371	<0.23	<0.24	<0.30	<0.27	<0.27	<0.31	<0.23	<0.25
UG/L	10								
METHYLENE CHLORIDE	34423	<4.0	<3.2	<0.45	<1.7	<3.6	<4.1	<2.3	<1.5
UG/L	10								
1,1,2,2-TE'CH'ETHANE	34516	<0.39	<0.41	<0.55	<0.62	<0.47	<0.54	<0.54	<0.58
UG/L	10								
TOLUENE	34010	<0.91	<0.17	<0.22	<0.19	<0.20	<0.23	<0.16	<0.17
UG/L	10								
1,1,1-TRICHL'ETHANE	34506	<0.19	<0.20	<0.26	<0.23	<0.23	<0.27	<0.20	<0.22
UG/L	10								
1,1,2-TRICHL'ETHANE	34511	<0.43	<0.44	<0.50	<0.50	<0.50	<0.59	<0.43	<0.46
UG/L	10								
TRICHLOROETHENE	39180	<0.31	<0.33	<0.43	<0.38	<0.37	<0.43	<0.33	<0.35
UG/L	10								
TRICHL'FLUOROMETHANE	34488	<0.46	<0.47	<0.59	<0.54	<0.54	<0.63	<0.47	<0.50
UG/L	10								
VINYL CHLORIDE	39175	<0.45	<0.47	<0.57	<0.60	<0.53	<0.62	<0.50	<0.54
UG/L	10								
DICHLOROBENZENE,T.	81524	<0.4	<0.4	<0.3	<0.4	<0.4	<0.5	70	<0.4
UG/L	10								
ACENAPHTHENE	34205	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	R7GW1	R7GW2	R7GW3	R7GW4	R7GW5	R7GW6	R7GW7	R7GW8
		SAMPLE ID/#							
UNITS	METHOD	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1
		10	11	12	13	14	15	16	17
DATE		02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME		10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
ACENAPHTHYLENE	34200	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
ANTHRACENE	34220	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
BENZO(A)ANTHRACENE	34526	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
BENZO(B)FLUORANTHENE	34230	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
UG/L	0								
BENZO(K)FLUORANTHENE	34242	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
BENZO(A)PYRENE	34247	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
BENZO(GHI)PERYLENE	34521	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
BUTYL BENZ'PHTHALATE	34292	17	*T0.3	2	5	*T0.6.	3	1	0.7
UG/L	0								
BIS(2-CHL'ETH')ETHER	34273	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
BIS(2-CHL'ETHOX)MTHN	34278	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
BIS(2-ETH'HEX')PHTH.	39100	6	6	1	3	5	2	3	8
UG/L	0								
BIS(2-CHL'ISOPR)ETHR	34283	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
4-BRO'PHEN'PHEN'ETHR	34636	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
2-CHLORONAPHTHALENE	34581	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
4-CHL'PHEN'PHEN'ETHR	34641	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
CHRYSENE	34320	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
DIBEN'(A,H)ANTH'CENE	34556	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
DI-N-BUTYLPHTHALATE	39110	2	0.9	<1	0.7	*T0.3	<1	*T0.3	1
UG/L	0								
1,3,DICHLOROBENZENE	34566	<1	<1	<1	<1	<1	<1	<1	0.7
UG/L	0								
1,2-DICHLOROBENZENE	34536	<1	<1	<1	<1	<1	<1	<1	0.9
UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	R7GW1	R7GW2	R7GW3	R7GW4	R7GW5	R7GW6	R7GW7	R7GW8
		SAMPLE ID/#							
UNITS	METHOD	PRGW1 10	PRGW1 11	PRGW1 12	PRGW1 13	PRGW1 14	PRGW1 15	PRGW1 16	PRGW1 17
DATE		02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME		10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
1,4-DICHLOROBENZENE	34571	<1	<1	<1	1	<1	<1	<1	9
UG/L	0								
3,3'-DICHL'BENZIDINE	34631	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
DIETHYLPHTHALATE	34336	<1	<1	<1	<1	*TO.4	<1	<1	<1
UG/L	0								
DIMETHYLPTHALATE	34341	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
2,4-DINITROTOLUENE	34611	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0								
2,6-DINITROTOLUENE	34626	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0								
DI-N-OCTYL PHTHALATE	34596	1	*TO.6	<1	<1	<1	<1	*TO.5	0.8
UG/L	0								
FLUORANTHENE	34376	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
FLUORENE	34381	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
HEXACH'CYC'PEN'DIENE	34386	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
HEXACHLOROBENZENE	39700	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
HEXACHLOROBUTADIENE	34391	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
HEXACHLOROETHANE	34396	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
INDENO(1,2,3-CD)PYRN	34403	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
ISOPHORONE	34408	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
NAPHTHALENE	34696	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
NITROBENZENE	34447	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0								
N-NITROSODIPRO'AMINE	34428	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
N-NITROSODIMET'AMINE	34438	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
N-NITROSODIPHE'AMINE	34433	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	R7GW1 PRGW1 10	R7GW2 PRGW1 11	R7GW3 PRGW1 12	R7GW4 PRGW1 13	R7GW5 PRGW1 14	R7GW6 PRGW1 15	R7GW7 PRGW1 16	R7GW8 PRGW1 17
		SAMPLE ID/#							
DATE		02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME		10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
PHENANTHRENE UG/L	34461 0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
PYRENE UG/L	34469 0	<1	<1	<1	<1	<1	<1	<1	<1
1,2,4-TRICHL'BENZENE UG/L	34551 0	<1	<1	<1	<1	<1	<1	<1	<1
ALDRIN UG/L	39330 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
BHC,A UG/L	39337 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
BHC,B UG/L	39338 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
BHC-D UG/L	34259 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
BHC,G(LINDANE) UG/L	39340 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
CHLORDANE UG/L	39350 0	<1.25	<1.25	<1.25	<1.25	<1.25	<1.25	<1.25	<1.25
DDD,PP' UG/L	39310 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
DDE,PP' UG/L	39320 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	0.019	<0.013
DDT,PP' UG/L	39300 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
DIELDRIN UG/L	39380 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
ENDOSULFAN,A UG/L	34361 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
ENDOSULFAN,B UG/L	34356 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
ENDOSULFAN SULFATE UG/L	34351 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
ENDRIN UG/L	39390 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
ENDRIN ALDEHYDE UG/L	34366 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
HEPTACHLOR UG/L	39410 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013
HEPTACHLOR EPOXIDE UG/L	39420 0	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013	<0.013

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS	UNITS	STORET # METHOD	R7GW1 PRGW1 10	R7GW2 PRGW1 11	R7GW3 PRGW1 12	R7GW4 PRGW1 13	R7GW5 PRGW1 14	R7GW6 PRGW1 15	R7GW7 PRGW1 16	R7GW8 PRGW1 17
			SAMPLE ID/#							
DATE			02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME			10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
TOXAPHENE		39400	<1.56	<1.56	<1.56	<1.56	<1.56	<1.56	<1.56	<1.56
	UG/L	0								
PCB-1016		34671	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
PCB-1221		39488	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
PCB-1232		39492	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
PCB-1242		39496	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
PCB 1248		39500	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
PCB-1254		39504	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
PCB-1260		39508	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
	UG/L	0								
ANTIMONY,TOTAL		1097	<30.0	<30.0	<24.0	<30.0	<30.0	<30.0	<30.0	<30.0
	UG/L	0								
ARSENIC,TOTAL		1002	73.6	58.6	121	87.0	84.9	93.9	46.1	120
	UG/L	0								
BERYLLIUM,T,		1012	3.12	<3.00	<3.00	<3.00	<3.00	11.3	4.16	6.65
	UG/L	0								
CADMIUM,TOTAL		1027	<3.00	<3.00	<3.00	<3.00	<3.00	<3.00	<3.00	<3.00
	UG/L	0								
CHROMIUM,TOTAL		1034	15.9	6.89	30.8	8.72	15.9	22.3	11.3	57.7
	UG/L	0								
COPPER,TOTAL		1042	42.9	5.18	73.5	4.56	23.2	135	33.0	42.8
	UG/L	0								
LEAD,TOTAL		1051	<27.0	<27.0	<24.0	<27.0	424	<27.0	<27.0	<27.0
	UG/L	0								
MERCURY,TOTAL		71900	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500	<0.500
	UG/L	0								
NICKEL,T,		1067	11.5	<6.00	14.3	10.2	10.0	13.5	12.2	18.7
	UG/L	0								
SELENIUM,TOTAL		1147	<36.0	<36.0	<21.0	<36.0	<36.0	88.9	<36.0	<36.0
	UG/L	0								
SILVER,TOTAL		1077	<6.00	<6.00	<3.00	<6.00	<6.00	<6.00	<6.00	<6.00
	UG/L	0								
THALLIUM,TOTAL		1059	187	187	1780	31.2	31.5	60.6	4.57	10.9
	UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRW2 LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# R7GW1 PRGW1 10	R7GW2 PRGW1 11	R7GW3 PRGW1 12	R7GW4 PRGW1 13	R7GW5 PRGW1 14	R7GW6 PRGW1 15	R7GW7 PRGW1 16	R7GW8 PRGW1 17
DATE		02/24/86	02/24/86	02/27/86	02/25/86	02/26/86	02/26/86	02/25/86	02/25/86
TIME		10:38	13:00	09:00	09:49	10:20	11:30	12:40	13:23
ZINC,TOTAL	1092	95.6	53.2	50.0	62.7	225	103	64.0	52.2
UG/L	0								
PH,FIELD	400	6.90	7.32	6.69	6.89	6.81	6.83	7.61	7.05
STD UNITS	0								
TETRACHLOROETHENE	34475	<0.40	<0.42	<0.51	<0.46	<0.47	<0.55	<0.40	<0.43
UG/L	10								
CHROMIUM,(+6)	1032	<20.0	<20.0	<20.0	46.0	<20.0	<20.0	<20.0	<20.0
UG/L	0								

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/13/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVNPS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R7S1N PRS01 30	R7S2N PRS01 31	R7S2N2 PRS01 107
DATE			11/29/85	11/29/85	11/29/85
TIME			07:45	09:05	09:15
MOISTURE		70320	10.1	14.6	14.1
	%WET WT	0			
OIL&GR.IR.SED		561	198	80	127
	UG/G- DRY	0			
BENZENE		98699	<0.08	<0.09	<0.14
	UG/G-DRY	10			
BROMODICHLOROMETHANE		98783	<0.10	<0.11	<0.29
	UG/G-DRY	10			
BROMOFORM		98784	<0.22	<0.26	<0.58
	UG/G-DRY	10			
BROMOMETHANE		98785	<0.27	<0.23	<0.63
	UG/G-DRY	10			
CARBON TETRACHLORIDE		98680	<0.09	<0.09	<0.56
	UG/G-DRY	10			
CHLOROBENZENE		98681	<0.07	<0.08	<0.22
	UG/G-DRY	10			
CHLOROETHANE		98786	<0.51	<0.49	<0.88
	UG/G-DRY	10			
2-CHLOROETHYLVINYLET		98796	<0.96	<0.52	<0.55
HER	UG/G-DRY	10			
CHLOROFORM		98682	<0.082	<0.094	<0.267
	UG/G-DRY	10			
CHLOROMETHANE		98787	<0.25	<0.23	<0.62
	UG/G-DRY	10			
DIBROMOCHLOROMETHANE		98788	<0.14	<0.18	<0.47
	UG/G-DRY	10			
1,1-DICHLOROETHANE		98683	<0.13	<0.15	<0.23
	UG/G-DRY	10			
1,2-DICHLOROETHANE		98684	<0.11	<0.12	<0.44
	UG/G-DRY	10			
1,1-DICHLOROETHENE		98789	<0.24	<0.26	<0.53
	UG/G-DRY	10			
TRANS-1,2-DICHLOROET		98687	<0.23	<0.24	<0.48
ENE	UG/G-DRY	10			
1,2-DICHLOROPROPANE		98790	<0.23	<0.31	<0.31
	UG/G-DRY	10			
CIS-1,3-DICHLOROPROP		98791	<0.09	<0.12	<0.20
ENE	UG/G-DRY	10			
TRANS-1,3-DICHLOROPR		98792	<0.09	<0.12	<0.55
OPENE	UG/G-DRY	10			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVNPS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R7S1N PRS01 30	R7S2N PRS01 31	R7S2N2 PRS01 107
DATE		11/29/85	11/29/85	11/29/85
TIME		07:45	09:05	09:15
ETHYLBENZENE UG/G-DRY	98688 10	<0.16	<0.17	<0.49
METHYLENE CHLORIDE UG/G-DRY	98689 10	<0.19	<1.2	<0.52
1,1,2,2-TETRACHLOROETHANE UG/G-DRY	98793 10	<0.29	<0.35	<0.24
TETRACHLOROETHENE UG/G-DRY	98690 10	<0.15	<0.17	<0.75
TOLUENE UG/G-DRY	98691 10	<0.11	<0.12	<0.23
1,1,1-TRICHLOROETHANE UG/G-DRY	98692 10	<0.10	<0.10	<0.53
1,1,2-TRICHLOROETHANE UG/G-DRY	98693 10	<0.21	<0.26	<0.49
TRICHLOROETHENE UG/G-DRY	98694 10	<0.14	<0.16	<0.52
TRICHLOROFLUOROMETHANE UG/G-DRY	98794 10	<0.36	<0.36	<0.41
VINYL CHLORIDE UG/G-DRY	98795 10	<0.23	<0.20	<0.55
DICHLOROBENZENE,TOTAL UG/G-DRY	98803 10	<0.08	<0.08	<0.33
METHYL ETHYL KETONE UG/G-DRY	98801 10	<0.69	<0.82	<2.2
MIBK UG/G-DRY	98696 10	<0.54	<0.65	<0.92
1,2-DIBROMOETHANE (EDB) MG/KG-DRY	98798 0	<0.002	<0.002	<0.002
M-XYLENE MG/KG-DRY	98799 10	<0.06	<0.05	<0.45
O,P-XYLENE MG/KG-DRY	98800 10	<0.05	<0.05	<0.36

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 05275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
PRW1 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8SW1 PRSW1 14	8SW2 PRSW1 15	8SW3 PRSW1 16
DATE			01/05/86	01/09/86	01/09/86
TIME			09:45	10:30	11:00
BENZENE		34030	<0.20	<0.26	<0.25
	UG/L	10			
BROMODICHLOROMETHANE		32101	<0.55	<0.57	<0.56
	UG/L	10			
BROMOFORM		32104	<1.1	<1.2	<1.1
	UG/L	10			
BROMOMETHANE		34413	<1.0	<1.1	<1.1
	UG/L	10			
CARBON TETRACHLORIDE		32102	<0.86	<0.90	<0.87
	UG/L	10			
CHLOROBENZENE		34301	<0.39	<0.41	<0.40
	UG/L	10			
CHLOROETHANE		34311	<1.4	<1.5	<1.4
	UG/L	10			
2-CHL'ETH'VINYLETHER		34576	<0.99	<1.0	<1.0
	UG/L	10			
CHLOROFORM		32106	<0.45	<0.47	<0.45
	UG/L	10			
CHLOROMETHANE		34418	<3.3	<3.5	<3.4
	UG/L	10			
DIBROMOCHLOROMETHANE		32105	<0.792	<0.828	<0.805
	UG/L	10			
1,1-DICHLOROETHANE		34496	<0.32	<0.32	<0.32
	UG/L	10			
1,2-DICHLOROETHANE		34531	<0.82	<0.86	<0.83
	UG/L	10			
1,1-DICHLOROETHYLENE		34501	<0.91	<0.95	<0.92
	UG/L	10			
T-1,2-DICHLOROETHENE		34546	<0.91	<0.95	<0.92
	UG/L	10			
1,2-DICHLOROPROPANE		34541	<0.51	<0.54	<0.52
	UG/L	10			
CIS-1,3-DICH'PROPENE		34704	<0.38	<0.39	<0.38
	UG/L	10			
T-1,3-DICHL'PROPENE		34699	<1.1	<1.1	<1.1
	UG/L	10			
ETHYLBENZENE		34371	<0.97	<1.0	<0.99
	UG/L	10			
METHYLENE CHLORIDE		34423	<3.6	<1.9	<0.60
	UG/L	10			

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
PRWI LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	8SW1 PRSWI	8SW2 PRSWI	8SW3 PRSWI
UNITS	METHOD	14	15	16
DATE		01/09/86	01/09/86	01/09/86
TIME		09:45	10:30	11:00
1,1,2,2-TE'CH'ETHANE	34516	<0.47	<0.50	<0.48
UG/L	10			
TOLUENE	34010	<0.38	<0.38	<0.38
UG/L	10			
1,1,1-TRICHL'ETHANE	34506	<0.93	<0.98	<0.95
UG/L	10			
1,1,2-TRICHL'ETHANE	34511	<0.88	<0.92	<0.90
UG/L	10			
TRICHLOROETHENE	39180	<0.90	<0.94	<0.92
UG/L	10			
TRICHL'FLUOROMETHANE	34488	<0.76	<0.80	<0.78
UG/L	10			
VINYL CHLORIDE	39175	<0.92	<0.97	<0.94
UG/L	10			
1,2-DIBR'ETHANE(EDB)	77651	<0.010	<0.010	<0.010
UG/L	0			
M-XYLENE	98553	<0.69	<0.72	<0.70
UG/L	10			
OIL&GR,IR	560	5	102	98
MG/L	0			
LEAD,TOTAL	1051	<24.0	<24.0	<24.0
UG/L	0			
METHYL ETHYL KETONE	81595	<3.8	<6.7	<3.9
UG/L	10			
METHYL ISOBUT'KETONE	81596	<0.47	<0.47	<0.47
UG/L	10			
O-AND/OR-P XYLENE	98554	<0.73	<0.76	<0.74
UG/L	10			
DICHLOROBENZENE,T.	81524	<0.6	<0.6	<0.6
UG/L	10			
TETRACHLOROETHENE	34475	<1.3	<1.4	<1.3
UG/L	10			

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS3 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8SE1 PRSE1 17	8SE2 PRSE1 18	8SE3 PRSE1 19
DATE			01/09/86	01/09/86	01/09/86
TIME			09:45	10:30	11:00
BENZENE	UG/G-DRY	98699 10	<0.14	<0.10	<0.15
BROMODICHLOROMETHANE	UG/G-DRY	98783 10	<0.30	<0.21	<0.33
BROMOFORM	UG/G-DRY	98784 10	<0.65	<0.45	<0.71
BROMOMETHANE	UG/G-DRY	98785 10	<0.61	<0.42	<0.67
CARBON TETRACHLORIDE	UG/G-DRY	98680 10	<0.50	<0.35	<0.55
CHLOROBENZENE	UG/G-DRY	98681 10	<0.24	<0.16	<0.26
CHLOROETHANE	UG/G-DRY	98786 10	<0.81	<0.56	<0.90
2-CHLOROETHYLVINYLETHER	UG/G-DRY	98796 10	<0.65	<0.45	<0.72
CHLOROFORM	UG/G-DRY	98682 10	<0.266	<0.185	<0.293
CHLOROMETHANE	UG/G-DRY	98787 10	<0.50	<0.35	<0.55
DIBROMOCHLOROMETHANE	UG/G-DRY	98788 10	<0.50	<0.35	<0.55
1,1-DICHLOROETHANE	UG/G-DRY	98683 10	<0.24	<0.16	<0.26
1,2-DICHLOROETHANE	UG/G-DRY	98684 10	<0.47	<0.32	<0.51
1,1-DICHLOROETHENE	UG/G-DRY	98769 10	<0.53	<0.36	<0.58
TRANS-1,2-DICHLOROETENE	UG/G-DRY	98687 10	<0.49	<0.34	<0.53
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.33	<0.23	<0.36
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.22	<0.24	<0.24
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.59	<0.40	<0.64
ETHYLBENZENE	UG/G-DRY	98688 10	<0.53	<0.37	<0.59
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.48	<0.34	<0.51

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS3 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8SE1 PRSE1 17	8SE2 PRSE1 18	8SE3 PRSE1 19
DATE-TIME			01/09/86 09:45	01/09/86 10:30	01/09/86 11:00
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.29	<0.20	<0.32
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.77	<0.53	<0.85
TOLUENE	UG/G-DRY	98691 10	<0.24	<0.17	<0.26
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.50	<0.35	<0.55
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.56	<0.38	<0.61
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.53	<0.37	<0.58
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.43	<0.30	<0.47
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.50	<0.35	<0.55
1,2-DIBROMOETHANE (EDB)	MG/KG-DRY	98798 0	<0.004	<0.003	<0.004
M-XYLENE	MG/KG-DRY	90799 10	<0.42	<0.29	<0.46
O,P-XYLENE	MG/KG-DRY	98800 10	<0.42	<0.29	<0.46
OIL&GR,IR,SED	UG/G- DRY	561 0	4740	787	1670
LEAD,SED	UG/G-DRY	1052 0	28.8	<3.77	43.4
MOISTURE	%WET WT	70320 0	50.3	29.0	53.2
METHYL ETHYL KETONE	UG/G-DRY	98801 10	<4.6	<4.1	<6.2
MIBK	UG/G-DRY	98696 10	<0.60	<0.42	<0.66
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.39	<0.27	<0.43

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
PRS3 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8S1A PRS01 32
DATE			01/09/86
TIME			09:00
BENZENE		98699	<0.09
	UG/G-DRY	10	
BROMODICHLOROMETHANE		98783	<0.19
	UG/G-DRY	10	
BROMOFORM		98784	<0.41
	UG/G-DRY	10	
BROMOMETHANE		98785	<0.39
	UG/G-DRY	10	
CARBON TETRACHLORIDE		98600	<0.32
	UG/G-DRY	10	
CHLOROBENZENE		98681	<0.15
	UG/G-DRY	10	
CHLOROETHANE		98786	<0.52
	UG/G-DRY	10	
2-CHLOROETHYLVINYLET		98796	<0.41
HER	UG/G-DRY	10	
CHLOROFORM		98682	<0.169
	UG/G-DRY	10	
CHLOROMETHANE		98787	<0.32
	UG/G-DRY	10	
DIBROMOCHLOROMETHANE		98788	<0.32
	UG/G-DRY	10	
1,1-DICHLOROETHANE		98683	<0.16
	UG/G-DRY	10	
1,2-DICHLOROETHANE		98684	<0.30
	UG/G-DRY	10	
1,1-DICHLOROETHENE		98789	<0.34
	UG/G-DRY	10	
TRANS-1,2-DICHLOROET		98687	<0.31
ENE	UG/G-DRY	10	
1,2-DICHLOROPROPANE		98790	<0.21
	UG/G-DRY	10	
CIS-1,3-DICHLOROPROP		98791	<0.14
ENE	UG/G-DRY	10	
TRANS-1,3-DICHLOROPR		98792	<0.37
OPENE	UG/G-DRY	10	
ETHYLBENZENE		98688	<0.34
	UG/G-DRY	10	
METHYLENE CHLORIDE		98689	<0.32
	UG/G-DRY	10	

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
PRS3 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8S1A PRS01 32
DATE			01/09/86
TIME			09:00
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.18
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.49
TOLUENE	UG/G-DRY	98691 10	<0.16
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.32
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.35
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.34
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.28
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.32
1,2-DIBROMOETHANE (EDB)	MG/KG-DRY	98798 0	<0.003
M-XYLENE	MG/KG-DRY	98799 10	<0.27
O,P-XYLENE	MG/KG-DRY	98800 10	<0.27
OIL&GR,IR,SED	UG/G- DRY	561 0	821
LEAD,SED	UG/G-DRY	1052 0	6.70
MOISTURE	%WET WT	70320 0	25.6
METHYL ETHYL KETONE	UG/G-DRY	98801 10	<4.2
MIBK	UG/G-DRY	98696 10	<0.40
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.25

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
NAVPCW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	9SW1 PRSW1 17	9SW2 PRSW1 18	9SW3 PRSW1 19	9SW4 PRSW1 20
DATE			12/02/85	12/02/85	12/02/85	12/02/85
TIME			08:30	08:45	09:30	10:00
PCB-1016		34671	<0.206	<0.206	<0.206	<0.206
	UG/L	0				
PCB-1221		39488	<0.430	<0.430	<0.430	<0.430
	UG/L	0				
PCB-1232		39492	<0.333	<0.333	<0.333	<0.333
	UG/L	0				
PCB-1242		39496	<0.286	<0.286	<0.286	<0.286
	UG/L	0				
PCB 1248		39500	<0.197	<0.197	<0.197	<0.197
	UG/L	0				
PCB-1254		39504	<0.224	<0.224	<0.224	<0.224
	UG/L	0				
PCB-1260		39500	<0.358	<0.358	<0.358	<0.358
	UG/L	0				

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVPMS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	9SE1A	9SE1B	9SE1C	9SE2A	9SE2B	9SE2C	9SE3A	9SE3B	9SE3C	9SE4A	9SE4B	9SE4C	9SE5A	9SE5B	9SE5C
		SAMPLE ID/#														
UNITS	METHOD	PRSE1 20	PRSE1 21	PRSE1 22	PRSE1 23	PRSE1 24	PRSE1 25	PRSE1 26	PRSE1 27	PRSE1 28	PRSE1 29	PRSE1 30	PRSE1 31	PRSE1 32	PRSE1 33	PRSE1 34
DATE		12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85
TIME		09:40	09:40	09:40	10:00	10:00	10:00	10:20	10:20	10:20	10:40	10:40	10:40	11:00	11:00	11:00
PCB 1016,SED	98140	<1.16	<1.70	<1.58	<1.92	<1.75	<1.58	<2.04	<1.87	<2.26	<2.26	<1.74	<1.43	<2.30	<1.76	<1.75
UG/G-DRY	0															
PCB-1221,SOIL	98351	<1.16	<1.70	<1.58	<1.92	<1.75	<1.58	<2.04	<1.87	<2.26	<2.26	<1.74	<1.43	<2.30	<1.76	<1.75
UG/G-DRY	0															
PCB-1232,SOIL	98352	<1.16	<1.70	<1.58	<1.92	<1.75	<1.58	<2.04	<1.87	<2.26	<2.26	<1.74	<1.43	<2.30	<1.76	<1.75
UG/G- DRY	0															
PCB-1242,SOIL	98353	<1.16	<1.70	<1.58	<1.92	<1.75	<1.58	<2.04	<1.87	<2.26	<2.26	<1.74	<1.43	<2.30	<1.76	<1.75
UG/G-DRY	0															
PCB1254-SOIL	98354	<1.16	<1.70	<1.58	<1.92	<1.75	<1.58	<2.04	<1.87	<2.26	<2.26	<1.74	<1.43	<2.30	<1.76	<1.75
UG/G- DRY	0															
PCB-1248 SOIL	98802	<1	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	<1	<2	<2	<2
UG/G-DRY	0															
PCB 1260,SED	98139	<1.16	<1.70	<1.58	<1.92	<1.75	<1.58	<2.04	<1.87	<2.26	<2.26	<1.74	<1.43	<2.30	<1.76	<1.75
UG/G-DRY	0															
MOISTURE	70320	48.1	41.0	36.8	48.0	42.8	36.9	50.9	46.5	55.7	55.7	42.7	30.0	56.4	43.1	42.7
%WET WT	0															

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 2

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVPMS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	9SE6A	9SE6B	9SE6C	9SE7A	9SE7B	9SE7C	9SE8A	9SE8B	9SE8C	9SE9A	9SE9B	9SE9C	9SE10A	9SE10B	9SE10C
		SAMPLE ID/#														
UNITS	METHOD	PRSE1 35	PRSE1 36	PRSE1 37	PRSE1 38	PRSE1 39	PRSE1 40	PRSE1 41	PRSE1 42	PRSE1 43	PRSE1 44	PRSE1 45	PRSE1 46	PRSE1 47	PRSE1 48	PRSE1 49
DATE		12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85	12/02/85
TIME		11:20	11:20	11:20	11:40	11:40	11:40	12:00	12:00	12:00	12:20	12:20	12:20	12:40	12:40	12:40
PCB 1016,SED	98140	<2.07	<1.63	<1.53	<2.23	<1.92	<1.71	<2.26	<1.89	<1.94	<2.07	<1.96	<1.88	<2.17	<1.90	<1.77
UG/G-DRY	0															
PCB-1221,SOIL	98351	<2.07	<1.63	<1.53	<2.23	<1.92	<1.71	<2.26	<1.89	<1.94	<2.07	<1.96	<1.88	<2.17	<1.90	<1.77
UG/G-DRY	0															
PCB-1232,SOIL	98352	<2.07	<1.63	<1.53	<2.23	<1.92	<1.71	<2.26	<1.89	<1.94	<2.07	<1.96	<1.88	<2.17	<1.90	<1.77
UG/G- DRY	0															
PCB-1242,SOIL	98353	<2.07	<1.63	<1.53	<2.23	<1.92	<1.71	<2.26	<1.89	<1.94	<2.07	<1.96	<1.88	<2.17	<1.90	<1.77
UG/G-DRY	0															
PCB1254-SOIL	98354	<2.07	<1.63	<1.53	<2.23	<1.92	<1.71	<2.26	<1.89	<1.94	<2.07	<1.96	<1.88	<2.17	<1.90	<1.77
UG/G- DRY	0															
PCB-1248 SOIL	98002	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2	<2
UG/G-DRY	0															
PCB 1260,SED	98139	<2.07	<1.63	<1.53	<2.23	<1.92	<1.71	<2.26	<1.89	<1.94	<2.07	<1.96	<1.88	<2.17	<1.90	<1.77
UG/G-DRY	0															
MOISTURE	70320	51.6	38.7	34.6	55.2	47.8	41.5	55.8	47.0	48.3	51.7	48.9	46.7	53.9	47.3	43.6
%WET WT	0															

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/13/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	10GW1 PRGWI 18	10GW2 PRGWI 19	10GW3 PRGWI 20	10GW4 PRGWI 21	10GW5 PRGWI 22	10GW6 PRGWI 23	10GW7 PRGWI 24	10GW8 PRGWI 25
		SAMPLE ID/#							
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
1,2-DIBR'ETHANE(EDB) UG/L	77651 0	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020
PH,FIELD STD UNITS	400 0	6.16	7.30	6.86	7.40	7.21	6.85	7.52	7.57
CHROMIUM,(+6) UG/L	1032 0	<20.0	<20.0	<20.0	<20.0	<20.0	42.9	<20.0	<20.0
METHYL ETHYL KETONE UG/L	81595 10	<5.0	<5.1	<5.2	9.3	<5.4	<5.9	<5.9	<5.8
METHYL ISOBUT'KETONE UG/L	81596 10	<0.57	<0.57	<0.57	<0.60	<0.57	<0.57	<0.57	<0.57
BENZENE UG/L	34030 10	<0.23	<0.24	<0.24	<0.23	<0.25	<0.23	<0.23	<0.22
BROMODICHLOROMETHANE UG/L	32101 10	<0.47	<0.48	<0.49	<0.47	<0.50	<0.46	<0.46	<0.45
BROMOFORM UG/L	32104 10	<1.0	<1.0	<1.1	<1.0	<1.1	<1.00	<0.99	<0.97
BROMOMETHANE UG/L	34413 10	<0.91	<0.93	<0.95	<0.92	<0.98	<0.91	<0.90	<0.88
CARBON TETRACHLORIDE UG/L	32102 10	<0.85	<0.87	<0.89	<0.81	<0.91	<0.79	<0.79	<0.77
CHLOROBENZENE UG/L	34301 10	<0.38	<0.38	<0.39	<0.35	<0.40	<0.35	<0.34	<0.34
CHLOROETHANE UG/L	34311 10	<1.4	<1.4	<1.5	<1.4	<1.5	<1.3	<1.3	<1.3
2-CHL'ETH'VINYLETHER UG/L	34576 10	<1.1	<1.1	<1.2	<1.1	<1.2	<1.1	<1.1	<1.1
CHLOROFORM UG/L	32106 10	<0.42	<0.43	<0.44	<0.41	<0.45	<0.40	<0.40	<0.39
CHLOROMETHANE UG/L	34418 10	<1.7	<1.7	<1.7	<1.0	<1.8	<0.98	<0.98	<0.96
DIBROMOCHLOROMETHANE UG/L	32105 10	<0.833	<0.851	<0.870	<0.784	<0.891	<0.770	<0.766	<0.747
1,1-DICHLOROETHANE UG/L	34496 10	<0.39	<0.39	<0.40	<0.37	<0.41	<0.37	<0.37	<0.36
1,2-DICHLOROETHANE UG/L	34531 10	<0.76	<0.78	<0.79	<0.74	<0.81	<0.73	<0.73	<0.71
1,1-DICHLOROETHYLENE UG/L	34501 10	<0.83	<0.85	<0.87	<0.82	<0.89	<0.80	<0.80	<0.78
1-1,2-DICHLOROETHENE UG/L	34546 10	<0.73	<0.75	<0.76	<0.73	<0.78	<0.71	<0.71	<0.69

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	10GW1	10GW2	10GW3	10GW4	10GW5	10GW6	10GW7	10GW8
		SAMPLE ID/#							
UNITS	METHOD	PRGWI 18	PRGWI 19	PRGWI 20	PRGWI 21	PRGWI 22	PRGWI 23	PRGWI 24	PRGWI 25
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
1,2-DICHLOROPROPANE	34541	<0.54	<0.56	<0.57	<0.53	<0.58	<0.52	<0.52	<0.50
UG/L	10								
CIS-1,3-DICH'PROPENE	34704	<0.37	<0.38	<0.39	<0.36	<0.40	<0.36	<0.35	<0.35
UG/L	10								
T-1,3-DICHL'PROPENE	34699	<1.0	<1.1	<1.1	<0.97	<1.1	<0.95	<0.95	<0.93
UG/L	10								
ETHYLBENZENE	34371	<0.80	<0.82	<0.84	<0.77	<0.86	<0.75	<0.75	<0.73
UG/L	10								
METHYLENE CHLORIDE	34423	<0.65	<0.65	<0.66	<0.80	<0.70	<0.80	<0.80	<0.80
UG/L	10								
1,1,2,2-TE'CH'ETHANE	34516	<0.47	<0.48	<0.49	<0.48	<0.50	<0.47	<0.47	<0.46
UG/L	10								
TOLUENE	34010	<0.30	<0.30	<0.40	<0.30	<0.30	<0.30	<0.30	<0.30
UG/L	10								
1,1,1-TRICHL'ETHANE	34506	<0.76	<0.78	<0.79	<0.74	<0.81	<0.73	<0.73	<0.71
UG/L	10								
1,1,2-TRICHL'ETHANE	34511	<0.84	<0.86	<0.88	<0.87	<0.90	<0.85	<0.85	<0.83
UG/L	10								
TRICHLOROETHENE	39180	<0.83	<0.85	<0.87	<0.80	<0.89	<0.78	<0.78	<0.76
UG/L	10								
TRICHL'FLUOROMETHANE	34488	<0.74	<0.76	<0.78	<0.77	<0.80	<0.75	<0.75	<0.73
UG/L	10								
VINYL CHLORIDE	39175	<0.91	<0.93	<0.95	<0.89	<0.98	<0.87	<0.87	<0.85
UG/L	10								
DICHLOROBENZENE,T.	81524	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
UG/L	10								
4-CHL'-3-METH'PHENOL	34452	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
2-CHLOROPHENOL	34586	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7
UG/L	10								
2,4-DICHLOROPHENOL	34601	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
2,4-DIMETHYLPHENOL	34606	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								
2,4-DINITROPHENOL	34616	<30	<30	<30	<30	<30	<30	<30	<30
UG/L	10								
2-MET'-4,6-DN'PHENOL	34657	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
UG/L	10								
2-NITROPHENOL	34591	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	10								

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/13/86 STATUS: FINAL PAGE# 3

PROJECT NUMBER 05275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	10GW1 PRGW1 18	10GW2 PRGW1 19	10GW3 PRGW1 20	10GW4 PRGW1 21	10GW5 PRGW1 22	10GW6 PRGW1 23	SAMPLE ID/# 10GW7 PRGW1 24	10GW8 PRGW1 25
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
4-NITROPHENOL UG/L	34646 10	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
PENTACHLOROPHENOL UG/L	39032 10	<10	<10	<10	<10	<10	<10	<10	<10
PHENOL UG/L	34694 10	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3
2,4,6-TRICHL'PHENOL UG/L	34621 10	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8
ACENAPHTHENE UG/L	34205 0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
ACENAPHTHYLENE UG/L	34200 0	<1	<1	<1	<1	<1	<1	<1	<1
ANTHRACENE UG/L	34220 0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BENZO(A)ANTHRACENE UG/L	34526 0	<1	<1	<1	<1	<1	<1	<1	<1
BENZO(B)FLUORANTHENE UG/L	34230 0	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50	<1.50
BENZO(K)FLUORANTHENE UG/L	34242 0	<2	<2	<2	<2	<2	<2	<2	<2
BENZO(A)PYRENE UG/L	34247 0	<2	<2	<2	<2	<2	<2	<2	<2
BENZO(GHI)PERYLENE UG/L	34521 0	<2	<2	<2	<2	<2	<2	<2	<2
BUTYL BENZ'PHTHALATE UG/L	34292 0	3	16	40	4	11	20	16	15
BIS(2-CHL'ETH')ETHER UG/L	34273 0	<1	<1	<1	<1	<1	<1	<1	<1
BIS(2-CHL'ETHOX)MTHN UG/L	34278 0	<1	<1	<1	<1	<1	<1	<1	<1
BIS(2-ETH'HEX')PHTH. UG/L	39100 0	3	<1	<1	<1	<1	<1	<1	<1
BIS(2-CHL'ISOPR)ETHR UG/L	34283 0	<1	<1	<1	<1	<1	<1	<1	<1
4-BRO'PHEN'PHEN'ETHR UG/L	34636 0	<1	<1	<1	<1	<1	<1	<1	<1
2-CHLORONAPHTHALENE UG/L	34581 0	<1	<1	<1	<1	<1	<1	<1	<1
4-CHL'PHEN'PHEN'ETHR UG/L	34641 0	<1	<1	<1	<1	<1	<1	<1	<1

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	10GW1	10GW2	10GW3	10GW4	10GW5	10GW6	10GW7	10GW8
		SAMPLE ID/#							
UNITS	METHOD	PRGW1 18	PRGW1 19	PRGW1 20	PRGW1 21	PRGW1 22	PRGW1 23	PRGW1 24	PRGW1 25
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
CHRYSENE	34320	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
DIBEN'(A,H)ANTH'CENE	34556	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
DI-N-BUTYLPHTHALATE	39110	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
1,3,DICHLOROBENZENE	34566	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
1,2-DICHLOROBENZENE	34536	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
1,4-DICHLOROBENZENE	34571	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
3,3'-DICHL'BENZIDINE	34631	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
DIETHYLPHTHALATE	34336	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
DIMETHYLPTHALATE	34341	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
2,4-DINITROTOLUENE	34611	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0								
2,6-DINITROTOLUENE	34626	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0								
DI-N-OCTYL PHTHALATE	34596	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
FLUORANTHENE	34376	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
FLUORENE	34381	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
HEXACH'CYC'PEN'DIENE	34386	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
HEXACHLOROBENZENE	39700	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
HEXACHLOROBUTADIENE	34391	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
HEXACHLOROETHANE	34396	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
INDENO(1,2,3-CD)PYRN	34403	<2	<2	<2	<2	<2	<2	<2	<2
UG/L	0								
ISOPHORONE	34408	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	10GW1 PRGW1 18	10GW2 PRGW1 19	10GW3 PRGW1 20	10GW4 PRGW1 21	10GW5 PRGW1 22	10GW6 PRGW1 23	10GW7 PRGW1 24	10GW8 PRGW1 25
		SAMPLE ID/#							
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
NAPHTHALENE	34696	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
NITROBENZENE	34447	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00	<1.00
UG/L	0								
N-NITROSODIPRO'AMINE	34428	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
N-NITROSODIMET'AMINE	34438	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
N-NITROSODIPHE'AMINE	34433	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
PHENANTHRENE	34461	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	0								
PYRENE	34469	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
1,2,4-TRICHL'BENZENE	34551	<1	<1	<1	<1	<1	<1	<1	<1
UG/L	0								
ALDRIN	39330	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
BHC,A	39337	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
BHC,B	39338	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
BHC-D	34259	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
BHC,G(LINDANE)	39340	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
CHLORDANE	39350	<1.25	<1.25	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
DDD,PP'	39310	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
DDE,PP'	39320	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
DDT,PP'	39300	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
DIELDRIN	39380	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
ENDOSULFAN,A	34361	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
ENDOSULFAN,B	34356	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 05275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGWI PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	10GW1 PRGWI 18	10GW2 PRGWI 19	10GW3 PRGWI 20	10GW4 PRGWI 21	10GW5 PRGWI 22	10GW6 PRGWI 23	10GW7 PRGWI 24	10GW8 PRGWI 25
		SAMPLE ID/#							
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
ENDOSULFAN SULFATE	34351	<0.125	<0.125	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
ENDRIN	39390	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
ENDRIN ALDEHYDE	34366	<0.125	<0.125	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
HEPTACHLOR	39410	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
HEPTACHLOR EPOXIDE	39420	<0.031	<0.031	<0.063	<0.063	<0.063	<0.063	<0.063	<0.063
UG/L	0								
TOXAPHENE	39400	<4.69	<4.69	<0.625	<0.625	<0.625	<0.625	<0.625	<0.625
UG/L	0								
PCB-1016	34671	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
PCB-1221	39488	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
PCB-1232	39492	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
PCB-1242	39496	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
PCB 1248	39500	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
PCB-1254	39504	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
PCB-1260	39508	<0.375	<0.375	<0.313	<0.313	<0.313	<0.313	<0.313	<0.313
UG/L	0								
ANTIMONY,TOTAL	1097	<33.0	<33.0	<33.0	129	78.6	87.6	252	<33.0
UG/L	0								
ARSENIC,TOTAL	1002	119	<21.0	<21.0	<21.0	105	<21.0	<21.0	<21.0
UG/L	0								
BERYLLIUM,T.	1012	17.3	3.20	16.8	26.0	4.25	23.3	27.1	13.0
UG/L	0								
CADMIUM,TOTAL	1027	29.6	<3.00	5.78	5.39	<3.00	12.3	3.05	5.57
UG/L	0								
CHROMIUM,TOTAL	1034	72.7	5.90	71.8	138	36.2	113	179	112
UG/L	0								
COPPER,TOTAL	1042	600	06.7	613	927	144	1550	549	401
UG/L	0								
LEAD,TOTAL	1051	<21.0	<21.0	<21.0	147	<21.0	66.6	<21.0	69.1
UG/L	0								

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME , PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
NAVMXW LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	10GW1	10GW2	10GW3	10GW4	10GW5	10GW6	10GW7	10GW8
		SAMPLE ID/#							
		PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1
UNITS	METHOD	18	19	20	21	22	23	24	25
DATE		01/29/86	01/29/86	01/30/86	01/30/86	01/30/86	01/31/86	01/31/86	01/31/86
TIME		11:05	14:15	11:30	12:45	14:15	10:00	11:15	13:00
MERCURY,TOTAL	71900	0.309	<0.200	0.527	0.309	<0.200	0.309	<0.200	0.222
UG/L	0								
NICKEL,T,	1067	171	9.90	94.8	97.3	27.1	130	99.2	73.8
UG/L	0								
SELENIUM,TOTAL	1147	324	93.1	208	512	30.1	324	411	216
UG/L	0								
SILVER,TOTAL	1077	<6.00	<6.00	<6.00	<6.00	<6.00	<6.00	<6.00	<6.00
UG/L	0								
THALLIUM,TOTAL	1059	42.3	<3.12	24.3	<3.12	3.24	5.03	3.24	112
UG/L	0								
ZINC,TOTAL	1092	733	68.8	584	533	132	857	489	672
UG/L	0								
M-XYLENE	98553	<0.60	<0.61	<0.62	<0.61	<0.64	<0.60	<0.59	<0.58
UG/L	10								
O-AND/OR-P XYLENE	98554	<0.60	<0.61	<0.63	<0.62	<0.64	<0.61	<0.60	<0.59
UG/L	10								
TETRACHLOROETHENE	34475	<1.2	<1.2	<1.3	<1.1	<1.3	<1.1	<1.1	<1.1
UG/L	10								

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGWI PROJECT MANAGER RUSS BOWEN
PRGIA LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	12GW1 PRGWI 26	12GW2 PRGWI 27	12GW3 PRGWI 28	12GW4 PRGWI 29	12GW5 PRGWI 30	12GW6 PRGWI 31
DATE		02/19/86	02/12/86	02/19/86	02/27/86	02/20/86	02/19/86
TIME		08:45	14:00	09:45	09:30	12:00	12:20
PH,FIELD	400	6.70	7.65	7.30	7.00	6.60	7.32
STD UNITS	0						
BENZENE	34030	<0.87	2000	<0.13	<0.90	<0.25	<0.74
UG/L	10						
BROMODICHLOROMETHANE	32101	<0.14	<43	<0.20	<0.25	<0.54	<0.19
UG/L	10						
BROMOFORM	32104	<0.48	<92	<0.68	<0.75	<1.4	<0.66
UG/L	10						
BROMOMETHANE	34413	<0.53	<82	<0.75	<0.64	<1.1	<0.73
UG/L	10						
CARBON TETRACHLORIDE	32102	<0.19	<78	<0.27	<0.29	<1.1	<0.26
UG/L	10						
CHLOROBENZENE	34301	<0.10	<32	<0.14	<0.17	<0.43	<0.79
UG/L	10						
CHLOROETHANE	34311	<1.1	<120	<1.5	<1.3	<1.4	<1.5
UG/L	10						
2-CHL'ETH'VINYLETHER	34576	<1.2	<100	<1.7	<2.4	<1.2	<1.7
UG/L	10						
CHLOROFORM	32106	<0.12	<39	<0.17	<0.22	<0.49	<0.16
UG/L	10						
CHLOROMETHANE	34418	<0.31	<110	<0.44	<0.46	<0.97	<0.43
UG/L	10						
DIBROMOCHLOROMETHANE	32105	<0.273	<72.8	<0.386	<0.469	<1.05	<0.379
UG/L	10						
1,1-DICHLOROETHANE	34496	<0.15	<36	<0.22	<0.30	<0.40	<0.21
UG/L	10						
1,2-DICHLOROETHANE	34531	<0.16	<72	<0.23	<0.27	<0.86	<0.23
UG/L	10						
1,1-DICHLOROETHYLENE	34501	<0.31	<76	<0.44	<0.66	<0.99	<0.44
UG/L	10						
T-1,2-DICHLOROETHENE	34546	<0.28	<66	<0.40	<0.58	<0.86	<0.39
UG/L	10						
1,2-DICHLOROPROPANE	34541	<0.27	<51	<0.38	<0.53	<0.54	<0.37
UG/L	10						
CIS-1,3-DICH'PROPENE	34704	<0.76	<34	<0.20	<0.26	<0.42	<0.20
UG/L	10						
T-1,3-DICHL'PROPENE	34699	<0.15	<94	<0.21	<0.26	<1.1	<0.21
UG/L	10						
ETHYLBENZENE	34371	<0.18	1300	<0.26	<0.32	<0.90	<0.25
UG/L	10						

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 2

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRC1A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	12GW1	12GW2	12GW3	12GW4	12GW5	12GW6
		PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1
UNITS	METHOD	26	27	28	29	30	31
DATE		02/19/86	02/12/86	02/19/86	02/27/86	02/20/86	02/19/86
TIME		08:45	14:00	09:45	09:30	12:00	12:20
METHYLENE CHLORIDE	34423	<4.7	<51	<5.8	<1.9	<0.62	<4.9
UG/L	10						
1,1,2,2-TE'CH'ETHANE	34516	<0.31	<44	<0.44	<0.58	<0.56	<0.43
UG/L	10						
TOLUENE	34010	<0.13	400	<0.18	<0.24	<0.38	<0.18
UG/L	10						
1,1,1-TRICHL'ETHANE	34506	<0.16	<70	<0.22	<0.27	<0.94	<0.22
UG/L	10						
1,1,2-TRICHL'ETHANE	34511	<0.34	<78	<0.48	<0.53	<1.00	<0.47
UG/L	10						
TRICHLOROETHENE	39180	<0.29	<73	<0.41	<0.46	<1.0	<0.41
UG/L	10						
TRICHL'FLUOROMETHANE	34488	<0.33	<70	<0.47	<2.0	<0.82	<0.46
UG/L	10						
VINYL CHLORIDE	39175	<0.44	<82	<0.62	<0.61	<0.93	<0.61
UG/L	10						
1,2-DIBR'ETHANE(EDB)	77651	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020
UG/L	0						
M-XYLENE	98553	<0.03	<55	<0.05	<0.10	<0.69	<0.05
UG/L	10						
OIL&GR,IR	560	0.4	1	0.7	3	0.4	42
MG/L	0						
LEAD,TOTAL	1051	<21.0	<21.0	<21.0	<24.0	<21.0	<21.0
UG/L	0						
O-AND/OR-P XYLENE	98554	<0.05	450	<0.07	<0.09	<0.70	<0.23
UG/L	10						
DICHLOROBENZENE,T.	81524	<0.10	<50	<0.1	<0.3	<0.7	<0.1
UG/L	10						
TETRACHLOROETHENE	34475	<0.31	<110	<0.44	<0.54	<1.5	<0.43
UG/L	10						

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
PRCIA LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	12SWI PRSWI
UNITS	METHOD	21
DATE		11/21/85
TIME		09:46
PH,FIELD	400	7.35
STD UNITS	0	
BENZENE	34030	<0.31
UG/L	10	
BROMODICHLOROMETHANE	32101	<0.41
UG/L	10	
BROMOFORM	32104	<1.2
UG/L	10	
BROMOMETHANE	34413	<0.85
UG/L	10	
CARBON TETRACHLORIDE	32102	<0.36
UG/L	10	
CHLOROBENZENE	34301	<0.28
UG/L	10	
CHLOROETHANE	34311	<1.9
UG/L	10	
2-CHL'ETH'VINYLETHER	34576	<1.8
UG/L	10	
CHLOROFORM	32106	<0.33
UG/L	10	
CHLOROMETHANE	34418	<0.73
UG/L	10	
DIBROMOCHLOROMETHANE	32105	<0.684
UG/L	10	
1,1-DICHLOROETHANE	34496	<0.51
UG/L	10	
1,2-DICHLOROETHANE	34531	<0.44
UG/L	10	
1,1-DICHLOROETHYLENE	34501	<0.92
UG/L	10	
T-1,2-DICHLOROETHENE	34546	<0.91
UG/L	10	
1,2-DICHLOROPROPANE	34541	<0.97
UG/L	10	
CIS-1,3-DICH'PROPENE	34704	<0.41
UG/L	10	
T-1,3-DICHL'PROPENE	34699	<0.41
UG/L	10	
ETHYLBENZENE	34371	<0.61
UG/L	10	

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
PRC1A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	12SWI PRSWI
UNITS	METHOD	21
DATE		11/21/85
TIME		09:46
METHYLENE CHLORIDE	34423	<15
UG/L	10	
1,1,2,2-TE'CH'ETHANE	34516	<1.1
UG/L	10	
TOLUENE	34010	<0.43
UG/L	10	
1,1,1-TRICHL'ETHANE	34506	<0.38
UG/L	10	
1,1,2-TRICHL'ETHANE	34511	<0.90
UG/L	10	
TRICHLOROETHENE	39180	<0.59
UG/L	10	
TRICHL'FLUOROMETHANE	34488	<1.1
UG/L	10	
VINYL CHLORIDE	39175	<0.75
UG/L	10	
1,2-DIBR'ETHANE(EDB)	77651	<0.010
UG/L	0	
M-XYLENE	98553	<0.16
UG/L	10	
OIL&GR,IR	560	0.4
MG/L	0	
LEAD,TOTAL	1051	<24.0
UG/L	0	
O-AND/OR-P XYLENE	98554	<0.15
UG/L	10	
DICHLOROBENZENE,T.	81524	<0.3
UG/L	10	
TETRACHLOROETHENE	34475	<0.60
UG/L	10	

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS1 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	12SE1 PRSE1 50
DATE			01/08/86
TIME			09:20
BENZENE	UG/G-DRY	98699 10	<0.13
BROMODICHLOROMETHANE	UG/G-DRY	98703 10	<0.28
BROMOFORM	UG/G-DRY	98704 10	<0.61
BROMOMETHANE	UG/G-DRY	98705 10	<0.57
CARBON TETRACHLORIDE	UG/G-DRY	98600 10	<0.47
CHLOROBENZENE	UG/G-DRY	98681 10	<0.22
CHLOROETHANE	UG/G-DRY	98706 10	<0.77
2-CHLOROETHYLVINYLETHER	UG/G-DRY	98796 10	<0.61
CHLOROFORM	UG/G-DRY	98602 10	<0.251
CHLOROMETHANE	UG/G-DRY	98707 10	<0.47
DIBROMOCHLOROMETHANE	UG/G-DRY	98708 10	<0.47
1,1-DICHLOROETHANE	UG/G-DRY	98603 10	<0.22
1,2-DICHLOROETHANE	UG/G-DRY	98604 10	<0.44
1,1-DICHLOROETHENE	UG/G-DRY	98709 10	<0.49
TRANS-1,2-DICHLOROETHENE	UG/G-DRY	98687 10	<0.46
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.31
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.20
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.55
ETHYLBENZENE	UG/G-DRY	98608 10	<0.50
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.50

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS1 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	12SE1 PRSE1 50
DATE			01/08/86
TIME			09:20
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.27
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.72
TOLUENE	UG/G-DRY	98691 10	<0.20
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.47
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.52
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.50
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.41
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.47
PH,SOIL		99218 0	8.1
1,2-DIBROMOETHANE (EDB)	MG/KG-DRY	98798 0	<0.003
M-XYLENE	MG/KG-DRY	98799 10	<0.39
O,P-XYLENE	MG/KG-DRY	98800 10	<0.39
OIL&GR,IR,SED	UG/G- DRY	561 0	3340
LEAD,SED	UG/G-DRY	1052 0	<4.68
MOISTURE	%WET WT	70320 0	41.0
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.37

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/14/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFORMATION STUDY
FIELD GROUP PRTOX PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	12TX1 PRTOX 1	12TX2 PRTOX 2
DATE		11/21/85	11/21/85
TIME		08:40	09:15
ARSENIC,DISS	1000	<10.0	<10.0
UG/L	0		
BARIUM,DISS	1005	452	309
UG/L	0		
CADMIUM,DISS	1025	<3.00	<3.00
UG/L	0		
CHROMIUM,DISS	1030	<5.00	<5.00
UG/L	0		
LEAD,DISS	1049	<36.0	<36.0
UG/L	0		
MERCURY,DISS.	71890	<0.500	<0.500
UG/L	0		
SELENIUM,DISS	1145	<1.00	<1.00
UG/L	0		
SILVER,DISS	1075	<6.00	<6.00
UG/L	0		

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRC1A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	13GW1	13GW2	13GW3	13GW4	13GW5	13GW6	13GW7	13GW8	13GW9	13GW10	13GW11
		PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1
UNITS	METHOD	32	33	34	35	36	37	38	39	40	41	42
DATE		03/05/86	03/05/86	03/05/86	03/12/86	03/05/86	03/04/86	03/03/86	03/03/86	03/04/86	03/04/86	03/03/86
TIME		10:10	10:30	10:00	10:15	10:45	12:45	14:30	14:00	12:00	12:24	13:45
PH,FIELD	400	7.59	6.57	7.08	6.60	7.55	6.43	6.58	7.41	7.09	7.12	6.95
STD UNITS	0											
BENZENE	34030	<0.23	2000	0.21	<0.25	350	<0.23	<0.22	<0.78	16	<0.24	<0.88
UG/L	10											
BROMODICHLOROMETHANE	32101	<0.49	<49	0.57	<0.51	<0.48	<0.50	<0.29	<0.26	<0.50	<0.52	<0.29
UG/L	10											
BROMOFORM	32104	<1.3	<120	<1.1	<1.2	<1.3	<1.3	<0.88	<0.79	<1.3	<1.4	<0.88
UG/L	10											
BROMOMETHANE	34413	<0.99	<110	<1.0	<1.1	<0.96	<1.0	<0.75	<0.68	<1.0	<1.1	<0.75
UG/L	10											
CARBON TETRACHLORIDE	32102	<0.96	<87	<0.85	<0.87	<0.93	<0.97	<0.34	<0.30	<0.99	<1.0	<0.34
UG/L	10											
CHLOROBENZENE	34301	<0.43	<40	<0.39	<0.42	1.5	<0.40	<0.20	<0.18	<0.41	<0.42	<0.20
UG/L	10											
CHLOROETHANE	34311	<1.2	<140	<1.3	<1.4	<1.2	<1.3	<1.6	<1.4	<1.3	<1.3	<1.6
UG/L	10											
2-CHL'ETH'VINYLETHER	34576	<1.2	<100	<1.0	<1.00	<1.1	<1.1	<2.8	<2.5	<1.1	<1.1	<2.8
UG/L	10											
CHLOROFORM	32106	1.0	<43	5.0	3.7	2.6	1.1	<0.26	<0.23	<0.46	0.42	<0.26
UG/L	10											
CHLOROMETHANE	34418	<0.89	<100	<1.0	<1.5	<0.86	<0.90	<0.54	<0.49	<0.91	<0.94	<0.54
UG/L	10											
DIBROMOCHLOROMETHANE	32105	<0.960	<88.0	<0.850	<0.908	<0.932	<0.972	<0.550	<0.494	<0.986	<1.02	<0.550
UG/L	10											
1,1-DICHLOROETHANE	34496	<0.40	<38	<0.35	<0.37	<1.2	<0.37	<0.35	<0.32	<0.37	<0.39	<0.35
UG/L	10											
1,2-DICHLOROETHANE	34531	<0.86	90	<0.73	170	<0.79	<0.80	<0.32	<0.29	<0.81	<0.81	<0.32
UG/L	10											
1,1-DICHLOROETHYLENE	34501	<0.91	<98	<0.95	<0.98	<0.88	<0.92	<0.77	<0.69	<0.93	<0.96	<0.77
UG/L	10											
T-1,2-DICHLOROETHENE	34546	<0.78	<84	<0.82	<0.86	<0.76	<0.79	<0.68	<0.61	<0.80	<0.83	<0.68
UG/L	10											
1,2-DICHLOROPROPANE	34541	<0.54	<50	<0.50	<0.53	<0.51	<0.50	<0.63	<0.56	<0.49	<0.52	<0.63
UG/L	10											
CIS-1,3-DICH'PROPENE	34704	<0.38	<35	<0.36	<0.37	<0.38	<0.39	<0.30	<0.84	<0.38	<0.41	<0.30
UG/L	10											
T-1,3-DICHL'PROPENE	34699	<1.0	<100	<0.99	<1.0	<0.97	<1.0	<0.31	<0.28	<1.0	<1.1	<0.31
UG/L	10											
ETHYLBENZENE	34371	<0.82	130	<0.81	1.0	74	<0.83	<0.37	<0.33	<0.85	<0.87	<0.37
UG/L	10											

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 2

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRGW1 PROJECT MANAGER RUSS BOWEN
PRC1A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	13GW1	13GW2	13GW3	13GW4	13GW5	13GW6	13GW7	13GW8	13GW9	13GW10	13GW11
		PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1	PRGW1
UNITS	METHOD	32	33	34	35	36	37	38	39	40	41	42
DATE		03/05/86	03/05/86	03/05/86	03/12/86	03/05/86	03/04/86	03/03/86	03/03/86	03/04/86	03/04/86	03/03/86
TIME		10:10	10:30	10:00	10:15	10:45	12:45	14:30	14:00	12:00	12:24	13:45
METHYLENE CHLORIDE	34423	<0.62	<73	<0.60	<0.65	<0.61	<0.62	<3.5	<2.1	<0.62	<0.62	<2.2
UG/L	10											
1,1,2,2-TE'CH'ETHANE	34516	<0.55	<49	<0.47	<0.47	<0.51	<0.52	<0.69	<8.8	<0.52	<0.52	<0.69
UG/L	10											
TOLUENE	34010	<0.38	34000	<0.40	<0.40	420	<0.38	<0.28	<0.25	<0.38	<0.38	<0.28
UG/L	10											
1,1,1-TRICHL'ETHANE	34506	<0.86	<82	<0.80	<0.81	<0.83	<0.87	<0.32	<0.30	<0.88	<0.91	<0.32
UG/L	10											
1,1,2-TRICHL'ETHANE	34511	<0.91	<93	<0.90	<0.94	<0.88	<0.92	<0.62	<0.56	<0.94	<0.97	<0.62
UG/L	10											
TRICHLOROETHENE	39180	<0.92	<95	<0.93	<1.00	<0.90	<0.93	<0.53	<0.48	<0.95	<0.98	<0.53
UG/L	10											
TRICHL'FLUOROMETHANE	34488	<0.74	<77	<0.75	<0.81	<0.72	<0.75	<0.73	<0.66	<0.76	<0.79	<0.73
UG/L	10											
VINYL CHLORIDE	39175	<0.85	<94	<0.91	<1.0	1.9	<0.86	<0.71	<0.64	<0.88	<0.90	<0.71
UG/L	10											
1,2-DIBR'ETHANE(EDB)	77651	<0.020	0.365	0.045	<0.020	<0.020	0.297	<0.020	<0.020	<0.020	<0.020	<0.020
UG/L	0											
M-XYLENE	98553	<0.63	290	<0.65	<0.66	220	<0.64	<0.11	<0.10	<0.65	<0.67	<0.11
UG/L	10											
OIL&GR,IR	560	0.7	5	0.6	3	2	0.5	0.3	0.4	0.2	0.4	0.2
MG/L	0											
LEAD,TOTAL	1051	<24.0	<24.0	<24.0	<21.0	<24.0	<24.0	<24.0	<24.0	<24.0	<24.0	<24.0
UG/L	0											
O-AND/OR-P XYLENE	98554	<0.64	360	0.83	0.57	180	<0.65	<0.10	<0.09	4.9	<0.68	<0.10
UG/L	10											
DICHLOROBENZENE,T.	81524	<0.6	<60	<0.6	<0.6	<0.6	<0.6	<0.3	<0.3	<0.6	<0.7	<0.3
UG/L	10											
TETRACHLOROETHENE	34475	<1.4	<140	<1.4	<1.4	<1.3	<1.4	<0.64	<0.57	<1.4	<1.5	<0.64
UG/L	10											

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
PRCIA LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	13SW1	13SW2	13SW3	13SW4	13SW5	13SW6
		PRSWI	PRSWI	PRSWI	PRSWI	PRSWI	PRSWI
UNITS	METHOD	22	23	24	25	26	27
DATE		01/23/86	01/23/86	01/23/86	01/22/86	01/22/86	01/22/86
TIME		10:30	11:00	11:30	09:15	10:45	11:15
PH,FIELD	400	7.34	7.52	7.54	7.70	7.84	7.83
STD UNITS	0						
BENZENE	34030	<0.40	<0.40	<0.42	<0.37	<0.36	<0.41
UG/L	10						
BROMODICHLOROMETHANE	32101	<0.48	<0.49	<0.51	<0.45	<0.44	<0.50
UG/L	10						
BROMOFORM	32104	<1.3	<1.3	<1.4	<1.2	<1.2	<1.3
UG/L	10						
BROMOMETHANE	34413	<1.0	<1.0	<1.1	<0.94	<0.91	<1.0
UG/L	10						
CARBON TETRACHLORIDE	32102	<0.41	<0.41	<0.43	<0.38	<0.37	<0.42
UG/L	10						
CHLOROBENZENE	34301	<0.33	<0.33	<0.35	<0.31	<0.30	<0.34
UG/L	10						
CHLOROETHANE	34311	<2.9	<2.9	<3.1	<2.7	<2.6	<3.0
UG/L	10						
2-CHL'ETH'VINYLETHER	34576	<4.3	<4.3	<4.5	<4.0	<3.9	<4.4
UG/L	10						
CHLOROFORM	32106	<0.42	<0.43	<0.45	<0.40	<0.38	<0.44
UG/L	10						
CHLOROMETHANE	34418	<1.5	<1.5	<1.6	<1.4	<1.4	<1.6
UG/L	10						
DIBROMOCHLOROMETHANE	32105	<0.815	<0.825	<0.867	<0.762	<0.737	<0.847
UG/L	10						
1,1-DICHLOROETHANE	34496	<0.63	<0.64	<0.67	<0.59	<0.57	<0.66
UG/L	10						
1,2-DICHLOROETHANE	34531	<0.56	<0.57	<0.60	<0.53	<0.51	<0.59
UG/L	10						
1,1-DICHLOROETHYLENE	34501	<1.2	<1.3	<1.3	<1.2	<1.1	<1.3
UG/L	10						
T-1,2-DICHLOROETHENE	34546	<1.1	<1.1	<1.2	<1.0	<0.98	<1.1
UG/L	10						
1,2-DICHLOROPROPANE	34541	<1.2	<1.2	<1.2	<1.1	<1.1	<1.2
UG/L	10						
CIS-1,3-DICH'PROPENE	34704	<0.43	<0.48	<0.51	<0.45	<0.43	<0.50
UG/L	10						
T-1,3-DICHL'PROPENE	34699	<0.49	<0.50	<0.52	<0.46	<0.44	<0.51
UG/L	10						
ETHYLBENZENE	34371	<0.68	<0.69	<0.72	<0.63	<0.61	<0.71
UG/L	10						

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 2

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
PRC1A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	13SW1 PRSW1 22	13SW2 PRSW1 23	13SW3 PRSW1 24	13SW4 PRSW1 25	13SW5 PRSW1 26	13SW6 PRSW1 27
DATE		01/23/86	01/23/86	01/23/86	01/22/86	01/22/86	01/22/86
TIME		10:30	11:00	11:30	09:15	10:45	11:15
METHYLENE CHLORIDE	34423	<1.5	<1.5	<4.0	<1.5	<1.0	<1.5
UG/L	10						
1,1,2,2-TE'CH'ETHANE	34516	<1.4	<1.4	<1.5	<1.3	<1.2	<1.4
UG/L	10						
TOLUENE	34010	<0.47	<0.48	<0.50	<0 44	<0.42	<0.49
UG/L	10						
1,1,1-TRICHL'ETHANE	34506	<0.44	<0.45	<0.47	<0.42	<0.40	<0.46
UG/L	10						
1,1,2-TRICHL'ETHANE	34511	<1.1	<1.1	<1.1	<1.00	<0.97	<1.1
UG/L	10						
TRICHLOROETHENE	39180	<0.75	<0.75	<0.79	<0.70	<0.67	<0.77
UG/L	10						
TRICHL'FLUOROMETHANE	34488	<1.5	<1.5	<1.6	<1.4	<1.4	<1.6
UG/L	10						
VINYL CHLORIDE	39175	<1.5	<1.5	<1.6	<1.4	<1.3	<1.5
UG/L	10						
1,2-DIBR'ETHANE(EDB)	77651	<0.020	<0.020	<0.020	<0.020	<0.020	<0.020
UG/L	0						
M-XYLENE	98553	<0.21	<0.21	<0.22	<0.20	<0.19	<0.22
UG/L	10						
OIL&GR,IR	560	<0.2	<0.2	<0.2	<0.2	0.6	0.4
MG/L	0						
LEAD,TOTAL	1051	<24.0	<24.0	<24.0	<24.0	<24.0	<24.0
UG/L	0						
O-AND/OR-P XYLENE	98554	<0.22	<0.22	<0.23	<0.21	<0.20	<0.23
UG/L	10						
DICHLOROBENZENE,T.	81524	<0.4	<0.4	<0.4	<0.3	<0.3	<0.4
UG/L	10						
TETRACHLOROETHENE	34475	<0.75	<0.76	<0.80	<0.70	<0.68	<0.78
UG/L	10						

A-90

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS1 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	13SE1 PRSE1 51	13SE2 PRSE1 52	13SE3 PRSE1 53	13SE4 PRSE1 54	13SE5 PRSE1 55	13SE6 PRSE1 56
DATE			01/23/86	01/23/86	01/23/86	01/22/86	01/22/86	01/22/86
TIME			10:30	11:00	11:30	09:15	10:45	11:15
BENZENE	UG/G-DRY	98699 10	<0.13	<0.10	<0.17	<0.12	<0.17	<0.15
BROMODICHLOROMETHANE	UG/G-DRY	98783 10	<0.25	<0.20	<0.33	<0.23	<0.33	<0.31
BROMOFORM	UG/G-DRY	98784 10	<0.53	<0.42	<0.70	<0.49	<0.70	<0.65
BROMOMETHANE	UG/G-DRY	98785 10	<0.51	<0.41	<0.68	<0.47	<0.68	<0.63
CARBON TETRACHLORIDE	UG/G-DRY	98680 10	<0.43	<0.34	<0.57	<0.40	<0.57	<0.53
CHLOROBENZENE	UG/G-DRY	98681 10	<0.19	<0.15	<0.25	<0.17	<0.25	<0.23
CHLOROETHANE	UG/G-DRY	98786 10	<0.72	<0.58	<0.96	<0.66	<0.96	<0.89
2-CHLOROETHYLVINYLETHER	UG/G-DRY	98796 10	<0.59	<0.47	<0.79	<0.55	<0.79	<0.73
CHLOROFORM	UG/G-DRY	98682 10	<0.224	<0.178	<0.297	<0.206	<0.296	<0.275
CHLOROMETHANE	UG/G-DRY	98787 10	<0.54	<0.43	<0.71	<0.49	<0.71	<0.66
DIBROMOCHLOROMETHANE	UG/G-DRY	98788 10	<0.41	<0.33	<0.55	<0.38	<0.54	<0.51
1,1-DICHLOROETHANE	UG/G-DRY	98683 10	<0.21	<0.19	<0.27	<0.19	<0.27	<0.25
1,2-DICHLOROETHANE	UG/G-DRY	98684 10	<0.40	<0.32	<0.53	<0.37	<0.53	<0.50
1,1-DICHLOROETHENE	UG/G-DRY	98789 10	<0.44	<0.35	<0.58	<0.40	<0.57	<0.54
TRANS-1,2-DICHLOROETENE	UG/G-DRY	98687 10	<0.39	<0.31	<0.52	<0.36	<0.51	<0.48
1,2-DICHLOROPROPANE	UG/G-DRY	98790 10	<0.29	<0.23	<0.38	<0.27	<0.38	<0.36
CIS-1,3-DICHLOROPROPENE	UG/G-DRY	98791 10	<0.19	<0.16	<0.26	<0.18	<0.26	<0.24
TRANS-1,3-DICHLOROPROPENE	UG/G-DRY	98792 10	<0.51	<0.41	<0.68	<0.47	<0.68	<0.63
ETHYLBENZENE	UG/G-DRY	98688 10	<0.41	<0.32	<0.54	<0.38	<0.54	<0.50
METHYLENE CHLORIDE	UG/G-DRY	98689 10	<0.31	<0.26	<0.41	<0.29	<0.41	<0.37

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS1 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	13SE1 PRSE1 51	13SE2 PRSE1 52	13SE3 PRSE1 53	13SE4 PRSE1 54	13SE5 PRSE1 55	13SE6 PRSE1 56
DATE			01/23/86	01/23/86	01/23/86	01/22/86	01/22/86	01/22/86
TIME			10:30	11:00	11:30	09:15	10:45	11:15
1,1,2,2-TETRACHLOROETHANE	UG/G-DRY	98793 10	<0.25	<0.20	<0.33	<0.23	<0.33	<0.31
TETRACHLOROETHENE	UG/G-DRY	98690 10	<0.59	<0.47	<0.79	<0.55	<0.79	<0.73
TOLUENE	UG/G-DRY	98691 10	<0.20	<0.16	<0.26	<0.18	<0.26	<0.23
1,1,1-TRICHLOROETHANE	UG/G-DRY	98692 10	<0.40	<0.32	<0.53	<0.37	<0.53	<0.49
1,1,2-TRICHLOROETHANE	UG/G-DRY	98693 10	<0.45	<0.36	<0.59	<0.41	<0.59	<0.55
TRICHLOROETHENE	UG/G-DRY	98694 10	<0.42	<0.34	<0.56	<0.39	<0.56	<0.52
TRICHLOROFLUOROMETHANE	UG/G-DRY	98794 10	<0.47	<0.37	<0.62	<0.43	<0.62	<0.58
VINYL CHLORIDE	UG/G-DRY	98795 10	<0.51	<0.41	<0.68	<0.47	<0.68	<0.63
PH,SOIL		99218 0	7.3	7.2	7.5	7.4	7.3	7.3
1,2-DIBROMOETHANE (EDB)	MG/KG-DRY	98798 0	<0.005	<0.004	<0.007	<0.005	<0.007	<0.006
M-XYLENE	MG/KG-DRY	98799 10	<0.36	<0.29	<0.48	<0.33	<0.48	<0.44
O,P-XYLENE	MG/KG-DRY	98800 10	<0.37	<0.30	<0.49	<0.34	<0.49	<0.46
OIL&GR,IR,SED	UG/G- DRY	561 0	52300	6710	3280	1730	1830	10200
LEAD,SED	UG/G-DRY	1052 0	400	42.3	<12.0	7.79	<11.7	<10.2
MOISTURE	%WET WT	70320 0	61.5	53.2	70.2	58.6	70.2	67.1
DICHLOROBENZENE,TOTAL	UG/G-DRY	98803 10	<0.34	<0.27	<0.45	<0.31	<0.45	<0.41

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
PRC2A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	14SW1	14SW2	14SW3	14SW4	14SW5	14SW6	14SW7	14SW8	14SW9	14SW10	14SW11	14SW12
		PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1	PRSW1
UNITS	METHOD	28	29	30	31	32	33	34	35	36	37	38	39
DATE		11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85
TIME		08:15	08:40	08:55	09:15	10:10	10:30	10:45	11:15	12:05	12:30	12:50	13:10
PH,FIELD	400	7.01	7.27	7.34	7.35	7.33	7.38	7.36	7.68	8.01	8.07	7.96	8.02
STD UNITS	0												
BENZENE	34030	<0.32	<0.30	<0.29	<0.30	<0.30	<0.30	<0.30	<0.30	<0.30	<0.30	<0.30	<0.51
UG/L	10												
BROMODICHLOROMETHANE	32101	<0.41	<0.38	<0.38	<0.39	<0.41	<0.29	<0.31	<0.33	<0.37	<0.35	<0.34	<0.68
UG/L	10												
BROMOFORM	32104	<1.3	<1.2	<1.2	<1.2	<1.3	<0.83	<0.89	<0.93	<1.1	<1.0	<0.98	<1.9
UG/L	10												
BROMOMETHANE	34413	<0.76	<0.70	<0.70	<0.71	<0.76	<0.61	<0.65	<0.68	<0.77	<0.74	<0.72	<1.4
UG/L	10												
CARBON TETRACHLORIDE	32102	<0.33	<0.31	<0.31	<0.31	<0.34	<0.25	<0.27	<0.28	<0.32	<0.31	<0.30	<0.59
UG/L	10												
CHLOROBENZENE	34301	<0.28	<0.26	<0.26	<0.27	<0.28	<0.20	<0.21	<0.22	<0.25	<0.24	<0.23	<0.46
UG/L	10												
CHLOROETHANE	34311	<1.8	<1.7	<1.6	<1.7	<1.8	<1.3	<1.4	<1.5	<1.7	<1.6	<1.6	<3.1
UG/L	10												
2-CHL'ETH'VINYLETHER	34576	<1.8	<1.7	<1.7	<1.7	<1.9	<1.3	<1.4	<1.5	<1.6	<1.6	<1.5	<3.0
UG/L	10												
CHLOROFORM	32106	<0.32	<0.30	<0.30	<0.30	<0.32	<0.24	<0.25	<0.26	<0.30	<0.29	<0.28	<0.55
UG/L	10												
CHLOROMETHANE	34418	<0.69	<0.63	<0.63	<0.64	<0.69	<0.52	<0.56	<0.58	<0.66	<0.63	<0.62	<1.2
UG/L	10												
DIBROMOCHLOROMETHANE	32105	<0.553	<0.512	<0.507	<0.520	<0.555	<0.488	<0.524	<0.546	<0.616	<0.591	<0.576	<1.13
UG/L	10												
1,1-DICHLOROETHANE	34496	<0.50	<0.47	<0.46	<0.47	<0.51	<0.36	<0.39	<0.41	<0.46	<0.44	<0.43	<0.84
UG/L	10												
1,2-DICHLOROETHANE	34531	<0.43	<0.40	<0.40	<0.41	<0.44	<0.31	<0.34	<0.35	<0.39	<0.38	<0.37	<0.73
UG/L	10												
1,1-DICHLOROETHYLENE	34501	<0.96	<0.88	<0.87	<0.90	<0.96	<0.66	<0.70	<0.73	<0.83	<0.80	<0.77	<1.5
UG/L	10												
T-1,2-DICHLOROETHENE	34546	<0.94	<0.87	<0.86	<0.88	<0.94	<0.65	<0.70	<0.73	<0.82	<0.79	<0.77	<1.5
UG/L	10												
1,2-DICHLOROPROPANE	34541	<0.97	<0.90	<0.89	<0.92	<0.98	<0.69	<0.74	<0.78	<0.88	<0.84	<0.82	<1.6
UG/L	10												
CIS-1,3-DICH'PROPENE	34704	<0.41	<0.38	<0.37	<0.38	<0.41	<0.29	<0.31	<0.32	<0.37	<0.35	<0.34	<0.67
UG/L	10												
T-1,3-DICHL'PROPENE	34699	<0.41	<0.38	<0.38	<0.39	<0.41	<0.29	<0.31	<0.33	<0.37	<0.35	<0.34	<0.68
UG/L	10												
ETHYLBENZENE	34371	<0.61	<0.56	<0.56	<0.57	<0.61	<0.44	<0.47	<0.49	<0.55	<0.53	<0.51	<1.0
UG/L	10												

RR-00039-03.13-04/01/88

PROJECT NUMBER 05275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSW1 PROJECT MANAGER RUSS BOWEN
PRC2A LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	14SW1 PRSW1 28	14SW2 PRSW1 29	14SW3 PRSW1 30	14SW4 PRSW1 31	14SW5 PRSW1 32	14SW6 PRSW1 33	14SW7 PRSW1 34	14SW8 PRSW1 35	14SW9 PRSW1 36	14SW10 PRSW1 37	14SW11 PRSW1 38	14SW12 PRSW1 39
DATE		11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85
TIME		08:15	08:40	08:55	09:15	10:10	10:30	10:45	11:15	12:05	12:30	12:50	13:10
METHYLENE CHLORIDE UG/L	34423 10	<0.85	<0.79	<0.78	<0.80	<0.85	<0.59	<0.63	<0.66	<0.74	<0.71	<0.69	<1.4
1,1,2,2-TE'CH'ETHANE UG/L	34516 10	<1.2	<1.1	<1.1	<1.2	<1.2	<0.81	<0.87	<0.90	<1.0	<0.98	<0.95	<1.9
TOLUENE UG/L	34010 10	<0.43	<0.40	<0.40	<0.41	<0.44	<0.31	<0.33	<0.34	<0.39	<0.37	<0.36	<0.71
1,1,1-TRICHL'ETHANE UG/L	34506 10	<0.36	<0.34	<0.33	<0.34	<0.36	<0.27	<0.29	<0.30	<0.34	<0.33	<0.32	<0.63
1,1,2-TRICHL'ETHANE UG/L	34511 10	<0.90	<0.84	<0.83	<0.85	<0.91	<0.64	<0.69	<0.72	<0.81	<0.78	<0.76	<1.5
TRICHLOROETHENE UG/L	39180 10	<0.55	<0.51	<0.51	<0.52	<0.56	<0.42	<0.45	<0.47	<0.53	<0.51	<0.49	<0.97
TRICHL'FLUOROMETHANE UG/L	34488 10	<1.1	<1.0	<1.0	<1.1	<1.1	<0.81	<0.87	<0.91	<1.0	<0.98	<0.96	<1.9
VINYL CHLORIDE UG/L	39175 10	<0.72	<0.66	<0.66	<0.67	<0.72	<0.54	<0.58	<0.60	<0.68	<0.65	<0.63	<1.3
1,2-DIBR'ETHANE(EDB) UG/L	77651 0	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010
M-XYLENE UG/L	98553 10	<0.20	<0.20	<0.20	<0.20	<0.20	<0.11	<0.12	<0.13	<0.14	<0.14	<0.13	<0.26
OIL&GR,IR MG/L	560 0	<0.2	<0.2	<0.2	0.8	2	0.7	0.5	0.3	0.6	0.5	0.5	<0.2
LEAD,TOTAL UG/L	1051 0	<24.0	<24.0	<24.0	<51.0	<27.0	<27.0	<27.0	<27.0	<27.0	<27.0	<27.0	<27.0
METHYL ETHYL KETONE UG/L	81595 10	<14	<3.7	<3.7	<14	<4.1	<9.7	<10	<7.1	<9.0	<8.1	<8.7	<4.7
METHYL ISOBUT'KETONE UG/L	81596 10	<2.5	<2.3	<2.3	<2.3	<2.5	<1.3	<1.4	<1.4	<1.6	<1.5	<1.5	<2.9
O-AND/OR-P XYLENE UG/L	98554 10	<0.16	<0.15	<0.15	<0.15	<0.16	<0.11	<0.12	<0.12	<0.14	<0.13	<0.13	<0.26
DICHLOROBENZENE,T. UG/L	81524 10	<0.3	<0.2	<0.2	<0.2	<0.3	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.4
TETRACHLOROETHENE UG/L	34475 10	<0.60	<0.56	<0.55	<0.57	<0.60	<0.43	<0.46	<0.48	<0.54	<0.52	<0.50	<0.99

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 05275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS2 LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	14SE1 PRSE1 57	14SE2 PRSE1 58	14SE3 PRSE1 59	14SE4 PRSE1 60	14SE5 PRSE1 61	14SE6 PRSE1 62	14SE7 PRSE1 63	14SE8 PRSE1 64	14SE9 PRSE1 65	14SE10 PRSE1 66	14SE11 PRSE1 67	14SE12 PRSE1 68
		SAMPLE ID/#											
DATE		11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85
TIME		08:20	08:45	09:00	09:20	10:15	10:35	10:50	11:20	12:10	12:35	12:55	13:15
BENZENE	98699	<0.13	<0.09	<0.19	<0.20	<0.55	<0.37	<0.43	<0.10	<0.10	<0.17	<0.38	<0.10
UG/G-DRY	10												
BROMODICHLOROMETHANE	98703	<0.17	<0.17	<0.36	<0.38	<1.0	<0.49	<0.00	<0.18	<0.19	<0.22	<0.51	<0.18
UG/G-DRY	10												
BROMOFORM	98704	<0.46	<0.30	<0.64	<0.68	<1.8	<1.3	<1.4	<0.33	<0.34	<0.58	<1.3	<0.32
UG/G-DRY	10												
BROMOMETHANE	98705	<0.37	<0.26	<0.55	0.0	<1.6	<1.0	<1.2	<0.28	<0.29	<0.46	<1.1	<0.27
UG/G-DRY	10												
CARBON TETRACHLORIDE	98680	<0.16	<0.31	<0.66	<0.69	<1.9	<0.45	<1.5	<0.34	<0.35	<0.20	<0.46	<0.33
UG/G-DRY	10												
CHLOROBENZENE	98681	<0.12	<0.13	<0.27	<0.29	<0.78	<0.35	<0.61	<0.14	<0.15	<0.16	<0.36	<0.14
UG/G-DRY	10												
CHLOROETHANE	98706	<0.80	<0.45	<0.98	<1.0	<2.8	<2.3	<2.2	<0.50	<0.52	<1.0	<2.3	<0.49
UG/G-DRY	10												
2-CHLOROETHYLVINYLETHER	98796	<0.79	<0.40	<0.86	<0.90	<2.4	<2.2	<1.9	<0.44	<0.45	<1.00	<2.3	<0.42
UG/G-DRY	10												
CHLOROFORM	98682	<0.142	<0.155	<0.335	<0.354	<0.960	<0.403	<0.748	<0.172	<0.178	<0.180	<0.415	<0.165
UG/G-DRY	10												
CHLOROMETHANE	98707	<0.32	<0.46	<0.99	<1.0	<2.8	<0.90	<2.2	<0.51	<0.53	<0.40	<0.93	<0.49
UG/G-DRY	10												
DIBROMOCHLOROMETHANE	98708	<0.28	<0.26	<0.56	<0.59	<1.6	<0.80	<1.2	<0.29	<0.30	<0.36	<0.83	<0.28
UG/G-DRY	10												
1,1-DICHLOROETHANE	98683	<0.22	<0.15	<0.32	<0.34	<0.91	<0.62	<0.71	<0.16	<0.17	<0.28	<0.64	<1.6
UG/G-DRY	10												
1,2-DICHLOROETHANE	98684	<0.20	<0.25	<0.54	<0.57	<1.5	<0.57	<1.2	<0.28	<0.29	<0.25	<0.59	<0.27
UG/G-DRY	10												
1,1-DICHLOROETHENE	98789	<0.40	<0.33	<0.72	<0.76	<2.1	<1.1	<1.6	<0.37	<0.38	<0.51	<1.2	<0.36
UG/G-DRY	10												
TRANS-1,2-DICHLOROETHENE	98687	<0.37	<0.28	<0.61	<0.64	<1.7	<1.1	<1.4	<0.31	<0.32	<0.47	<1.1	<0.30
UG/G-DRY	10												
1,2-DICHLOROPROPANE	98790	<0.41	<0.21	<0.46	<0.48	<1.3	<1.2	<1.0	<0.23	<0.24	<0.52	<1.2	<0.23
UG/G-DRY	10												
CIS-1,3-DICHLOROPROPENE	98791	<0.17	<0.13	<0.28	<0.29	<0.79	<0.49	<0.62	<0.14	<0.15	<0.22	<0.50	<0.14
UG/G-DRY	10												
TRANS-1,3-DICHLOROPROPENE	98792	<0.17	<0.35	<0.76	<0.80	<2.2	<0.49	<1.7	<0.39	<0.40	<0.22	<0.50	<0.38
UG/G-DRY	10												
ETHYLBENZENE	98688	<0.28	<0.27	<0.59	<0.62	<1.7	<0.79	<1.3	<0.30	<0.31	<0.35	<0.81	<0.29
UG/G-DRY	10												
METHYLENE CHLORIDE	98689	<1.3	<0.25	<0.52	<0.57	<1.5	<3.7	<1.2	<0.27	<0.28	<0.40	<0.92	<0.26
UG/G-DRY	10												

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
PRS2 LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	14SE1 PRSE1 57	14SE2 PRSE1 58	14SE3 PRSE1 59	14SE4 PRSE1 60	14SE5 PRSE1 61	14SE6 PRSE1 62	14SE7 PRSE1 63	14SE8 PRSE1 64	14SE9 PRSE1 65	14SE10 PRSE1 66	14SE11 PRSE1 67	14SE12 PRSE1 68
DATE		11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85	11/22/85
TIME		08:20	08:45	09:00	09:20	10:15	10:35	10:50	11:20	12:10	12:35	12:55	13:15
1,1,2,2-TETRACHLOROETHANE UG/G-DRY	98793 10	<0.51	<0.16	<0.35	<0.37	<1.0	<1.5	<0.79	<0.18	<0.19	<0.65	<1.5	<0.18
TETRACHLOROETHENE UG/G-DRY	98690 10	<0.28	<0.39	<0.85	<0.90	<2.4	<0.79	<1.9	<0.43	<0.45	<0.35	<0.81	<0.42
TOLUENE UG/G-DRY	98691 10	<0.19	<0.14	<0.31	<0.33	<0.88	<0.53	<0.70	<0.16	<0.16	<0.23	<0.54	<1.5
1,1,1-TRICHLOROETHANE UG/G-DRY	98692 10	<0.18	<0.26	<0.57	<0.60	<1.6	<0.50	<1.3	<0.29	<0.30	<0.22	<0.51	<0.28
1,1,2-TRICHLOROETHANE UG/G-DRY	98693 10	<0.39	<0.31	<0.66	<0.70	<1.9	<1.1	<1.5	<0.34	<0.35	<0.49	<1.1	<0.33
TRICHLOROETHENE UG/G-DRY	98694 10	<0.25	<0.29	<0.62	<0.65	<1.8	<0.71	<1.4	<0.32	<0.33	<0.32	<0.73	<0.31
TRICHLOROFLUOROMETHANE UG/G-DRY	98794 10	<0.49	<0.28	<0.60	<0.63	<1.7	<1.4	<1.3	<0.31	<0.32	<0.61	<1.4	<0.30
VINYL CHLORIDE UG/G-DRY	98795 10	<0.34	<0.26	<0.57	<0.60	<1.6	<0.96	<1.3	<0.29	<0.30	<0.43	<0.99	<0.28
PH,SOIL	99218 0	8.0	8.1	7.9	7.7	7.7	7.8	7.4	8.0	7.8	7.9	8.1	8.2
1,2-DIBROMOETHANE (EDB) MG/KG-DRY	98798 0	<0.004	<0.004	<0.007	<0.007	<0.02	<0.01	<0.02	<0.004	<0.004	<0.004	<0.003	<0.003
M-XYLENE MG/KG-DRY	98799 10	<0.08	<0.27	<0.58	<0.61	<1.7	<0.22	<1.3	<0.30	<0.31	<0.10	<0.23	<0.29
O,P-XYLENE MG/KG-DRY	98800 10	<0.08	<0.21	<0.46	<0.49	<1.3	<0.22	<1.0	<0.24	<0.24	<0.10	<0.22	<0.23
OIL&GR,IR,SED UG/G- DRY	561 0	112	119	250	219	656	147	806	225	2080	1670	1180	993
LEAD,SED UG/G-DRY	1052 0	<2.87	<2.81	<6.62	<6.15	<18.7	<9.57	<13.9	<3.18	<3.34	<3.94	<2.88	<3.08
MOISTURE %WET WT	70320 0	43.0	43.0	71.1	72.8	89.4	82.4	88.2	44.6	46.5	54.5	39.0	39.0
METHYL ETHYL KETONE UG/G-DRY	98801 10	0.008	<2.0	<4.3	<4.6	<12	<2.8	<9.4	<2.2	<2.1	<1.1	<3.6	<2.1
MIBK UG/G-DRY	98696 10	<0.96	<0.03	<0.62	<0.66	<1.8	<2.7	<1.4	<0.32	<0.34	<1.2	<2.8	<0.31
DICHLOROBENZENE,TOTAL UG/G-DRY	98803 10	<0.10	<0.17	<0.37	<0.39	<1.0	<0.30	<0.82	<0.19	<0.19	<0.13	<0.31	<0.18

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVPMS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	15S1A	15S2A	15S3A	15S4A	15S5A	15S6A	15S7A	15S8A	15S9C	15S10C	15S11C	15S12C	15S13C	15S14C	15S15C
		SAMPLE ID/#														
UNITS	METHOD	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01
		33	34	35	36	37	38	39	40	41	42	43	44	45	46	47
DATE		11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85	11/27/85
TIME		07:10	07:25	07:30	07:35	07:40	07:45	07:50	07:55	08:10	08:15	08:35	08:45	08:50	09:00	09:10
PCB 1016,SED	98140	<1.14	<1.13	<1.13	<1.12	<1.19	<1.25	<1.20	<1.17	<1.20	<1.22	<1.23	<1.48	<1.13	<1.19	<1.48
UG/G-DRY	0															
PCB-1221,SOIL	98351	<1.14	<1.13	<1.13	<1.12	<1.19	<1.25	<1.20	<1.17	<1.20	<1.22	<1.23	<1.48	<1.13	<1.19	<1.48
UG/G-DRY	0															
PCB-1232,SOIL	98352	<1.14	<1.13	<1.13	<1.12	<1.19	<1.25	<1.20	<1.17	<1.20	<1.22	<1.23	<1.48	<1.13	<1.19	<1.48
UG/G- DRY	0															
PCB-1242,SOIL	98353	<1.14	<1.13	<1.13	<1.12	<1.19	<1.25	<1.20	<1.17	<1.20	<1.22	<1.23	<1.48	<1.13	<1.19	<1.48
UG/G-DRY	0															
PCB1254-SOIL	98354	<1.14	<1.13	<1.13	<1.12	<1.19	<1.25	<1.20	<1.17	<1.20	<1.22	<1.23	<1.48	<1.13	<1.19	<1.48
UG/G- DRY	0															
PCB-1248 SOIL	98802	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1
UG/G-DRY	0															
PCB 1260,SED	98139	32.1	308	91.3	9.41	2.38	186	<1.20	8.18	<1.20	<1.22	<1.23	<1.48	<1.13	<1.19	<1.48
UG/G-DRY	0															
MOISTURE	70320	12.1	11.7	11.3	10.7	16.0	19.8	16.8	14.5	16.8	18.1	19.0	32.6	11.3	15.8	32.3
%WET WT	0															

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSO1 PROJECT MANAGER R. BOWEN
NAVPMS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	15S16A PRSO1
UNITS	METHOD	48
DATE		11/27/85
TIME		09:20
PCB 1016,SED	98140	<1.50
UG/G-DRY	0	
PCB-1221,SOIL	98351	<1.50
UG/G-DRY	0	
PCB-1232,SOIL	98352	<1.50
UG/G- DRY	0	
PCB-1242,SOIL	98353	<1.50
UG/G-DRY	0	
PCB1254-SOIL	98354	<1.50
UG/G- DRY	0	
PCB-1248 SOIL	98802	<1
UG/G-DRY	0	
PCB 1260,SED	98139	<1.50
UG/G-DRY	0	
MOISTURE	70320	33.2
%WET WT	0	

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVYPS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	16S1A PRS01 49	16S2A PRS01 50	16S3A PRS01 51	16S4A PRS01 52	16S5A PRS01 53	16S6A PRS01 54	16S7A PRS01 55	16S8A PRS01 56	16S8A PRS01 109	16S9A PRS01 57
DATE		11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	12/03/85	11/30/85
TIME		07:10	07:23	07:40	07:45	08:00	08:10	08:20	08:30	08:09	08:40
MOISTURE	70320	11.8	11.5	11.1	13.1	11.6	9.6	11.5	14.4	13.7	12.1
%WET WT	0										
OIL&GR,IR,SED	561	3910	420	6350	5720	919	574	1310	840	NRQ	221
UG/G- DRY	0										
PCB 1016,SED	98140	<1.13	<1.13	<1.12	<1.15	<1.13	<1.11	<1.13	<1.17	NRQ	4.78
UG/G-DRY	0										
PCB-1221,SOIL	98351	<1.13	<1.13	<1.12	<1.15	<1.13	<1.11	<1.13	<1.17	NRQ	<1.14
UG/G-DRY	0										
PCB-1232,SOIL	98352	<1.13	<1.13	<1.12	<1.15	<1.13	<1.11	<1.13	<1.17	NRQ	<1.14
UG/G- DRY	0										
PCB-1242,SOIL	98353	<1.13	<1.13	<1.12	<1.15	<1.13	<1.11	<1.13	<1.17	NRQ	<1.14
UG/G-DRY	0										
PCB1254-SOIL	98354	<1.13	<1.13	<1.12	<1.15	<1.13	<1.11	<1.13	<1.17	NRQ	<1.14
UG/G- DRY	0										
PCB-1248 SOIL	98802	<1	<1	<1	<1	<1	<1	<1	<1	NRQ	<1
UG/G-DRY	0										
PCB 1260,SED	98139	<1.13	404	92.9	55.9	3.39	8.85	22.8	<1.17	NRQ	2.73
UG/G-DRY	0										
BENZENE	98699	<0.06	<0.09	<0.04	<0.10	<0.10	<0.10	<0.10	NA	<0.07	<0.10
UG/G-DRY	10										
BROMODICHLOROMETHANE	98783	<0.08	<0.10	<0.08	<0.12	<0.13	<0.13	<0.12	NA	<0.13	<0.12
UG/G-DRY	10										
BROMOFORM	98784	<0.18	<0.25	<0.19	<0.27	<0.46	<0.47	<0.26	NA	<0.26	<0.27
UG/G-DRY	10										
BROMOMETHANE	98785	<0.22	<0.22	<0.18	<0.25	<0.21	<0.21	<0.24	NA	<0.26	<0.25
UG/G-DRY	10										
CARBON TETRACHLORIDE	98680	<0.07	<0.09	<0.16	<0.09	<0.11	<2.2	<0.09	NA	<0.23	<0.09
UG/G-DRY	10										
CHLOROBENZENE	98681	<0.06	<0.08	<0.06	<0.08	<0.08	<0.09	<0.08	NA	<0.09	<0.09
UG/G-DRY	10										
CHLOROETHANE	98786	<0.43	<0.46	<0.26	<0.55	<0.63	<0.64	<0.54	NA	<0.36	<0.56
UG/G-DRY	10										
2-CHLOROETHYLVINYLETHER UG/G-DRY	98796 10	<0.81	<0.49	<0.17	<0.53	<0.89	<0.91	<0.52	NA	<0.27	<0.54
CHLOROFORM	98682	<0.068	<0.090	<0.072	<0.102	<0.101	<4.43	<0.100	NA	<0.111	<0.104
UG/G-DRY	10										
CHLOROMETHANE	98787	<0.21	<0.22	<0.21	<0.39	<0.35	<0.36	<0.39	NA	<0.34	<0.40
UG/G-DRY	10										
DIBROMOCHLOROMETHANE	98788	<0.12	<0.17	<0.14	<0.17	<0.23	<0.23	<0.17	NA	<0.20	<0.18
UG/G-DRY	10										

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSOI PROJECT MANAGER R. BOWEN
NAVYPS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	16S1A PRSOI 49	16S2A PRSOI 50	16S3A PRSOI 51	16S4A PRSOI 52	16S5A PRSOI 53	16S6A PRSOI 54	16S7A PRSOI 55	16S8A PRSOI 56	16S8A PRSOI 109	16S9A PRSOI 57
DATE		11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	12/03/85	11/30/85
TIME		07:10	07:23	07:40	07:45	08:00	08:10	08:20	08:30	08:09	08:40
1,1-DICHLOROETHANE UG/G-DRY	98683 10	<0.11	<0.14	<0.07	<0.18	<0.16	<0.16	<0.18	NA	<0.10	<0.18
1,2-DICHLOROETHANE UG/G-DRY	98684 10	<0.09	<0.12	<0.13	<0.14	<0.13	<1.7	<0.14	NA	<0.21	<0.15
1,1-DICHLOROETHENE UG/G-DRY	98789 10	<0.20	<0.24	<0.15	<0.30	<0.30	<0.31	<0.30	NA	<0.21	<0.31
TRANS-1,2-DICHLOROETENE UG/G-DRY	98687 10	<0.20	<0.23	<0.14	<0.30	<0.31	<0.32	<0.29	NA	<0.21	<0.30
1,2-DICHLOROPROPANE UG/G-DRY	98790 10	<0.19	<0.30	<0.08	<0.33	<0.27	<0.28	<0.33	NA	<0.14	<0.34
CIS-1,3-DICHLOROPROPENE UG/G-DRY	98791 10	<0.08	<0.11	<0.06	<0.12	<0.14	<0.14	<0.12	NA	<0.10	<0.12
TRANS-1,3-DICHLOROPROPENE UG/G-DRY	98792 10	<0.08	<0.11	<0.16	<0.12	<0.36	<0.37	<0.12	NA	<0.28	<0.12
ETHYLBENZENE UG/G-DRY	98688 10	<0.13	<0.17	<0.13	<0.19	<0.18	<0.19	<0.19	NA	<0.22	<0.19
METHYLENE CHLORIDE UG/G-DRY	98689 10	<0.16	<1.5	<0.13	<0.26	<6.1	<35	<0.26	NA	<0.20	<0.27
1,1,2,2-TETRACHLOROETHANE UG/G-DRY	98793 10	<0.24	<0.33	<0.09	<0.40	<0.29	<0.29	<0.39	NA	<0.12	<0.40
TETRACHLOROETHENE UG/G-DRY	98690 10	<0.12	<0.16	<0.21	<0.17	<0.18	<1.2	<0.17	NA	<0.29	<0.17
TOLUENE UG/G-DRY	98691 10	<0.09	<0.12	<0.07	<0.13	<0.13	<0.13	<0.13	NA	<0.11	<0.13
1,1,1-TRICHLOROETHANE UG/G-DRY	98692 10	<0.08	<0.10	<0.14	<0.11	<0.12	<0.71	<0.11	NA	<0.23	<0.11
1,1,2-TRICHLOROETHANE UG/G-DRY	98693 10	<0.18	<0.25	<0.14	<0.25	<0.27	<0.28	<0.25	NA	<0.20	<0.26
TRICHLOROETHENE UG/G-DRY	98694 10	<0.11	<0.16	<0.14	<0.19	<0.18	<0.18	<0.19	NA	<0.21	<0.20
TRICHLOROFLUOROMETHANE UG/G-DRY	98794 10	<0.30	<0.34	<0.11	<0.36	<0.34	<0.35	<0.35	NA	<0.20	<0.37
VINYL CHLORIDE UG/G-DRY	98795 10	<0.19	<0.19	<0.17	<0.28	<0.35	<0.36	<0.28	NA	<0.23	<0.29
DICHLOROBENZENE,TOTAL UG/G-DRY	98803 10	<0.07	<0.08	<0.08	<0.07	<0.09	<0.09	<0.07	NA	<0.13	<0.07
LEAD,SED UG/G-DRY	1052 0	109	<3.25	15700	834	151	12.7	69.8	215	NRQ	<2.81
1,2-DIBROMOETHANE (EDB) MG/KG-DRY	98798 0	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	<0.002	NRQ	<0.002

RR-00039-03.13-04/01/88

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVYPS LAB COORDINATOR LISA BARE

PARAMETERS	UNITS	STORET # METHOD	SAMPLE ID/# 16S1A PRS01 49	16S2A PRS01 50	16S3A PRS01 51	16S4A PRS01 52	16S5A PRS01 53	16S6A PRS01 54	16S7A PRS01 55	16S8A PRS01 56	16S8A PRS01 109	16S9A PRS01 57
DATE			11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	11/30/85	12/03/85	11/30/85
TIME			07:10	07:23	07:40	07:45	08:00	08:10	08:20	08:30	08:09	08:40
M-XYLENE	MG/KG-DRY	98799 10	<0.05	<0.05	<0.04	<0.05	<0.05	<0.05	<0.05	NA	<0.19	<0.05
O,P-XYLENE	MG/KG-DRY	98800 10	<0.04	<0.05	<0.02	<0.05	<0.19	<0.43	<0.05	NA	<0.08	<0.05
METHYL ETHYL KETONE	UG/G-DRY	98801 10	<0.58	<2.4	<0.17	1.0	<11	<7.6	<0.98	NA	<1.5	1.0
MIBK	UG/G-DRY	98696 10	<0.45	<0.62	<0.14	<0.68	<0.30	<0.31	<0.67	NA	<0.19	<0.69

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSWI PROJECT MANAGER RUSS BOWEN
NAVPSW LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	18SW1 PRSWI 40	18SW2 PRSWI 41
DATE			11/26/85	11/26/85
TIME			08:50	09:05
ALDRIN		39330	<0.010	<0.010
	UG/L	0		
BHC,A		39337	<0.006	<0.006
	UG/L	0		
BHC,B		39338	<0.015	<0.015
	UG/L	0		
BHC-D		34259	<0.019	<0.019
	UG/L	0		
BHC,G(LINDANE)		39340	<0.015	<0.015
	UG/L	0		
CHLORDANE		39350	0.571	0.616
	UG/L	0		
DDD,PP'		39310	<0.156	<0.156
	UG/L	0		
DDE,PP'		39320	<0.024	<0.024
	UG/L	0		
DDT,PP'		39300	<0.089	<0.089
	UG/L	0		
DIELDRIN		39380	<0.027	<0.027
	UG/L	0		
ENDOSULFAN,A		34361	<0.024	<0.024
	UG/L	0		
ENDOSULFAN,B		34356	<0.062	<0.062
	UG/L	0		
ENDOSULFAN SULFATE		34351	<0.417	<0.417
	UG/L	0		
ENDRIN		39390	<0.069	<0.069
	UG/L	0		
ENDRIN ALDEHYDE		34366	<0.069	<0.069
	UG/L	0		
HEPTACHLOR		39410	<0.009	<0.009
	UG/L	0		
HEPTACHLOR EPOXIDE		39420	<0.015	<0.015
	UG/L	0		
TOXAPHENE		39400	<1.95	<1.95
	UG/L	0		

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRSE1 PROJECT MANAGER RUSS BOWEN
NAVPSM LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	18SE1 PRSE1 69	18SE2 PRSE1 70
DATE			11/26/85	11/26/85
TIME			09:15	09:33
ALDRIN,SED		98356	<0.517	<0.628
	UG/G- DRY	0		
BHC,A,SED		98357	<0.517	<0.628
	UG/G-DRY	0		
BHC,B,SED		98358	<0.517	<0.628
	UG/G-DRY	0		
BHC,D,SED		98359	<0.517	<0.628
	UG/G-DRY	0		
BHC,G,SED		98360	<0.517	<0.628
	UG/G-DRY	0		
CHLORDANE,SED		98361	34.1	66.7
	UG/G- DRY	0		
DDD,PP'		98362	<0.517	<0.628
	UG/G-DRY	0		
DDE,PP'		98363	1.37	2.63
	UG/G-DRY	0		
DDT,PP'		98364	<0.517	<0.628
	UG/G-DRY	0		
DIELDRIN		98365	<0.517	<0.628
	UG/G-DRY	0		
ENDOSULFAN,A		98366	3.32	3.44
	UG/G- DRY	0		
ENDOSULFAN,B		98367	4.38	7.65
	UG/G- DRY	0		
ENDOSULFAN SULFATE		98368	<0.517	<0.628
	UG/G-DRY	0		
ENDRIN		98369	<0.517	<0.628
	UG/G-DRY.	0		
ENDRIN ALDEHYDE MG/K		98370	<0.517	<0.628
G-DRY	MG/KG-DRY	0		
HEPTACHLOR		98371	<0.517	<0.628
	UG/G- DRY	0		
HEPTACHLOR EPOXIDE		98372	<0.517	<0.628
	UG/G-DRY	0		
TOXAPHENE		98373	<20.7	<25.1
	UG/G- DRY	0		
MOISTURE		70320	51.6	60.2
	%WET WT	0		

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 05/12/86 STATUS: FINAL PAGE# 1

PROJECT NUMBER 85275 3000 PROJECT NAME PUERTO RICO CONFIRMATION STUDY
FIELD GROUP PRS01 PROJECT MANAGER R. BOWEN
NAVPSM LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	18S1A	18S2A	18S3A	18S4A	18S5A	18S6C	18S7C	18S8C	18S9C	18S10C	18S11C	18S12C	18S13C	18S14C	18S15C
UNITS	METHOD	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01	PRS01
		58	59	60	61	62	63	64	65	66	67	68	69	70	71	72
DATE		11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85	11/26/85
TIME		10:00	10:10	10:25	10:35	10:40	11:00	11:11	11:22	11:27	11:35	11:40	11:55	11:56	12:00	12:05
ALDRIN,SED	98356	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	0.803	<0.291	0.761	2.06	<0.285
UG/G- DRY	0															
BHC,A,SED	98357	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	<0.288	<0.285
UG/G-DRY	0															
BHC,B,SED	98358	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<11.5	<5.83	<0.297	<2.88	<0.285
UG/G-DRY	0															
BHC,D,SED	98359	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	<0.288	<0.285
UG/G-DRY	0															
BHC,G,SED	98360	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<11.5	<0.291	<0.297	<0.288	<0.285
UG/G-DRY	0															
CHLORDANE,SED	98361	<3.21	<2.78	<2.47	<2.97	<2.64	<2.15	<2.11	<2.13	<2.23	<2.28	57.4	38.3	142	181	<2.28
UG/G- DRY	0															
DDD,PP'	98362	<0.402	<0.348	6.65	17.3	55.3	1.84	<0.264	<0.266	1.68	<0.285	1.90	0.752	<0.297	<2.88	<0.285
UG/G-DRY	0															
DDE,PP'	98363	<0.402	<0.348	2.23	<14.8	<13.2	2.10	0.549	<0.266	3.16	23.1	11.5	36.4	<0.297	7.93	0.750
UG/G-DRY	0															
DDT,PP'	98364	<0.402	<0.348	<1.54	<1.86	<13.2	<0.268	<0.264	<0.266	6.92	88.1	130	208	<0.297	7.24	<0.285
UG/G-DRY	0															
DIELDRIN	98365	<0.402	<0.348	<0.309	<0.371	<13.2	<0.268	<0.264	<0.266	<0.279	<0.285	<11.5	<29.1	<0.297	<0.288	<0.285
UG/G-DRY	0															
ENDOSULFAN,A	98366	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	<2.88	<0.285
UG/G- DRY	0															
ENDOSULFAN,B	98367	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	<2.88	<0.285
UG/G- DRY	0															
ENDOSULFAN SULFATE	98368	<0.402	<0.348	<0.309	<0.371	<0.330	2.54	2.16	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	<0.288	<0.285
UG/G-DRY	0															
ENDRIN	98369	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	13.2	<0.285
UG/G-DRY.	0															
ENDRIN ALDEHYDE MG/K	98370	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<0.288	<0.291	<0.297	<0.288	<0.285
G-DRY MG/KG-DRY	0															
HEPTACHLOR	98371	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<11.5	<29.1	<0.297	<2.88	<0.285
UG/G- DRY	0															
HEPTACHLOR EPOXIDE	98372	<0.402	<0.348	<0.309	<0.371	<0.330	<0.268	<0.264	<0.266	<0.279	<0.285	<11.5	<0.291	<0.297	0.993	<0.285
UG/G-DRY	0															
TOXAPHENE	98373	<16.1	<13.9	<12.4	<14.8	<13.2	<10.7	<10.6	<10.6	<11.1	<11.4	<11.5	<11.7	<11.9	<11.5	<11.4
UG/G- DRY	0															
MOISTURE	70320	37.8	28.1	19.1	32.6	24.1	6.8	5.3	5.9	10.3	12.3	13.1	14.2	15.9	13.1	12.3
%WET WT	0															

RR-00039-03.13-04/01/88

APPENDIX B

LABORATORY DATA FOR ROUND 2 OF VERIFICATION SAMPLING AND ANALYSIS

ENVIRONMENTAL SCIENCE & ENGINEERING 02/[illegible]/88 STATUS: FINAL PAGE# 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPRIW PROJECT MANAGER RUSS BOWEN
VIEQUES SITE I WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	IGW01 VQPRIW 1	IGW02 VQPRIW 2	IGW03 VQPRIW 3
DATE			11/16/87	11/16/87	11/16/87
TIME			12:30	09:50	11:00
WATER TEMP	C	10 0	26.0	27.1	26.4
PH,FIELD	STD UNITS	400 0	7.00	7.60	7.20
SP.COND.,FIELD@25C	UMHOS/CM	94 0	807	1660	455
BENZENE	UG/L	34030 GMS	<1.0	<1.0	<1.0
BROMODICHLOROMETHANE	UG/L	32101 GMS	<2.2	<2.2	<2.2
BROMOFORM	UG/L	32104 GMS	<4.7	<4.7	<4.7
BROMOMETHANE	UG/L	34413 GMS	<5.8	<5.8	<5.8
CARBON TETRACHLORIDE	UG/L	32102 GMS	<2.8	<2.8	<2.8
CHLOROBENZENE	UG/L	34301 GMS	<6.0	<6.0	<6.0
CHLOROETHANE	UG/L	34311 GMS	<8.2	<8.2	<8.2
2-CHLOROETHYLVINYL ETHER	UG/L	34576 GMS	<15	<15	<15
CHLOROFORM	UG/L	32106 GMS	<1.6	<1.6	<1.6
CHLOROMETHANE	UG/L	34418 GMS	<4.3	<4.3	<4.3
DIBROMOCHLOROMETHANE	UG/L	32105 GMS	<3.1	<3.1	<3.1
1,1-DICHLOROETHANE	UG/L	34496 GMS	<4.7	<4.7	<4.7
1,2-DICHLOROETHANE	UG/L	34531 GMS	<2.8	<2.8	<2.8
1,1-DICHLOROETHYLENE	UG/L	34501 GMS	<2.8	<2.8	<2.8
TRANS-1,2-DICHLORO ETHENE	UG/L	34546 GMS	<1.6	<1.6	<1.6
1,2-DICHLOROPROPANE	UG/L	34541 GMS	<6.0	<6.0	<6.0
CIS-1,3-DICHLORO PROPENE	UG/L	34704 GMS	<5.0	<5.0	<5.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPRIW PROJECT MANAGER RUSS BOWEN
VIEQUES SITE I WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	IGW01 VQPRIW 1	IGW02 VQPRIW 2	IGW03 VQPRIW 3
DATE		11/16/87	11/16/87	11/16/87
TIME		12:30	09:50	11:00
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12	<12
M-XYLENE UG/L	98553 GMS	<12	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<12
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.010	<0.010	<0.010
ACENAPHTHENE UG/L	34205 GMS	<1.0	<1.0	<1.0
ACENAPHTHYLENE UG/L	34200 GMS	<1.0	<1.0	<1.0
ANTHRACENE UG/L	34220 GMS	<1.0	<1.0	<1.0
BENZIDINE UG/L	39120 GMS	<2.1	<2.1	<2.1

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR1W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 1 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	1GW01 VQPR1W 1	1GW02 VQPR1W 2	1GW03 VQPR1W 3
UNITS	METHOD			
DATE		11/16/87	11/16/87	11/16/87
TIME		12:30	09:50	11:00
BENZO(A)ANTHRACENE	34526	<1.0	<1.0	<1.0
UG/L	GMS			
BENZO(B)FLUORANTHENE	34230	<1.5	<1.5	<1.5
UG/L	GMS			
BENZO(K)FLUORANTHENE	34242	<1.5	<1.5	<1.5
UG/L	GMS			
BENZO(A)PYRENE	34247	<1.5	<1.5	<1.5
UG/L	GMS			
BENZO(GHI)PERYLENE	34521	<2.0	<2.0	<2.0
UG/L	GMS			
BUTYLBENZYLPHTHALATE	34292	<1.0	<1.0	<1.0
UG/L	GMS			
BIS(2-CHLOROETHYL)	34273	<1.0	<1.0	<1.0
ETHER UG/L	GMS			
BIS(2-CHLOROETHOXY)	34278	<1.0	<1.0	<1.0
METHANE UG/L	GMS			
BIS(2-ETHYLHEXYL)	39100	<1.0	<1.0	<1.0
PHTHALATE UG/L	GMS			
BIS(2-CHL'ISOPROPYL)	34283	<1.0	<1.0	<1.0
ETHER UG/L	GMS			
4-BROMOPHENYLPHENYL	34636	<1.0	<1.0	<1.0
ETHER UG/L	GMS			
2-CHLORONAPHTHALENE	34581	<1.0	<1.0	<1.0
UG/L	GMS			
2-CHLOROPHENOL	34586	<1.7	<1.7	<1.7
UG/L	GMS			
4-CHLORO-3-METHYL	34452	<1.4	<1.4	<1.4
PHENOL UG/L	GMS			
4-CHLOROPHENYLPHENYL	34641	<1.0	<1.0	<1.0
ETHER UG/L	GMS			
CHRYSENE	34320	<1.0	<1.0	<1.0
UG/L	GMS			
DIBEN'(A,H)ANTH'CENE	34556	<2.0	<2.0	<2.0
UG/L	GMS			
DI-N-BUTYLPHTHALATE	39110	<1.0	<1.0	<1.0
UG/L	GMS			
1,3,DICHLOROBENZENE	34566	<1.0	<1.0	<1.0
UG/L	GMS			
1,2-DICHLOROBENZENE	34536	<1.0	<1.0	<1.0
UG/L	GMS			

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR1W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 1 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	1GW01 VQPR1W 1	1GW02 VQPR1W 2	1GW03 VQPR1W 3
DATE		11/16/87	11/16/87	11/16/87
TIME		12:30	09:50	11:00
1,4-DICHLOROBENZENE UG/L	34571 GMS	<1.0	<1.0	<1.0
3,3'-DICHL'BENZIDINE UG/L	34631 GMS	<1.5	<1.5	<1.5
2,4-DICHLOROPHENOL UG/L	34601 GMS	<1.4	<1.4	<1.4
DIETHYLPHTHALATE UG/L	34336 GMS	<1.0	<1.0	<1.0
2,4-DIMETHYLPHENOL UG/L	34606 GMS	<1.4	<1.4	<1.4
DIMETHYLPTHALATE UG/L	34341 GMS	<1.0	<1.0	<1.0
2,4-DINITROPHENOL UG/L	34616 GMS	<30	<30	<30
2,4-DINITROTOLUENE UG/L	34611 GMS	<1.0	<1.0	<1.0
2,6-DINITROTOLUENE UG/L	34626 GMS	<1.0	<1.0	<1.0
DI-N-OCTYLPHTHALATE UG/L	34596 GMS	<1.1	<1.1	<1.1
FLUORANTHENE UG/L	34376 GMS	<1.0	<1.0	<1.0
FLUORENE UG/L	34381 GMS	<1.0	<1.0	<1.0
HEXACHLOROBENZENE UG/L	39700 GMS	<1.0	<1.0	<1.0
HEXACHLOROBUTADIENE UG/L	34391 GMS	<1.0	<1.0	<1.0
HEXACHLOROCYCLOPENTA DIENE UG/L	34386 GMS	<2.0	<2.0	<2.0
HEXACHLOROETHANE UG/L	34396 GMS	<1.5	<1.5	<1.5
INDENO(1,2,3-CD) PYRENE UG/L	34403 GMS	<2.0	<2.0	<2.0
ISOPHORONE UG/L	34408 GMS	<1.0	<1.0	<1.0
2-METHYL-4,6-DINITRO PHENOL UG/L	34657 GMS	<5.0	<5.0	<5.0
NAPHTHALENE UG/L	34696 GMS	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPRIW PROJECT MANAGER RUSS BOWEN
VIEQUES SITE I WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	IGW01 VQPRIW 1	IGW02 VQPRIW 2	IGW03 VQPRIW 3
DATE		11/16/87	11/16/87	11/16/87
TIME		12:30	09:50	11:00
NITROBENZENE UG/L	34447 GMS	<1.0	<1.0	<1.0
2-NITROPHENOL UG/L	34591 GMS	<1.4	<1.4	<1.4
4-NITROPHENOL UG/L	34646 GMS	<3.3	<3.3	<3.3
N-NITROSODIMET'AMINE UG/L	34438 GMS	<1.0	<1.0	<1.0
N-NITROSODI-N-PROPYL AMINE UG/L	34428 GMS	<1.0	<1.0	<1.0
N-NITROSODIPHE'AMINE UG/L	34433 GMS	<1.0	<1.0	<1.0
PENTACHLOROPHENOL UG/L	39032 GMS	<10	<10	<10
PHENANTHRENE UG/L	34461 GMS	<1.0	<1.0	<1.0
PHENOL UG/L	34694 GMS	<1.3	<1.3	<1.3
PYRENE UG/L	34469 GMS	<1.0	<1.0	<1.0
1,2,4-TRICH'BENZENE UG/L	34551 GMS	<1.0	<1.0	<1.0
2,4,6-TRICHL'PHENOL UG/L	34621 GMS	<1.8	<1.8	<1.8
ALDRIN UG/L	39330 EC	<0.005	<0.005	<0.005
BHC,A UG/L	39337 EC	<0.005	<0.005	<0.005
BHC,B UG/L	39338 EC	<0.005	<0.005	<0.005
BHC,D UG/L	34259 EC	<0.005	<0.005	<0.005
BHC,G(LINDANE) UG/L	39340 EC	<0.005	<0.005	<0.005
CHLORDANE UG/L	39350 EC	<0.006	<0.006	<0.006
DDD,PP' UG/L	39310 EC	<0.005	<0.005	<0.005
DDE,PP' UG/L	39320 EC	<0.005	<0.005	<0.005

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPRIW PROJECT MANAGER RUSS BOWEN
VIEQUES SITE : WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	IGW01 VQPRIW 1	IGW02 VQPRIW 2	IGW03 VQPRIW 3
DATE			11/16/87	11/16/87	11/16/87
TIME			12:30	09:50	11:00
DDT,PP'	UG/L	39300 EC	<0.005	<0.005	<0.005
DIELDRIN	UG/L	39380 EC	<0.005	<0.005	<0.005
ENDOSULFAN,A	UG/L	34361 EC	<0.005	<0.005	<0.005
ENDOSULFAN,B	UG/L	34356 EC	<0.005	<0.005	<0.005
ENDOSULFAN SULFATE	UG/L	34351 EC	<0.005	<0.005	<0.005
ENDRIN	UG/L	39390 EC	<0.005	<0.005	<0.005
ENDRIN ALDEHYDE	UG/L	34366 EC	<0.005	<0.005	<0.005
HEPTACHLOR	UG/L	39410 EC	<0.005	<0.005	<0.005
HEPTACHLOR EPOXIDE	UG/L	39420 EC	<0.005	<0.005	<0.005
TOXAPHENE	UG/L	39400 EC	<0.600	<0.600	<0.600
PCB-1016	UG/L	34671 EC	<0.121	<0.121	<0.121
PCB-1221	UG/L	39488 EC	<0.121	<0.121	<0.121
PCB-1232	UG/L	39492 EC	<0.121	<0.121	<0.121
PCB-1242	UG/L	39496 EC	<0.121	<0.121	<0.121
PCB 1248	UG/L	39500 EC	<0.121	<0.121	<0.121
PCB-1254	UG/L	39504 EC	<0.121	<0.121	<0.121
PCB-1260	UG/L	39508 EC	<0.121	<0.121	<0.121
ANTIMONY,TOTAL	UG/L	1097 ICAP	<39.0	<39.0	<39.0
ARSENIC,TOTAL	UG/L	1002 GFAA	<1.6	<1.6	<1.6
BERYLLIUM, TOTAL	UG/L	1012 ICAP	<0.7	<0.7	<0.7

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPRIW PROJECT MANAGER RUSS BOWEN
VIEQUES SITE I WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	IGW01	IGW02	IGW03
		VQPRIW	VQPRIW	VQPRIW
UNITS	METHOD	1	2	3
DATE		11/16/87	11/16/87	11/16/87
TIME		12:30	09:50	11:00
CADMIUM,TOTAL	1027	13.0	6.0	6.0
UG/L	ICAP			
CHROMIUM,TOTAL	1034	512	221	173
UG/L	ICAP			
COPPER,TOTAL	1042	629	121	168
UG/L	ICAP			
LEAD,TOTAL	1051	<21.0	<21.0	<21.0
UG/L	ICAP			
MERCURY,TOTAL	71900	<0.2	<0.2	<0.2
UG/L	CVAA			
NICKEL,TOTAL	1067	215	108	74.0
UG/L	ICAP			
SELENIUM,TOTAL	1147	<2.0	<2.0	<2.0
UG/L	GFAA			
SILVER,TOTAL	1077	<2.5	<2.5	<2.5
UG/L	ICAP			
THALLIUM,TOTAL	1059	<2.8	<2.8	<2.8
UG/L	GFAA			
ZINC,TOTAL	1092	400	113	193
UG/L	ICAP			
PHENOLS	32730	<2	<2	<2
UG/L	1			
CHROMIUM,(+6)	1032	73.2	<10.0	<10.0
UG/L	1			

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000
FIELD GROUP VQPR2W
VIEQUES SITE 2 WATERS

PROJECT NAME PUERTO RICO - NAF VIEQUES
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET #	METHOD	2SW01 VQPR2W 1	2SW02 VQPR2W 2	2SW03 VQPR2W 3	2SW04 VQPR2W 4	2SW05 VQPR2W 5
DATE				11/09/87	11/09/87	11/09/87	11/09/87	11/09/87
TIME				09:30	10:00	10:45	11:30	12:15
WATER TEMP	C	10	0	29.0	28.6	28.7	32.7	30.0
PH,FIELD	STD UNITS	400	0	7.90	7.90	8.00	8.40	7.80
SP.COND.,FIELD@25C	UMHOS/CM	94	0	15,000	47,800	46,800	47,300	42,200
BENZENE	UG/L	34030	GMS	<1.0	<1.0	<1.0	<1.0	<1.0
BROMODICHLOROMETHANE	UG/L	32101	GMS	<2.2	<2.2	<2.2	<2.2	<2.2
BROMOFORM	UG/L	32104	GMS	<4.7	<4.7	<4.7	<4.7	<4.7
BROMOMETHANE	UG/L	34413	GMS	<5.8	<5.8	<5.8	<5.8	<5.8
CARBON TETRACHLORIDE	UG/L	32102	GMS	<2.8	<2.8	<2.8	<2.8	<2.8
CHLOROBENZENE	UG/L	34301	GMS	<6.0	<6.0	<6.0	<6.0	<6.0
CHLO ETHANE	UG/L	34311	GMS	<8.2	<8.2	<8.2	<8.2	<8.2
2-CI OETHYLVINYL ETHE	UG/L	34576	GMS	<15	<15	<15	<15	<15
CHLOROFORM	UG/L	32106	GMS	<1.6	<1.6	<1.6	<1.6	<1.6
CHLOROMETHANE	UG/L	34418	GMS	<4.3	<4.3	<4.3	<4.3	<4.3
DIBROMOCHLOROMETHANE	UG/L	32105	GMS	<3.1	<3.1	<3.1	<3.1	<3.1
1,1-DICHLOROETHANE	UG/L	34496	GMS	<4.7	<4.7	<4.7	<4.7	<4.7
1,2-DICHLOROETHANE	UG/L	34531	GMS	<2.8	<2.8	<2.8	<2.8	<2.8
1,1-DICHLOROETHYLENE	UG/L	34501	GMS	<2.8	<2.8	<2.8	<2.8	<2.8
TRANS-1,2-DICHLORO ETHENE	UG/L	34546	GMS	<1.6	<1.6	<1.6	<1.6	<1.6
1,2-DICHLOROPROPANE	UG/L	34541	GMS	<6.0	<6.0	<6.0	<6.0	<6.0
CIS-1,3-DICHLORO PROPENE	UG/L	34704	GMS	<5.0	<5.0	<5.0	<5.0	<5.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR2W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 2 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	2SW01 VQPR2W 1	2SW02 VQPR2W 2	2SW03 VQPR2W 3	2SW04 VQPR2W 4	2SW05 VQPR2W 5
DATE		11/09/87	11/09/87	11/09/87	11/09/87	11/09/87
TIME		09:30	10:00	10:45	11:30	12:15
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0	<1.0	<1.0
M-XYLENE UG/L	98553 GMS	<12	<12	<12	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<12	<12	<12
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48	<48	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12	<12	<12	<12
LEAD,TOTAL UG/L	1051 GFAA	<4.4	<4.4	<4.4	8.4	<4.4
CHROMIUM,TOTAL UG/L	1034 ICAP	<7.6	<7.6	<7.6	<7.6	<7.6
CHROMIUM,(+6) UG/L	1032 1	<10.0	<10.0	<10.0	<10.0	<10.0

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE# 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR2S PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 2 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	2SE01 VQPR2S 1	2SE02 VQPR2S 2	2SE03 VQPR2S 3	2SE04 VQPR2S 4	2SE05 VQPR2S 5
DATE			11/09/87	11/09/87	11/09/87	11/09/87	11/09/87
TIME			09:40	10:10	11:00	11:45	12:30
MOISTURE		70320	27.5	22.5	24.2	34.8	48.3
	%WET WT	1					
PH,SOIL		99218	8.2	8.1	8.0	8.0	7.9
	STD UNITS	1					
CHROMIUM(+6),SED		29405	<13.8	<12.9	<13.2	<15.3	<19.3
	MG/KG-DRY	1					
CHROMIUM,SED		1029	36.2	9.38	16.0	8.13	8.49
	UG/G- DRY	ICAP					
LEAD,SED		1052	2.82	3.15	25.0	219	312
	UG/G-DRY	GFAA					
BENZENE		34237	<300	<280	<290	<340	<430
	UG/KG-DRY	GMS					
BROMODICHLOROMETHANE		34330	<150	<140	<150	<170	<210
	UG/KG-DRY	GMS					
BROMOFORM		34290	<320	<300	<310	<360	<450
	UG/KG-DRY	GMS					
BROMOMETHANE		34416	<390	<360	<370	<430	<540
	UG/KG-DRY	GMS					
CARBON TETRACHLORIDE		34299	<190	<180	<180	<210	<270
	UG/KG-DRY	GMS					
CHLOROBENZENE		34304	<410	<390	<400	<460	<580
	UG/KG-DRY	GMS					
CHLOROETHANE		34314	<570	<530	<540	<630	<790
	UG/KG-DRY	GMS					
2-CHLOROETHYLVINYL		34579	<690	<650	<660	<770	<970
ETHER	UG/KG-DRY	GMS					
CHLOROFORM		34318	<110	<100	<110	<120	<150
	UG/KG-DRY	GMS					
CHLOROMETHANE		34421	<300	<280	<280	<330	<420
	UG/KG-DRY	GMS					
DIBROMOCHLOROMETHANE		34309	<210	<200	<200	<240	<300
	UG/KG-DRY	GMS					
1,1-DICHLOROETHANE		34499	<320	<300	<310	<360	<450
	UG/KG-DRY	GMS					
1,2-DICHLOROETHANE		34534	<190	<180	<180	<210	<270
	UG/KG-DRY	GMS					
1,1-DICHLOROETHYLENE		34504	<190	<180	<180	<210	<270
	UG/KG-DRY	GMS					
TRANS-1,2-DICHLORO		34549	<110	<100	<110	<120	<150
ETHENE	UG/KG-DRY	GMS					

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000
FIELD GROUP VQPR2S
VIEQUES SITE 2 SOILS

PROJECT NAME PUERTO RICO - NAF VIEQUES
PROJECT MANAGER RUSS BOWEN
LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	2SE01 VQPR2S 1	2SE02 VQPR2S 2	2SE03 VQPR2S 3	2SE04 VQPR2S 4	2SE05 VQPR2S 5
DATE		11/09/87	11/09/87	11/09/87	11/09/87	11/09/87
TIME		09:40	10:10	11:00	11:45	12:30
1,2-DICHLOROPROPANE UG/KG-DRY	34544 GMS	<410	<390	<400	<460	<580
CIS-1,3-DICHLORO PROPENE UG/KG-DRY	34702 GMS	<340	<320	<330	<380	<480
TRANS-1,3-DICHLORO PROPENE UG/KG-DRY	34697 GMS	<440	<410	<420	<490	<620
ETHYLBENZENE UG/KG-DRY	34374 GMS	<500	<460	<470	<550	<700
METHYLENE CHLORIDE UG/KG-DRY	34426 GMS	<1400	<1300	<1300	<1500	<1900
1,1,2,2-TETRACHLORO ETHANE UG/KG-DRY	34519 GMS	<280	<260	<270	<310	<400
TETRACHLOROETHENE UG/KG-DRY	34478 GMS	<280	<260	<270	<310	<400
TOLUENE UG/KG-DRY	34483 GMS	<410	<390	<400	<460	<580
1,1,1-TRICHL'ETHANE UG/KG-DRY	34509 GMS	<260	<250	<250	<290	<370
1,1,2-TRICHL'ETHANE UG/KG-DRY	34514 GMS	<340	<320	<330	<380	<480
TRICHLOROETHENE UG/KG-DRY	34487 GMS	<130	<120	<130	<150	<180
TRICHLOROFLUOROMETHA NE UG/KG-DRY	34491 GMS	<220	<210	<210	<250	<310
VINYL CHLORIDE UG/KG-DRY	34495 GMS	<340	<320	<320	<380	<470
M-XYLENE UG/KG-DRY	97016 GMS	<410	<390	<400	<460	<580
O,P-XYLENE UG/KG-DRY	97017 GMS	<410	<390	<400	<460	<580
METHYL ETHYL KETONE UG/KG-DRY	75078 GMS	<3300	<3100	<3200	<3700	<4600
METHYL ISOBUT'KETONE UG/KG-DRY	75169 GMS	<830	<770	<790	<920	<1200

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE# 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # / METHOD	3PW01 VQPR3W 1
DATE			11/18/87
TIME			11:00
WATER TEMP	C	10 / 0	25.5
PH,FIELD	STD UNITS	400 / 0	7.90
SP.COND.,FIELD@25C	UMHOS/CM	94 / 0	895
BENZENE	UG/L	34030 / GMS	<1.0
BROMODICHLOROMETHANE	UG/L	32101 / GMS	<2.2
BROMOFORM	UG/L	32104 / GMS	<4.7
BROMOMETHANE	UG/L	34413 / GMS	<5.8
CARBON TETRACHLORIDE	UG/L	32102 / GMS	<2.8
CHLOROBENZENE	UG/L	34301 / GMS	<6.0
CHLOROETHANE	UG/L	34311 / GMS	<8.2
2-CHLOROETHYLVINYL ETHER	UG/L	34576 / GMS	<15
CHLOROFORM	UG/L	32106 / GMS	<1.6
CHLOROMETHANE	UG/L	34418 / GMS	<4.3
DIBROMOCHLOROMETHANE	UG/L	32105 / GMS	<3.1
1,1-DICHLOROETHANE	UG/L	34496 / GMS	<4.7
1,2-DICHLOROETHANE	UG/L	34531 / GMS	<2.8
1,1-DICHLOROETHYLENE	UG/L	34501 / GMS	<2.8
TRANS-1,2-DICHLORO ETHENE	UG/L	34546 / GMS	<1.6
1,2-DICHLOROPROPANE	UG/L	34541 / GMS	<6.0
CIS-1,3-DICHLORO PROPENE	UG/L	34704 / GMS	<5.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	3PW01 VQPR3W 1
DATE		11/18/87
TIME		11:00
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0
TOLUENE UG/L	34010 GMS	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0
ACENAPHTHENE UG/L	34205 GMS	<1.0
ACENAPHTHYLENE UG/L	34200 GMS	<1.0
ANTHRACENE UG/L	34220 GMS	<1.0
BENZIDINE UG/L	39120 GMS	<2.1
BENZO(A)ANTHRACENE UG/L	34526 GMS	<1.0
BENZO(B)FLUORANTHENE UG/L	34230 GMS	<1.5
BENZO(K)FLUORANTHENE UG/L	34242 GMS	<1.5
BENZO(A)PYRENE UG/L	34247 GMS	<1.5
BENZO(GHI)PERYLENE UG/L	34521 GMS	<2.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	3PW01 VQPR3W 1
DATE		11/18/87
TIME		11:00
BUTYLBENZYLPHTHALATE UG/L	34292 GMS	<1.0
BIS(2-CHLOROETHYL) ETHER UG/L	34273 GMS	<1.0
BIS(2-CHLOROETHOXY) METHANE UG/L	34278 GMS	<1.0
BIS(2-ETHYLHEXYL) PHTHALATE UG/L	39100 GMS	<1.0
BIS(2-CHL'ISOPROPYL) ETHER UG/L	34283 GMS	<1.0
4-BROMOPHENYLPHENYL ETHER UG/L	34636 GMS	<1.0
2-CHLORONAPHTHALENE UG/L	34581 GMS	<1.0
2-CHLOROPHENOL UG/L	34586 GMS	<1.7
4-CHLORO-3-METHYL PHENOL UG/L	34452 GMS	<1.4
4-CHLOROPHENYLPHENYL ETHER UG/L	34641 GMS	<1.0
CHRYSENE UG/L	34320 GMS	<1.0
DIBEN'(A,H)ANTH'CENE UG/L	34556 GMS	<2.0
DI-N-BUTYLPHTHALATE UG/L	39110 GMS	<1.0
1,3,DICHLOROBENZENE UG/L	34566 GMS	<1.0
1,2-DICHLOROBENZENE UG/L	34536 GMS	<1.0
1,4-DICHLOROBENZENE UG/L	34571 GMS	<1.0
3,3'-DICHL'BENZIDINE UG/L	34631 GMS	<1.5
2,4-DICHLOROPHENOL UG/L	34601 GMS	<1.4
DIETHYLPHTHALATE UG/L	34336 GMS	<1.0
2,4-DIMETHYLPHENOL UG/L	34606 GMS	<1.4

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	3PW01 VQPR3W 1
DATE		11/18/87
TIME		11:00
DIMETHYLPTHALATE UG/L	34341 GMS	<1.0
2,4-DINITROPHENOL UG/L	34616 GMS	<30
2,4-DINITROTOLUENE UG/L	34611 GMS	<1.0
2,6-DINITROTOLUENE UG/L	34626 GMS	<1.0
DI-N-OCTYLPHTHALATE UG/L	34596 GMS	<1.1
FLUORANTHENE UG/L	34376 GMS	<1.0
FLUORENE UG/L	34381 GMS	<1.0
HEXACHLOROBENZENE UG/L	39700 GMS	<1.0
HEXACHLOROBUTADIENE UG/L	34391 GMS	<1.0
HEXACHLOROCYCLOPENTA DIENE UG/L	34386 GMS	<2.0
HEXACHLOROETHANE UG/L	34396 GMS	<1.5
INDENO(1,2,3-CD) PYRENE UG/L	34403 GMS	<2.0
ISOPHORONE UG/L	34408 GMS	<1.0
2-METHYL-4,6-DINITRO PHENOL UG/L	34657 GMS	<5.0
NAPHTHALENE UG/L	34696 GMS	<1.0
NITROBENZENE UG/L	34447 GMS	<1.0
2-NITROPHENOL UG/L	34591 GMS	<1.4
4-NITROPHENOL UG/L	34646 GMS	<3.3
N-NITROSODIMET'AMINE UG/L	34438 GMS	<1.0
N-NITROSODI-N-PROPYL AMINE UG/L	34428 GMS	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	3PW01 VQPR3W 1
DATE			11/18/87
TIME			11:00
N-NITROSODIPHE'AMINE	UG/L	34433 GMS	<1.0
PENTACHLOROPHENOL	UG/L	39032 GMS	<10
PHENANTHRENE	UG/L	34461 GMS	<1.0
PHENOL	UG/L	34694 GMS	<1.3
PYRENE	UG/L	34469 GMS	<1.0
1,2,4-TRICH'BENZENE	UG/L	34551 GMS	<1.0
2,4,6-TRICHL'PHENOL	UG/L	34621 GMS	<1.8
ALDRIN	UG/L	39330 EC	<0.005
BHC,A	UG/L	39337 EC	<0.005
BHC,B	UG/L	39338 EC	<0.005
BHC,D	UG/L	34259 EC	<0.005
BHC,G(LINDANE)	UG/L	39340 EC	<0.005
CHLORDANE	UG/L	39350 EC	<0.006
DDD,PP'	UG/L	39310 EC	<0.005
DDE,PP'	UG/L	39320 EC	<0.005
DDT,PP'	UG/L	39300 EC	<0.005
DIELDRIN	UG/L	39380 EC	<0.005
ENDOSULFAN,A	UG/L	34361 EC	<0.005
ENDOSULFAN,B	UG/L	34356 EC	<0.005
ENDOSULFAN SULFATE	UG/L	34351 EC	<0.005

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # / METHOD	3PW01 VQPR3W 1
DATE			11/18/87
TIME			11:00
ENDRIN	UG/L	39390 EC	<0.005
ENDRIN ALDEHYDE	UG/L	34366 EC	<0.005
HEPTACHLOR	UG/L	39410 EC	<0.047
HEPTACHLOR EPOXIDE	UG/L	39420 EC	<0.005
TOXAPHENE	UG/L	39400 EC	<0.600
PCB-1016	UG/L	34671 EC	<0.121
PCB-1221	UG/L	39488 EC	<0.121
PCB-1232	UG/L	39492 EC	<0.121
PCB-1242	UG/L	39496 EC	<0.121
PCB 1248	UG/L	39500 EC	<0.121
PCB-1254	UG/L	39504 EC	<0.121
PCB-1260	UG/L	39508 EC	<0.121
ANTIMONY, TOTAL	UG/L	1097 ICAP	<39.0
ARSENIC, TOTAL	UG/L	1002 GFAA	<1.6
BERYLLIUM, TOTAL	UG/L	1012 ICAP	<2.9
CADMIUM, TOTAL	UG/L	1027 ICAP	<2.3
CHROMIUM, TOTAL	UG/L	1034 ICAP	<7.6
COPPER, TOTAL	UG/L	1042 ICAP	<10.0
LEAD, TOTAL	UG/L	1051 ICAP	<34.0
MERCURY, TOTAL	UG/L	71900 CVAA	<0.2

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAF VIEQUES
FIELD GROUP VQPR3W PROJECT MANAGER RUSS BOWEN
VIEQUES SITE 3 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	3PW01 VQPR3W
UNITS	METHOD	1
DATE		11/18/87
TIME		11:00
NICKEL,TOTAL	1067	<33.0
UG/L	ICAP	
SELENIUM,TOTAL	1147	<2.5
UG/L	GFAA	
SILVER,TOTAL	1077	<2.7
UG/L	ICAP	
THALLIUM,TOTAL	1059	<2.8
UG/L	GFAA	
ZINC,TOTAL	1092	469
UG/L	ICAP	
PHENOLS	32730	<2
UG/L	1	

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5GW01	5GW02	5GW03	5GW04	5GW05	5SW01	5SW02	5SW03	5SW04	5SW05
		SAMPLE ID/#									
UNITS	METHOD	RRPR5W 1	RRPR5W 2	RRPR5W 3	RRPR5W 4	RRPR5W 5	RRPR5W 6	RRPR5W 7	RRPR5W 8	RRPR5W 9	RRPR5W 10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
WATER TEMP	10	28.8	28.4	27.4	27.8	29.1	44.4	NA	NA	NA	NA
C	0										
PH,FIELD	400	7.80	7.40	6.40	6.40	7.10	7.80	8.80	8.40	8.60	8.20
STD UNITS	0										
SP.COND.,FIELD@25C	94	3960	4070	49200	49500	45100	44000	2850	3200	3630	42100
UMHOS/CM	0										
BENZENE	34030	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
BROMODICHLOROMETHANE	32101	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2
UG/L	GMS										
BROMOFORM	32104	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS										
BROMOMETHANE	34413	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8
UG/L	GMS										
CARBON TETRACHLORIDE	32102	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS										
CHLOROBENZENE	34301	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS										
CHLOROETHANE	34311	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2
UG/L	GMS										
2-CHLOROETHYLVINYL	34576	<15	<15	<15	<15	<15	<15	<15	<15	<15	<15
ETHER UG/L	GMS										
CHLOROFORM	32106	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6
UG/L	GMS										
CHLOROMETHANE	34418	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3
UG/L	GMS										
DIBROMOCHLOROMETHANE	32105	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1
UG/L	GMS										
1,1-DICHLOROETHANE	34496	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS										
1,2-DICHLOROETHANE	34531	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS										
1,1-DICHLOROETHYLENE	34501	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS										
TRANS-1,2-DICHLORO	34546	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6
ETHENE UG/L	GMS										
1,2-DICHLOROPROPANE	34541	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS										
CIS-1,3-DICHLORO	34704	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
PROPENE UG/L	GMS										

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 5GW01 RRPR5W 1	5GW02 RRPR5W 2	5GW03 RRPR5W 3	5GW04 RRPR5W 4	5GW05 RRPR5W 5	5SW01 RRPR5W 6	5SW02 RRPR5W 7	5SW03 RRPR5W 8	5SW04 RRPR5W 9	5SW05 RRPR5W 10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50	<50	<50	<50	<50	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48	<48	<48	<48	<48	<48	<48	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12
M-XYLENE UG/L	98553 GMS	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.013	<0.010	<0.010	<0.010	<0.010	<0.013	<0.013	<0.013	<0.013	<0.013
ACENAPHTHENE UG/L	34205 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
ACENAPHTHYLENE UG/L	34200 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
ANTHRACENE UG/L	34220 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BENZIDINE UG/L	39120 GMS	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 5GW01 RRPR5W 1	5GW02 RRPR5W 2	5GW03 RRPR5W 3	5GW04 RRPR5W 4	5GW05 RRPR5W 5	5SW01 RRPR5W 6	5SW02 RRPR5W 7	5SW03 RRPR5W 8	5SW04 RRPR5W 9	5SW05 RRPR5W 10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
BENZO(A)ANTHRACENE UG/L	34526 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BENZO(B)FLUORANTHENE UG/L	34230 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
BENZO(K)FLUORANTHENE UG/L	34242 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
BENZO(A)PYRENE UG/L	34247 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
BENZO(GHI)PERYLENE UG/L	34521 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
BUTYLBENZYLPHTHALATE UG/L	34292 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BIS(2-CHLOROETHYL) ETHER UG/L	34273 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BIS(2-CHLOROETHOXY) METHANE UG/L	34278 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BIS(2-ETHYLHEXYL) PHTHALATE UG/L	39100 GMS	<1.0	<1.0	1.5	1.0	22	1.7	<1.0	1.6	2.4	10
BIS(2-CHL'ISOPROPYL) ETHER UG/L	34283 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
4-BROMOPHENYLPHENYL ETHER UG/L	34636 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-CHLORONAPHTHALENE UG/L	34581 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-CHLOROPHENOL UG/L	34586 GMS	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7
4-CHLORO-3-METHYL PHENOL UG/L	34452 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
4-CHLOROPHENYLPHENYL ETHER UG/L	34641 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
CHRYSENE UG/L	34320 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
DIBEN'(A,H)ANTH'CENE UG/L	34556 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
DI-N-BUTYLPHTHALATE UG/L	39110 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,3,DICHLOROBENZENE UG/L	34566 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-DICHLOROBENZENE UG/L	34536 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 5GW01 RRPR5W 1	5GW02 RRPR5W 2	5GW03 RRPR5W 3	5GW04 RRPR5W 4	5GW05 RRPR5W 5	5SW01 RRPR5W 6	5SW02 RRPR5W 7	5SW03 RRPR5W 8	5SW04 RRPR5W 9	5SW05 RRPR5W 10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
1,4-DICHLOROBENZENE UG/L	34571 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
3,3'-DICHL'BENZIDINE UG/L	34631 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
2,4-DICHLOROPHENOL UG/L	34601 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
DIETHYLPHTHALATE UG/L	34336 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2,4-DIMETHYLPHENOL UG/L	34606 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
DIMETHYLPTHALATE UG/L	34341 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2,4-DINITROPHENOL UG/L	34616 GMS	<30	<30	<30	<30	<30	<30	<30	<30	<30	<30
2,4-DINITROTOLUENE UG/L	34611 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2,6-DINITROTOLUENE UG/L	34626 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
DI-N-OCTYLPHTHALATE UG/L	34596 GMS	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1
FLUORANTHENE UG/L	34376 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
FLUORENE UG/L	34381 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
HEXACHLOROBENZENE UG/L	39700 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
HEXACHLOROBUTADIENE UG/L	34391 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
HEXACHLOROCYCLOPENTA DIENE UG/L	34386 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
HEXACHLOROETHANE UG/L	34396 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
INDENO(1,2,3-CD) PYRENE UG/L	34403 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
ISOPHORONE UG/L	34408 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-METHYL-4,6-DINITRO PHENOL UG/L	34657 GMS	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
NAPHTHALENE UG/L	34696 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	SAMPLE ID/# 5GW01	5GW02	5GW03	5GW04	5GW05	5SW01	5SW02	5SW03	5SW04	5SW05
		RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W
UNITS	METHOD	1	2	3	4	5	6	7	8	9	10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
NITROBENZENE	34447	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
2-NITROPHENOL	34591	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
UG/L	GMS										
4-NITROPHENOL	34646	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3
UG/L	GMS										
N-NITROSODIMET'AMINE	34438	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
N-NITROSODI-N-PROPYL	34428	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
AMINE UG/L	GMS										
N-NITROSODIPHE'AMINE	34433	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
PENTACHLOROPHENOL	39032	<10	<10	<10	<10	<10	<10	<10	<10	<10	<10
UG/L	GMS										
PHENANTHRENE	34461	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
PHENOL	34694	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3
UG/L	GMS										
PYRENE	34469	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
1,2,4-TRICH'BENZENE	34551	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS										
2,4,6-TRICHL'PHENOL	34621	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8
UG/L	GMS										
ALDRIN	39330	<0.008	<0.008	<0.008	<0.008	<0.824	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
BHC,A	39337	<0.012	<0.012	<0.012	<0.012	<1.18	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
BHC,B	39338	<0.005	<0.005	<0.005	<0.005	<0.471	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
BHC,D	34259	<0.008	<0.008	<0.008	<0.008	<0.824	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
BHC,G(LINDANE)	39340	<0.012	<0.012	<0.012	<0.012	<1.18	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
CHLORDANE	39350	<0.006	<0.006	<0.006	<0.006	<0.006	<0.012	<0.012	<0.012	<0.012	<0.012
UG/L	EC										
DDD,PP'	39310	<0.008	<0.008	<0.008	<0.008	<0.008	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
DDE,PP'	39320	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5GW01	5GW02	5GW03	5GW04	5GW05	5SW01	5SW02	5SW03	5SW04	5SW05
		SAMPLE ID/#									
		RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W	RRPR5W
UNITS	METHOD	1	2	3	4	5	6	7	8	9	10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
DDT,PP'	39300	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
DIELDRIN	39380	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
ENDOSULFAN,A	34361	<0.005	<0.005	<0.005	<0.005	<0.471	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
ENDOSULFAN,B	34356	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
ENDOSULFAN SULFATE	34351	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
ENDRIN	39390	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
ENDRIN ALDEHYDE	34366	<0.005	<0.005	<0.005	<0.005	<0.005	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
HEPTACHLOR	39410	<0.005	<0.005	<0.005	<0.005	<0.471	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
HEPTACHLOR EPOXIDE	39420	<0.005	<0.005	<0.005	<0.005	<0.471	<0.009	<0.009	<0.009	<0.009	<0.009
UG/L	EC										
TOXAPHENE	39400	<0.600	<0.600	<0.600	<0.600	<0.600	<1.20	<1.20	<1.20	<1.20	<1.20
UG/L	EC										
PCB-1016	34671	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
PCB-1221	39488	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
PCB-1232	39492	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
PCB-1242	39496	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
PCB 1248	39500	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
PCB-1254	39504	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
PCB-1260	39508	<0.121	<0.121	<0.121	<0.121	<0.121	<0.247	<0.247	<0.247	<0.247	<0.247
UG/L	EC										
ANTIMONY,TOTAL	1097	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0
UG/L	ICAP										
ARSENIC,TOTAL	1002	2.5	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2
UG/L	GFAA										
BERYLLIUM, TOTAL	1012	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	ICAP										

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	5GW01	5GW02	5GW03	5GW04	5GW05	5SW01	5SW02	5SW03	5SW04	5SW05
		SAMPLE ID/#									
UNITS	METHOD	RRPR5W 1	RRPR5W 2	RRPR5W 3	RRPR5W 4	RRPR5W 5	RRPR5W 6	RRPR5W 7	RRPR5W 8	RRPR5W 9	RRPR5W 10
DATE		10/12/87	10/12/87	10/13/87	10/13/87	10/12/87	10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		11:25	13:40	10:45	09:10	13:10	09:00	13:00	12:00	11:15	09:30
CADMIUM,TOTAL	1027	<2.4	<2.4	<2.4	<2.4	<2.4	<2.4	<2.4	<2.4	<2.4	<2.4
UG/L	ICAP										
CHROMIUM,TOTAL	1034	16.0	9.7	205	178	163	108	3.7	12.4	7.7	105
UG/L	ICAP										
COPPER,TOTAL	1042	<2.8	9.2	1780	<2.8	154	<2.8	<2.8	24.8	<2.8	<2.8
UG/L	ICAP										
LEAD,TOTAL	1051	<20.0	<20.0	<4000	<2000	<2000	<200	<400	<20.0	<20.0	<400
UG/L	ICAP										
MERCURY,TOTAL	71900	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
UG/L	CVAA										
NICKEL,TOTAL	1067	<8.6	<8.6	34.1	17.8	20.5	<8.6	<8.6	<8.6	<8.6	<8.6
UG/L	ICAP										
SELENIUM,TOTAL	1147	10.5	9.5	359	310	122	181	11.0	14.9	8.0	221
UG/L	GFAA										
SILVER,TOTAL	1077	<3.6	3.7	37.7	24.7	37.6	28.8	<3.6	3.8	<3.6	28.9
UG/L	ICAP										
THALLIUM,TOTAL	1059	<5.0	<5.0	<10.0	<10.0	69.4	<10.0	<5.0	<5.0	<5.0	<10.0
UG/L	GFAA										
ZINC,TOTAL	1092	35.0	<1.8	222	2.0	192	<1.8	<1.8	20.8	<1.8	<1.8
UG/L	ICAP										
PHENOLS	32730	76	30	350	800	220	540	29	57	33	130
UG/L	I										
CHROMIUM,(+6)	1032	<10.0	<10.0	<10.0	<10.0	110	<10.0	<10.0	<10.0	<10.0	<10.0
UG/L	I										

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE# 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
DATE			10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME			09:10	13:20	12:15	11:40	09:45
MOISTURE		70320	54.2	75.5	75.4	63.1	77.7
	%WET WT	1					
PH,SOIL		99218	7.0	6.9	7.1	7.3	7.0
	STD UNITS	1					
BENZENE		34237	<480	<900	<890	<600	<990
	UG/KG-DRY	GMS					
BROMODICHLOROMETHANE		34330	<240	<450	<450	<300	<490
	UG/KG-DRY	GMS					
BROMOFORM		34290	<510	<960	<960	<640	<1100
	UG/KG-DRY	GMS					
BROMOMETHANE		34416	<610	<1100	<1100	<760	<1300
	UG/KG-DRY	GMS					
CARBON TETRACHLORIDE		34299	<310	<570	<570	<380	<630
	UG/KG-DRY	GMS					
CHLOROBENZENE		34304	<660	<1200	<1200	<810	<1300
	UG/KG-DRY	GMS					
CHLOROETHANE		34314	<900	<1700	<1700	<1100	<1800
	UG/KG-DRY	GMS					
2-CHLOROETHYLVINYL		34579	<1100	<2000	<2000	<1400	<2200
ETHER	UG/KG-DRY	GMS					
CHLOROFORM		34318	<170	<330	<330	<220	<360
	UG/KG-DRY	GMS					
CHLOROMETHANE		34421	<470	<880	<870	<580	<960
	UG/KG-DRY	GMS					
DIBROMOCHLOROMETHANE		34309	<340	<630	<630	<420	<700
	UG/KG-DRY	GMS					
1,1-DICHLOROETHANE		34499	<510	<960	<960	<640	<1100
	UG/KG-DRY	GMS					
1,2-DICHLOROETHANE		34534	<310	<570	<570	<380	<630
	UG/KG-DRY	GMS					
1,1-DICHLOROETHYLENE		34504	<310	<570	<570	<380	<630
	UG/KG-DRY	GMS					
TRANS-1,2-DICHLORO		34549	<170	<330	<330	<220	<360
ETHENE	UG/KG-DRY	GMS					
1,2-DICHLOROPROPANE		34544	<660	<1200	<1200	<810	<1300
	UG/KG-DRY	GMS					
CIS-1,3-DICHLORO		34702	<550	<1000	<1000	<680	<1100
PROPENE	UG/KG-DRY	GMS					
TRANS-1,3-DICHLORO		34697	<700	<1300	<1300	<870	<1400
PROPENE	UG/KG-DRY	GMS					

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
DATE		10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		09:10	13:20	12:15	11:40	09:45
ETHYLBENZENE UG/KG-DRY	34374 GMS	<790	<1500	<1500	<980	<1600
METHYLENE CHLORIDE UG/KG-DRY	34426 GMS	3600	<4100	<4100	<2700	<4500
1,1,2,2-TETRACHLORO ETHANE UG/KG-DRY	34519 GMS	<450	<840	<830	<560	<920
TETRACHLOROETHENE UG/KG-DRY	34478 GMS	<450	<840	<830	<560	<920
TOLUENE UG/KG-DRY	34483 GMS	<660	<1200	<1200	<810	<1300
1,1,1-TRICHL'ETHANE UG/KG-DRY	34509 GMS	<410	<780	<770	<510	<850
1,1,2-TRICHL'ETHANE UG/KG-DRY	34514 GMS	<550	<1000	<1000	<680	<1100
TRICHLOROETHENE UG/KG-DRY	34487 GMS	<210	<390	<390	<260	<430
TRICHLOROFLUOROMETHA NE UG/KG-DRY	34491 GMS	<350	<650	<650	<430	<720
VINYL CHLORIDE UG/KG-DRY	34495 GMS	<530	<1000	<1000	<660	<1100
M-XYLENE UG/KG-DRY	97016 GMS	<660	<1200	<1200	<810	<1300
O,P-XYLENE UG/KG-DRY	97017 GMS	<660	<1200	<1200	<810	<1300
METHYL ETHYL KETONE UG/KG-DRY	75078 GMS	<5200	<9800	<9800	<6500	<11000
METHYL ISOBUT'KETONE UG/KG-DRY	75169 GMS	<1300	<2400	<2400	<1600	<2700
1,2-DIBROMOETHANE (EDB) UG/KG-DRY	78756 EC	<0.643	<1.17	<1.17	<0.778	<1.29
ACENAPHTHENE UG/KG-DRY	34208 GMS	<130	<240	<240	<160	<270
ACENAPHTHYLENE UG/KG-DRY	34203 GMS	<130	<240	<240	<160	<270
ANTHRACENE UG/KG-DRY	34223 GMS	<130	<240	<240	<160	<270
BENZIDINE UG/KG-DRY	39121 GMS	<1100	<2000	<2000	<1400	<2200
BENZO(A)ANTHRACENE UG/KG-DRY	34529 GMS	<130	<240	<240	<160	<270

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
DATE		10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		09:10	13:20	12:15	11:40	09:45
BENZO(B)FLUORANTHENE UG/KG-DRY	34233 GMS	<200	<370	<370	<240	<400
BENZO(K)FLUORANTHENE UG/KG-DRY	34245 GMS	<200	<370	<370	<240	<400
BENZO(A)PYRENE UG/KG-DRY	34250 GMS	<200	<370	<370	<240	<400
BENZO(GHI)PERYLENE UG/KG-DRY	34524 GMS	<260	<490	<490	<330	<540
BUTYLBENZYLPHTHALATE UG/KG-DRY	34295 GMS	<130	<240	<240	<160	<270
BIS(2-CHLOROETHYL) ETHER UG/KG-DRY	34276 GMS	<130	<240	<240	<160	<270
BIS(2-CHLOROETHOXY) METHANE UG/KG-DRY	34281 GMS	<130	<240	<240	<160	<270
BIS(2-ETHYLHEXYL) PHTHALATE UG/KG-DRY	39102 GMS	<170	<330	<330	<220	<360
BIS(2-CHL'ISOPROPYL) ETHER UG/KG-DRY	34286 GMS	<130	<240	<240	<160	<270
4-BROMOPHENYL PHENYL ETHER UG/KG-DRY	34639 GMS	<130	<240	<240	<160	<270
2-CHLORONAPHTHALENE UG/KG-DRY	34584 GMS	<130	<240	<240	<160	<270
2-CHLOROPHENOL UG/KG-DRY	34589 GMS	<220	<410	<410	<270	<450
4-CHLORO-3-METHYL PHENOL UG/KG-DRY	34455 GMS	<260	<490	<490	<330	<540
4-CHLOROPHENYLPHENYL ETHER UG/KG-DRY	34644 GMS	<130	<240	<240	<160	<270
CHRYSENE UG/KG- DRY	34323 GMS	<130	<240	<240	<160	<270
DIBEN(A,H)ANTHRACENE UG/KG-DRY	34559 GMS	<260	<490	<490	<330	<540
DI-N-BUTYL PHTHALATE UG/KG-DRY	39112 GMS	<130	<240	<240	<160	<270
1,3-DICHLOROBENZENE UG/KG-DRY	34569 GMS	<130	<240	<240	<160	<270
1,2-DICHLOROBENZENE UG/KG-DRY	34539 GMS	<130	<240	<240	<160	<270
1,4-DICHLOROBENZENE UG/KG-DRY	34574 GMS	<130	<240	<240	<160	<270

RR-00039-03.13-04/01/88

PROJECT NUMBER 87466 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
DATE		10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		09:10	13:20	12:15	11:40	09:45
3,3-DICHL'BENZIDINE UG/KG-DRY	34634 GMS	<220	<410	<410	<270	<450
2,4-DICHLOROPHENOL UG/KG-DRY	34604 GMS	<260	<490	<490	<330	<540
DIETHYL PHTHALATE UG/KG-DRY	34339 GMS	<130	<240	<240	<160	<270
2,4-DIMETHYLPHENOL UG/KG-DRY	34609 GMS	<1300	<2400	<2400	<1600	<2700
DIMETHYL PHTHALATE UG/KG-DRY	34344 GMS	<130	<240	<240	<160	<270
2,4-DINITROPHENOL UG/KG-DRY	34619 GMS	<2800	<5300	<5300	<3500	<5800
2,4-DINITROTOLUENE UG/KG-DRY	34614 GMS	<130	<240	<240	<160	<270
2,6-DINITROTOLUENE UG/KG-DRY	34629 GMS	<130	<240	<240	<160	<270
DI-N-OCTYL PHTHALATE UG/KG-DRY	34599 GMS	<190	<350	<350	<230	<380
FLUORANTHENE UG/KG-DRY	34379 GMS	<130	<240	<240	<160	<270
FLUORENE UG/KG- DRY	34384 GMS	<130	<240	<240	<160	<270
HEXACHLOROBENZENE UG/KG-DRY	39701 GMS	<130	<240	<240	<160	<270
HEXACHLOROBUTADIENE UG/KG-DRY	39705 GMS	<130	<240	<240	<160	<270
HEXACHLOROCYCLOPENTA DIENE UG/KG-DRY	34389 GMS	<2200	<4100	<4100	<2700	<4500
HEXACHLOROETHANE UG/KG-DRY	34399 GMS	<160	<310	<300	<200	<340
INDENO(1,2,3-CD) PYRENE UG/KG-DRY	34406 GMS	<260	<490	<490	<330	<540
ISOPHORONE UG/KG-DRY	34411 GMS	<130	<240	<240	<160	<270
2-METHYL-4,6-DINITRO PHENOL UG/KG-DRY	34660 GMS	<2200	<4100	<4100	<2700	<4500
NAPHTHALENE UG/KG-DRY	34445 GMS	<130	<240	<240	<160	<270
NITROBENZENE UG/KG-DRY	34450 GMS	<150	<290	<280	<190	<310

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
DATE			10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME			09:10	13:20	12:15	11:40	09:45
2-NITROPHENOL	UG/KG-DRY	34594 GMS	<220	<410	<410	<270	<450
4-NITROPHENOL	UG/KG-DRY	34649 GMS	<1300	<2400	<2400	<1600	<2700
N-NITROSODIMET'AMINE	UG/KG-DRY	34441 GMS	<220	<410	<410	<270	<450
N-NITROSODI-N-PROPYL AMINE	UG/KG-DRY	34431 GMS	<130	<240	<240	<160	<270
N-NITROSODIPHE'AMINE	UG/KG-DRY	34436 GMS	<130	<240	<240	<160	<270
PENTACHLPHENOL	UG/KG-DRY	39061 GMS	<660	<1200	<1200	<810	<1300
PHENANTHRENE	UG/KG-DRY	34464 GMS	<130	<240	<240	<160	<270
PHENOL	UG/KG-DRY	34695 GMS	<240	<450	<450	<300	<490
PYRENE	UG/KG-DRY	34472 GMS	<130	<240	<240	<160	<270
1,2,4-TRICH'BENZENE	UG/KG-DRY	34554 GMS	<130	<240	<240	<160	<270
2,4,6-TRICH'PHENOL	UG/KG-DRY	34624 GMS	<260	<490	<490	<330	<540
ALDRIN	UG/KG-DRY	39333 EC	<30.5	<57.1	<56.9	<37.8	<62.6
BHC,A	UG/KG-DRY	39076 EC	<30.5	<57.1	<56.9	<37.8	<62.6
BHC,B	UG/KG-DRY	34257 EC	<30.5	<57.1	<56.9	<37.8	<62.6
BHC,D	UG/KG-DRY	34262 EC	<30.5	<57.1	<56.9	<37.8	<62.6
BHC,G(LINDANE) -	UG/KG-DRY	39783 EC	<30.5	<57.1	<56.9	<37.8	<62.6
CHLORDANE	UG/KG-DRY	39351 EC	<30.5	<57.1	<56.9	<37.8	<62.6
DDD,PP'	UG/KG-DRY	39311 EC	<30.5	<57.1	<56.9	<37.8	<62.6
DDE,PP'	UG/KG-DRY	39321 EC	32.4	<57.1	<56.9	272	<62.6
DDT,PP'	UG/KG-DRY	39301 EC	<43.5	<81.6	138	<54.0	<89.4

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
UNITS	METHOD					
DATE		10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		09:10	13:20	12:15	11:40	09:45
DIELDRIN	39383	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
ENDOSULFAN,A	34364	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
ENDOSULFAN,B	34359	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
ENDOSULFAN SULFATE	34354	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
ENDRIN	39393	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
ENDRIN ALDEHYDE	34369	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
HEPTACHLOR	39413	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
HEPTACHLOR EPOXIDE	39423	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
TOXAPHENE	39403	<30.5	<57.1	<56.9	<37.8	<62.6
UG/KG-DRY	EC					
PCB 1016	39514	<448	<840	<837	<557	<921
UG/KG-DRY	EC					
PCB-1221	39491	<450	<840	<840	<560	<920
UG/KG-DRY	EC					
PCB-1232	39495	<450	<840	<840	<560	<920
UG/KG-DRY	EC					
PCB-1242	39499	<450	<840	<840	<560	<920
UG/KG-DRY	EC					
PCB-1248	39503	<450	<840	<840	<560	<920
UG/KG-DRY	EC					
PCB-1254	39507	<450	<840	<840	<560	<920
UG/KG-DRY	EC					
PCB-1260	39511	<450	<840	<840	<560	<920
UG/KG-DRY	EC					
ANTIMONY,SED	1098	<7.9	<15	<16	<10.0	<16
MG/KG-DRY	ICAP					
ARSENIC,SED	1003	4.47	6.05	5.58	3.78	3.45
UG/G- DRY	GFAA					
BERYLLIUM,SED	1013	<0.587	<1.13	<1.16	<0.743	<1.18
MG/KG-DRY	ICAP					
CADMIUM,SED	1028	3.04	3.13	2.40	1.28	1.63
UG/G- DRY	ICAP					

RR-00039-03.13-04/01/88

PROJECT NUMBER E7488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR5S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 5 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	5SE01 RRPR5S 1	5SE02 RRPR5S 2	5SE03 RRPR5S 3	5SE04 RRPR5S 4	5SE05 RRPR5S 5
UNITS	METHOD					
DATE		10/07/87	10/06/87	10/06/87	10/06/87	10/06/87
TIME		09:10	13:20	12:15	11:40	09:45
CHROMIUM,SED	1029	51.4	23.8	19.6	10.2	34.7
UG/G- DRY	ICAP					
COPPER,SED	1043	72.1	97.3	73.5	36.1	54.7
UG/G- DRY	ICAP					
LEAD,SED	1052	10.1	19.2	21.6	11.0	<13.9
UG/G-DRY	ICAP					
MERCURY	71921	<0.095	<0.173	<0.186	<0.129	<0.198
UG/G-DRY	CVAA					
NICKEL,SED	1068	14.4	<12.9	<13.2	8.45	<13.5
UG/G- DRY	ICAP					
SELENIUM,SED	1148	3.47	6.50	<1.12	1.09	5.51
MG/KG-DRY	GFAA					
SILVER,SED	1078	<0.547	<1.06	1.20	<0.691	<1.10
MG/KG- DRY	ICAP					
THALLIUM,SED	34480	<0.486	<1.01	<0.900	<0.590	<0.957
MG/KG- DRY	GFAA					
ZINC,SED	1093	75.7	98.1	89.5	51.5	50.2
UG/G-DRY	ICAP					
PHENOLS,SED	32731	<73	29800	5980	2500	5710
UG/KG- DRY	1					
CHROMIUM(+6),SED	29405	<2.18	<10.2	13.8	<2.71	<11.2
MG/KG-DRY	1					

RR-00039-03.13-04/01/88

PROJECT NUMBER 67468 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6GW01 RRPR6W 1	R6SW01 RRPR6W 2	R6SW02 RRPR6W 3	R6SW03 RRPR6W 4
DATE			11/02/87	10/07/87	10/07/87	10/07/87
TIME			13:15	10:40	11:30	12:00
WATER TEMP	C	10 0	28.4	38.3	33.9	40.2
PH,FIELD	STD UNITS	400 0	7.40	7.60	7.70	7.80
SP.COND.,FIELD@25C	UMHOS/CM	94 0	4010	41200	40500	39400
BENZENE	UG/L	34030 GMS	<1.0	<1.0	<1.0	<1.0
BROMODICHLOROMETHANE	UG/L	32101 GMS	<2.2	<2.2	<2.2	<2.2
BROMOFORM	UG/L	32104 GMS	<4.7	<4.7	<4.7	<4.7
BROMOMETHANE	UG/L	34413 GMS	<5.8	<5.8	<5.8	<5.8
CARBON TETRACHLORIDE	UG/L	32102 GMS	<2.8	<2.8	<2.8	<2.8
CHLOROBENZENE	UG/L	34301 GMS	<6.0	<6.0	<6.0	<6.0
CHLOROETHANE	UG/L	34311 GMS	<8.2	<8.2	<8.2	<8.2
2-CHLOROETHYLVINYL ETHER	UG/L	34576 GMS	<15	<15	<15	<15
CHLOROFORM	UG/L	32106 GMS	1.7	<1.6	<1.6	<1.6
CHLOROMETHANE	UG/L	34418 GMS	<4.3	<4.3	<4.3	<4.3
DIBROMOCHLOROMETHANE	UG/L	32105 GMS	<3.1	<3.1	<3.1	<3.1
1,1-DICHLOROETHANE	UG/L	34496 GMS	<4.7	<4.7	<4.7	<4.7
1,2-DICHLOROETHANE	UG/L	34531 GMS	<2.8	<2.8	<2.8	<2.8
1,1-DICHLOROETHYLENE	UG/L	34501 GMS	<2.8	<2.8	<2.8	<2.8
TRANS-1,2-DICHLORO ETHENE	UG/L	34546 GMS	<1.6	<1.6	<1.6	<1.6
1,2-DICHLOROPROPANE	UG/L	34541 GMS	<6.0	<6.0	<6.0	<6.0
CIS-1,3-DICHLORO PROPENE	UG/L	34704 GMS	<5.0	<5.0	<5.0	<5.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6GW01 RRPR6W 1	R6SW01 RRPR6W 2	R6SW02 RRPR6W 3	R6SW03 RRPR6W 4
DATE		11/02/87	10/07/87	10/07/87	10/07/87
TIME		13:15	10:40	11:30	12:00
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0	<1.0
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12	<12	<12
M-XYLENE UG/L	98553 GMS	<12	<12	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<12	<12
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.010	<0.013	<0.013	<0.013
ACENAPHTHENE UG/L	34205 GMS	<1.0	<1.0	<1.0	<1.0
ACENAPHTHYLENE UG/L	34200 GMS	<1.0	<1.0	<1.0	<1.0
ANTHRACENE UG/L	34220 GMS	<1.0	<1.0	<1.0	<1.0
BENZIDINE UG/L	39120 GMS	<2.1	<2.1	<2.1	<2.1

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6GW01 RRPR6W 1	R6SW01 RRPR6W 2	R6SW02 RRPR6W 3	R6SW03 RRPR6W 4
DATE		11/02/87	10/07/87	10/07/87	10/07/87
TIME		13:15	10:40	11:30	12:00
BENZO(A)ANTHRACENE UG/L	34526 GMS	<1.0	<1.0	<1.0	<1.0
BENZO(B)FLUORANTHENE UG/L	34230 GMS	<1.5	<1.5	<1.5	<1.5
BENZO(K)FLUORANTHENE UG/L	34242 GMS	<1.5	<1.5	<1.5	<1.5
BENZO(A)PYRENE UG/L	34247 GMS	<1.5	<1.5	<1.5	<1.5
BENZO(GHI)PERYLENE UG/L	34521 GMS	<2.0	<2.0	<2.0	<2.0
BUTYLBENZYLPHTHALATE UG/L	34292 GMS	<1.0	<1.0	<1.0	<1.0
BIS(2-CHLOROETHYL) ETHER UG/L	34273 GMS	<1.0	<1.0	<1.0	<1.0
BIS(2-CHLOROETHOXY) METHANE UG/L	34278 GMS	<1.0	<1.0	<1.0	<1.0
BIS(2-ETHYLHEXYL) PHTHALATE UG/L	39100 GMS	1.9	1.0	2.4	1.3
BIS(2-CHL'ISOPROPYL) ETHER UG/L	34283 GMS	<1.0	<1.0	<1.0	<1.0
4-BROMOPHENYLPHENYL ETHER UG/L	34636 GMS	<1.0	<1.0	<1.0	<1.0
2-CHLORONAPHTHALENE UG/L	34581 GMS	<1.0	<1.0	<1.0	<1.0
2-CHLOROPHENOL UG/L	34586 GMS	<1.7	<1.7	<1.7	<1.7
4-CHLORO-3-METHYL PHENOL UG/L	34452 GMS	<1.4	<1.4	<1.4	<1.4
4-CHLOROPHENYLPHENYL ETHER UG/L	34641 GMS	<1.0	<1.0	<1.0	<1.0
CHRYSENE UG/L	34320 GMS	<1.0	<1.0	<1.0	<1.0
DIBEN'(A,H)ANTH'CENE UG/L	34556 GMS	<2.0	<2.0	<2.0	<2.0
DI-N-BUTYLPHTHALATE UG/L	39110 GMS	<1.0	<1.0	<1.0	<1.0
1,3,DICHLOROBENZENE UG/L	34566 GMS	<1.0	<1.0	<1.0	<1.0
1,2-DICHLOROBENZENE UG/L	34536 GMS	<1.0	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6GW01 RRPR6W 1	R6SW01 RRPR6W 2	R6SW02 RRPR6W 3	R6SW03 RRPR6W 4
DATE		11/02/87	10/07/87	10/07/87	10/07/87
TIME		13:15	10:40	11:30	12:00
1,4-DICHLOROBENZENE UG/L	34571 GMS	<1.0	<1.0	<1.0	<1.0
3,3'-DICHL'BENZIDINE UG/L	34631 GMS	<1.5	<1.5	<1.5	<1.5
2,4-DICHLOROPHENOL UG/L	34601 GMS	<1.4	<1.4	<1.4	<1.4
DIETHYLPHTHALATE UG/L	34336 GMS	<1.0	<1.0	<1.0	<1.0
2,4-DIMETHYLPHENOL UG/L	34606 GMS	<1.4	<1.4	<1.4	<1.4
DIMETHYLPTHALATE UG/L	34341 GMS	<1.0	<1.0	<1.0	<1.0
2,4-DINITROPHENOL UG/L	34616 GMS	<30	<30	<30	<30
2,4-DINITROTOLUENE UG/L	34611 GMS	<1.0	<1.0	<1.0	<1.0
2,6-DINITROTOLUENE UG/L	34626 GMS	<1.0	<1.0	<1.0	<1.0
DI-N-OCTYLPHTHALATE UG/L	34596 GMS	<1.1	<1.1	<1.1	<1.1
FLUORANTHENE UG/L	34376 GMS	<1.0	<1.0	<1.0	<1.0
FLUORENE UG/L	34381 GMS	<1.0	<1.0	<1.0	<1.0
HEXACHLOROBENZENE UG/L	39700 GMS	<1.0	<1.0	<1.0	<1.0
HEXACHLOROBUTADIENE UG/L	34391 GMS	<1.0	<1.0	<1.0	<1.0
HEXACHLOROCYCLOPENTA DIENE UG/L	34386 GMS	<2.0	<2.0	<2.0	<2.0
HEXACHLOROETHANE UG/L	34396 GMS	<1.5	<1.5	<1.5	<1.5
INDENO(1,2,3-CD) PYRENE UG/L	34403 GMS	<2.0	<2.0	<2.0	<2.0
ISOPHORONE UG/L	34408 GMS	<1.0	<1.0	<1.0	<1.0
2-METHYL-4,6-DINITRO PHENOL UG/L	34657 GMS	<5.0	<5.0	<5.0	<5.0
NAPHTHALENE UG/L	34696 GMS	<1.0	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6GW01 RRPR6W 1	R6SW01 RRPR6W 2	R6SW02 RRPR6W 3	R6SW03 RRPR6W 4
DATE			11/02/87	10/07/87	10/07/87	10/07/87
TIME			13:15	10:40	11:30	12:00
NITROBENZENE	UG/L	34447 GMS	<1.0	<1.0	<1.0	<1.0
2-NITROPHENOL	UG/L	34591 GMS	<1.4	<1.4	<1.4	<1.4
4-NITROPHENOL	UG/L	34646 GMS	<3.3	<3.3	<3.3	<3.3
N-NITROSODIMET'AMINE	UG/L	34438 GMS	<1.0	<1.0	<1.0	<1.0
N-NITROSODI-N-PROPYL AMINE	UG/L	34428 GMS	<1.0	<1.0	<1.0	<1.0
N-NITROSODIPHE'AMINE	UG/L	34433 GMS	<1.0	<1.0	<1.0	<1.0
PENTACHLOROPHENOL	UG/L	39032 GMS	11	<10	<10	<10
PHENANTHRENE	UG/L	34461 GMS	<1.0	<1.0	<1.0	<1.0
PHENOL	UG/L	34694 GMS	<1.3	<1.3	<1.3	<1.3
PYRENE	UG/L	34469 GMS	<1.0	<1.0	<1.0	<1.0
1,2,4-TRICH'BENZENE	UG/L	34551 GMS	<1.0	<1.0	<1.0	<1.0
2,4,6-TRICHL'PHENOL	UG/L	34621 GMS	<1.8	<1.8	<1.8	<1.8
ALDRIN	UG/L	39330 EC	0.006	<0.009	<0.009	<0.009
BHC,A	UG/L	39337 EC	<0.005	<0.009	<0.009	<0.009
BHC,B	UG/L	39338 EC	<0.005	<0.009	<0.009	<0.009
BHC,D	UG/L	34259 EC	<0.005	<0.009	<0.009	<0.009
BHC,G(LINDANE)	UG/L	39340 EC	<0.005	<0.009	<0.009	<0.009
CHLORDANE	UG/L	39350 EC	<0.006	<0.012	<0.012	<0.012
DDD,PP'	UG/L	39310 EC	<0.012	<0.009	<0.009	<0.009
DDE,PP'	UG/L	39320 EC	<0.005	<0.009	<0.009	<0.009

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6GW01 RRPR6W 1	R6SW01 RRPR6W 2	R6SW02 RRPR6W 3	R6SW03 RRPR6W 4
DATE			11/02/87	10/07/87	10/07/87	10/07/87
TIME			13:15	10:40	11:30	12:00
DDT,PP'	UG/L	39300 EC	<0.012	<0.009	<0.009	<0.009
DIELDRIN	UG/L	39380 EC	<0.005	<0.009	<0.009	<0.009
ENDOSULFAN,A	UG/L	34361 EC	<0.005	<0.009	<0.009	<0.009
ENDOSULFAN,B	UG/L	34356 EC	<0.012	<0.009	<0.009	<0.009
ENDOSULFAN SULFATE	UG/L	34351 EC	<0.012	<0.009	<0.009	<0.009
ENDRIN	UG/L	39390 EC	<0.005	<0.009	<0.009	<0.009
ENDRIN ALDEHYDE	UG/L	34366 EC	<0.012	<0.009	<0.009	<0.009
HEPTACHLOR	UG/L	39410 EC	<0.005	<0.009	<0.009	<0.009
HEPTACHLOR EPOXIDE	UG/L	39420 EC	<0.005	<0.009	<0.009	<0.009
TOXAPHENE	UG/L	39400 EC	<0.600	<1.20	<1.20	<1.20
PCB-1016	UG/L	34671 EC	<0.121	<0.247	<0.247	<0.247
PCB-1221	UG/L	39488 EC	<0.121	<0.247	<0.247	<0.247
PCB-1232	UG/L	39492 EC	<0.121	<0.247	<0.247	<0.247
PCB-1242	UG/L	39496 EC	<0.121	<0.247	<0.247	<0.247
PCB 1248	UG/L	39500 EC	<0.121	<0.247	<0.247	<0.247
PCB-1254	UG/L	39504 EC	<0.121	<0.247	<0.247	<0.247
PCB-1260	UG/L	39508 EC	<0.121	<0.247	<0.247	<0.247
ANTIMONY,TOTAL	UG/L	1097 ICAP	<21.0	<21.0	<21.0	<21.0
ARSENIC,TOTAL	UG/L	1002 GFAA	<6.4	<10.0	<10.0	<10.0
BERYLLIUM, TOTAL	UG/L	1012 ICAP	<1.0	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	R6GW01 RRPR6W	R6SW01 RRPR6W	R6SW02 RRPR6W	R6SW03 RRPR6W
UNITS	METHOD	1	2	3	4
DATE		11/02/87	10/07/87	10/07/87	10/07/87
TIME		13:15	10:40	11:30	12:00
CADMIUM,TOTAL	1027	<2.4	<2.4	<2.4	<2.4
UG/L	ICAP				
CHROMIUM,TOTAL	1034	<3.3	97.4	107	116
UG/L	ICAP				
COPPER,TOTAL	1042	6.1	<2.8	<2.8	67.8
UG/L	ICAP				
LEAD,TOTAL	1051	121	<400	<400	<400
UG/L	ICAP				
MERCURY,TOTAL	71900	<0.2	<0.2	<0.2	<0.2
UG/L	CVAA				
NICKEL,TOTAL	1067	<8.6	<8.6	<8.6	<8.6
UG/L	ICAP				
SELENIUM,TOTAL	1147	<2.5	162	191	241
UG/L	GFAA				
SILVER,TOTAL	1077	<3.6	32.2	31.1	28.7
UG/L	ICAP				
THALLIUM,TOTAL	1059	<3.4	<6.8	<6.8	<6.8
UG/L	GFAA				
ZINC,TOTAL	1092	40.1	<1.8	<1.8	52.5
UG/L	ICAP				
PHENOLS	32730	58	70	40	1200
UG/L	1				

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE# 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	R6SE01 RRPR6S 1	R6SE02 RRPR6S 2	R6SE03 RRPR6S 3	R6S04A RRPR6S 4	R6S05A RRPR6S 5	R6S09A RRPR6S 6	R6S010A RRPR6S 7	R6S010B RRPR6S 8	R6S010C RRPR6S 9	R6S011A RRPR6S 10	R6S012A RRPR6S 11	R6S014A RRPR6S 12	R6S015A RRPR6S 13	R6S016A RRPR6S 14	R6S017A RRPR6S 15
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
MOISTURE %WET WT	70320 1	65.2	47.8	60.1	17.1	29.3	31.9	7.1	11.5	9.8	8.7	35.4	23.7	27.4	25.5	27.0
PH,SOIL STD UNITS	99218 1	6.6	7.1	7.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BENZENE UG/KG-DRY	34237 GMS	<630	<420	<550	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BROMODICHLOROMETHANE UG/KG-DRY	34330 GMS	<320	<210	<280	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BROMOFORM UG/KG-DRY	34290 GMS	<680	<450	<590	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BROMOMETHANE UG/KG-DRY	34416 GMS	<800	<540	<700	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CARBON TETRACHLORIDE UG/KG-DRY	34299 GMS	<400	<270	<350	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CHLOROBENZENE UG/KG-DRY	34304 GMS	<860	<570	<750	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CHLOROETHANE UG/KG-DRY	34314 GMS	<1200	<790	<1000	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2-CHLOROETHYLVINYL ETHER UG/KG-DRY	34579 GMS	<1400	<960	<1300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CHLOROFORM UG/KG-DRY	34318 GMS	<230	<150	<200	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CHLOROMETHANE UG/KG-DRY	34421 GMS	<620	<410	<540	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
DIBROMOCHLOROMETHANE UG/KG-DRY	34309 GMS	<450	<300	<390	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,1-DICHLOROETHANE UG/KG-DRY	34499 GMS	<680	<450	<590	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,2-DICHLOROETHANE UG/KG-DRY	34534 GMS	<400	<270	<350	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,1-DICHLOROETHYLENE UG/KG-DRY	34504 GMS	<400	<270	<350	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
TRANS-1,2-DICHLORO ETHENE UG/KG-DRY	34549 GMS	<230	<150	<200	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
,2-DICHLOROPROPANE UG/KG-DRY	34544 GMS	<860	<570	<750	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CIS-1,3-DICHLORO PROPENE UG/KG-DRY	34702 GMS	<720	<480	<630	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
TRANS-1,3-DICHLORO PROPENE UG/KG-DRY	34697 GMS	<920	<610	<800	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	R6SE01 RRPR6S 1	R6SE02 RRPR6S 2	R6SE03 RRPR6S 3	R6S04A RRPR6S 4	R6S05A RRPR6S 5	R6S09A RRPR6S 6	R6S010A RRPR6S 7	R6S010B RRPR6S 8	R6S010C RRPR6S 9	R6S011A RRPR6S 10	R6S012A RRPR6S 11	R6S014A RRPR6S 12	R6S015A RRPR6S 13	R6S016A RRPR6S 14	R6S017A RRPR6S 15
		SAMPLE ID/#														
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
ETHYLBENZENE UG/KG-DRY	34374 GMS	<1000	<690	<900	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
METHYLENE CHLORIDE UG/KG-DRY	34426 GMS	<2900	<1900	<2500	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,1,2,2-TETRACHLORO ETHANE UG/KG-DRY	34519 GMS	<590	<390	<510	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
TETRACHLOROETHENE UG/KG-DRY	34478 GMS	<590	<390	<510	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
TOLUENE UG/KG-DRY	34483 GMS	<860	<570	<750	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,1,1-TRICHL'ETHANE UG/KG-DRY	34509 GMS	<550	<360	<480	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,1,2-TRICHL'ETHANE UG/KG-DRY	34514 GMS	<720	<480	<630	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
TRICHLOROETHENE UG/KG-DRY	34487 GMS	<270	<180	<240	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
TRICHLOROFLUOROMETHA NE UG/KG-DRY	34491 GMS	<460	<310	<400	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
VINYL CHLORIDE UG/KG-DRY	34495 GMS	<700	<470	<610	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
M-XYLENE UG/KG-DRY	97016 GMS	<860	<570	<750	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
O,P-XYLENE UG/KG-DRY	97017 GMS	<860	<570	<750	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
METHYL ETHYL KETONE UG/KG-DRY	75078 GMS	<6900	<4600	<6000	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
METHYL ISOBUT'KETONE UG/KG-DRY	75169 GMS	<1700	<1100	<1500	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,2-DIBROMOETHANE (EDB) UG/KG-DRY	78756 EC	<0.816	<0.558	<0.706	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
ACENAPHTHENE UG/KG-DRY	34208 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
ACENAPHTHYLENE UG/KG-DRY	34203 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
ANTHRACENE UG/KG-DRY	34223 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BENZIDINE UG/KG-DRY	39121 GMS	<1400	<960	<1300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BENZO(A)ANTHRACENE UG/KG-DRY	34529 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE# 3

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	R6SE01 RRPR6S 1	R6SE02 RRPR6S 2	R6SE03 RRPR6S 3	R6SE4A RRPR6S 4	R6S05A RRPR6S 5	R6S09A RRPR6S 6	R6S010A RRPR6S 7	R6S010B RRPR6S 8	R6S010C RRPR6S 9	R6S011A RRPR6S 10	R6S012A RRPR6S 11	R6S014A RRPR6S 12	R6S015A RRPR6S 13	R6S016A RRPR6S 14	R6S017A RRPR6S 15
		SAMPLE ID/#														
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
BENZO(B)FLUORANTHENE UG/KG-DRY	34233 GMS	<260	<170	<230	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BENZO(K)FLUORANTHENE UG/KG-DRY	34245 GMS	<260	<170	<230	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BENZO(A)PYRENE UG/KG-DRY	34250 GMS	<260	<170	<230	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BENZO(GHI)PERYLENE UG/KG-DRY	34524 GMS	<340	<230	<300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BUTYLBENZYLPHTHALATE UG/KG-DRY	34295 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BIS(2-CHLOROETHYL) ETHER UG/KG-DRY	34276 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BIS(2-CHLOROETHOXY) METHANE UG/KG-DRY	34281 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BIS(2-ETHYLHEXYL) PHTHALATE UG/KG-DRY	39102 GMS	13000	<150	10000	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
BIS(2-CHLOROISOPROPYL) ETHER UG/KG-DRY	34286 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
4-BROMOPHENYL PHENYL ETHER UG/KG-DRY	34639 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2-CHLORONAPHTHALENE UG/KG-DRY	34584 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2-CHLOROPHENOL UG/KG-DRY	34589 GMS	<290	<190	<250	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
4-CHLORO-3-METHYL PHENOL UG/KG-DRY	34455 GMS	<340	<230	<300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
4-CHLOROPHENYLPHENYL ETHER UG/KG-DRY	34644 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CHRYSENE UG/KG- DRY	34323 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
DIBEN(A,H)ANTHRACENE UG/KG-DRY	34559 GMS	<340	<230	<300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
DI-N-BUTYL PHTHALATE UG/KG-DRY	39112 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,3-DICHLOROBENZENE UG/KG-DRY	34569 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,2-DICHLOROBENZENE UG/KG-DRY	34539 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
1,4-DICHLOROBENZENE UG/KG-DRY	34574 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/ STATUS: FINAL PAGE# 4

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# R6SE01 RRPR6S 1	R6SE02 RRPR6S 2	R6SE03 RRPR6S 3	R6S04A RRPR6S 4	R6S05A RRPR6S 5	R6S09A RRPR6S 6	R6S010A RRPR6S 7	R6S010B RRPR6S 8	R6S010C RRPR6S 9	R6S011A RRPR6S 10	R6S012A RRPR6S 11	R6S014A RRPR6S 12	R6S015A RRPR6S 13	R6S016A RRPR6S 14	R6S017A RRPR6S 15
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
3,3-DICHL'BENZIDINE UG/KG-DRY	34634 GMS	<290	<190	<250	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2,4-DICHLOROPHENOL UG/KG-DRY	34604 GMS	<340	<230	<300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
DIETHYL PHTHALATE UG/KG-DRY	34339 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2,4-DIMETHYLPHENOL UG/KG-DRY	34609 GMS	<1700	<1100	<1500	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
DIMETHYL PHTHALATE UG/KG-DRY	34344 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2,4-DINITROPHENOL UG/KG-DRY	34619 GMS	<3700	<2500	<3300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2,4-DINITROTOLUENE UG/KG-DRY	34614 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2,6-DINITROTOLUENE UG/KG-DRY	34629 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
DI-N-OCTYL PHTHALATE UG/KG-DRY	34599 GMS	<240	<160	<210	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
FLUORANTHENE UG/KG-DRY	34379 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
FLUORENE UG/KG- DRY	34384 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
HEXACHLOROBENZENE UG/KG-DRY	39701 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
HEXACHLOROBUTADIENE UG/KG-DRY	39705 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
HEXACHLOROCYCLOPENTA DIENE UG/KG-DRY	34389 GMS	<2900	<1900	<2500	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
HEXACHLOROETHANE UG/KG-DRY	34399 GMS	<220	<140	<190	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
INDENO(1,2,3-CD) PYRENE UG/KG-DRY	34406 GMS	<340	<230	<300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
'SOPHORONE UG/KG-DRY	34411 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
2-METHYL-4,6-DINITRO PHENOL UG/KG-DRY	34660 GMS	<2900	<1900	<2500	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
NAPHTHALENE UG/KG-DRY	34445 GMS	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
NITROBENZENE UG/KG-DRY	34450 GMS	<200	<130	<180	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	SAMPLE ID/# R6SE01	R6SE02	R6SE03	R6S04A	R6S05A	R6S09A	R6S010A	R6S010B	R6S010C	R6S011A	R6S012A	R6S014A	R6S015A	R6S016A	R6S017A
		RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S	RRPR6S
UNITS	METHOD	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
2-NITROPHENOL	34594	<290	<190	<250	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
4-NITROPHENOL	34649	<1700	<1100	<1500	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
N-NITROSODIMET'AMINE	34441	<290	<190	<250	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
N-NITROSODI-N-PROPYL	34431	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
AMINE UG/KG-DRY	GMS															
N-NITROSODIPHE'AMINE	34436	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
PENTACHLPHENOL	39061	<860	<570	<750	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
PHENANTHRENE	34464	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
PHENOL	34695	<320	<210	<280	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
PYRENE	34472	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
1,2,4-TRICH'BENZENE	34554	<170	<110	<150	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
2,4,6-TRICH'PHENOL	34624	<340	<230	<300	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	GMS															
ALDRIN	39333	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
BHC,A	39076	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
BHC,B	34257	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
BHC,D	34262	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
BHC,G(LINDANE)	39783	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
CHLORDANE	39351	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
DDD,PP'	39311	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
DDE,PP'	39321	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
DDT,PP'	39301	<57.2	<38.3	<50.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	SAMPLE ID/# R6SE01 RRPR6S 1	R6SE02 RRPR6S 2	R6SE03 RRPR6S 3	R6S04A RRPR6S 4	R6S05A RRPR6S 5	R6S09A RRPR6S 6	R6S010A RRPR6S 7	R6S010B RRPR6S 8	R6S010C RRPR6S 9	R6S011A RRPR6S 10	R6S012A RRPR6S 11	R6S014A RRPR6S 12	R6S015A RRPR6S 13	R6S016A RRPR6S 14	R6S017A RRPR6S 15
UNITS	METHOD															
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
DIELDRIN	39383	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
ENDOSULFAN,A	34364	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
ENDOSULFAN,B	34359	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
ENDOSULFAN SULFATE	34354	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
ENDRIN	39393	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
ENDRIN ALDEHYDE	34369	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
HEPTACHLOR	39413	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
HEPTACHLOR EPOXIDE	39423	<401	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
TOXAPHENE	39403	<40.1	<26.8	<35.1	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB 1016	39514	<590	<395	<516	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB-1221	39491	<590	<390	<520	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB-1232	39495	<590	<390	<520	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB-1242	39499	<590	<390	<520	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB-1248	39503	<590	<390	<520	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB-1254	39507	<590	<390	<520	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
PCB-1260	39511	<590	<390	<520	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG-DRY	EC															
ANTIMONY,SED	1098	<11	<6.8	<9.7	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
MG/KG-DRY	ICAP															
ARSENIC,SED	1003	3.76	1.94	4.75	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G- DRY	GFAA															
BERYLLIUM,SED	1013	<0.825	<0.502	<0.722	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
MG/KG-DRY	ICAP															
CADMIUM,SED	1028	1.71	0.520	0.747	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G- DRY	ICAP															

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	SAMPLE ID/# R6SE01	R6SE02	R6SE03	R6S04A	R6S05A	R6S09A	R6S010A	R6S010B	R6S010C	R6S011A	R6S012A	R6S014A	R6S015A	R6S016A	R6S017A
UNITS	METHOD	RRPR6S 1	RRPR6S 2	RRPR6S 3	RRPR6S 4	RRPR6S 5	RRPR6S 6	RRPR6S 7	RRPR6S 8	RRPR6S 9	RRPR6S 10	RRPR6S 11	RRPR6S 12	RRPR6S 13	RRPR6S 14	RRPR6S 15
DATE		10/07/87	10/07/87	10/07/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87	11/04/87
TIME		10:40	11:40	12:00	13:20	13:40	14:00	10:40	10:45	10:55	12:30	12:45	08:05	08:20	09:50	10:15
CHROMIUM,SED	1029	14.2	6.58	13.9	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G- DRY	ICAP															
COPPER,SED	1043	35.9	10.9	57.5	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G- DRY	ICAP															
LEAD,SED	1052	12.2	6.06	21.2	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G-DRY	ICAP															
MERCURY	71921	<0.144	<0.075	0.174	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G-DRY	CVAA															
NICKEL,SED	1068	<9.39	<5.71	<8.22	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G- DRY	ICAP															
SELENIUM,SED	1148	1.92	0.851	<0.742	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
MG/KG-DRY	GFAA															
SILVER,SED	1078	<0.768	<0.468	<0.673	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
MG/KG- DRY	ICAP															
THALLIUM,SED	34480	<0.696	<0.462	<0.594	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
MG/KG- DRY	GFAA															
ZINC,SED	1093	53.5	22.2	67.0	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/G-DRY	ICAP															
PHENOLS,SED	32731	6590	3670	5410	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/KG- DRY	I															
LEAD,SED	1052	NRQ	NRQ	NRQ	316	376	988	250	199	63.6	35.1	214	236	116	71.1	79.0
UG/G-DRY	GFAA															
EP-TOX,DATE OF EXTRA	97078	NRQ	NRQ	NRQ	NRQ	NRQ	3-3-88	11-10-87	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
CTION	M															
LEAD,DISS	1049	NRQ	NRQ	NRQ	NRQ	NRQ	10.6	2.8	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ
UG/L	GFAA															

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR6S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 6 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	R6S018A RRPR6S 16	R6S019A RRPR6S 17	R6S020A RRPR6S 18
DATE			11/04/87	11/04/87	11/04/87
TIME			10:30	12:15	13:10
MOISTURE		70320	25.7	30.2	28.4
	%WET WT	1			
LEAD,SED		1052	46.3	233	187
	UG/G-DRY	GFAA			

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE# 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# R7GW01 RRPR7W 1	R7GW02 RRPR7W 2	R7GW03 RRPR7W 3	R7GW04 RRPR7W 4	R7GW05 RRPR7W 5	R7GW06 RRPR7W 6	R7GW07 RRPR7W 7	R7GW08 RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
WATER TEMP	10	27.0	27.9	27.8	29.1	28.3	28.8	28.1	27.5
C	0								
PH,FIELD	400	7.10	7.40	7.90	7.30	7.00	7.00	6.80	6.70
STD UNITS	0								
SP.COND.,FIELD@25C	94	19800	7060	1810	17700	6000	5220	47200	590
UMHOS/CM	0								
BENZENE	34030	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS								
BROMODICHLOROMETHANE	32101	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2
UG/L	GMS								
BROMOFORM	32104	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS								
BROMOMETHANE	34413	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8
UG/L	GMS								
CARBON TETRACHLORIDE	32102	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS								
CHLOROBENZENE	34301	<6.0	<6.0	<6.0	180	<6.0	<6.0	<6.0	<6.0
UG/L	GMS								
CHLOROETHANE	34311	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2
UG/L	GMS								
2-CHLOROETHYLVINYL	34576	<15	<15	<15	<15	<15	<15	<15	<15
ETHER UG/L	GMS								
CHLOROFORM	32106	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6
UG/L	GMS								
CHLOROMETHANE	34418	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3
UG/L	GMS								
DIBROMOCHLOROMETHANE	32105	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1
UG/L	GMS								
1,1-DICHLOROETHANE	34496	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS								
1,2-DICHLOROETHANE	34531	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS								
1,1-DICHLOROETHYLENE	34501	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS								
TRANS-1,2-DICHLORO	34546	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6
ETHENE UG/L	GMS								
1,2-DICHLOROPROPANE	34541	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS								
CIS-1,3-DICHLORO	34704	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
PROPENE UG/L	GMS								

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# R7GW01 RRPR7W 1	R7GW02 RRPR7W 2	R7GW03 RRPR7W 3	R7GW04 RRPR7W 4	R7GW05 RRPR7W 5	R7GW06 RRPR7W 6	R7GW07 RRPR7W 7	R7GW08 RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50	<50	<50	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
ACENAPHTHENE UG/L	34205 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
ACENAPHTHYLENE UG/L	34200 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
ANTHRACENE UG/L	34220 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BENZIDINE UG/L	39120 GMS	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1	<2.1
BENZO(A)ANTHRACENE UG/L	34526 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BENZO(B)FLUORANTHENE UG/L	34230 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
BENZO(K)FLUORANTHENE UG/L	34242 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
BENZO(A)PYRENE UG/L	34247 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<2.0
BENZO(GHI)PERYLENE UG/L	34521 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.5

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# R7GW01 RRPR7W 1	R7GW02 RRPR7W 2	R7GW03 RRPR7W 3	R7GW04 RRPR7W 4	R7GW05 RRPR7W 5	R7GW06 RRPR7W 6	R7GW07 RRPR7W 7	R7GW08 RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
BUTYLBENZYLPHTHALATE UG/L	34292 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.5
BIS(2-CHLOROETHYL) ETHER UG/L	34273 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BIS(2-CHLOROETHOXY) METHANE UG/L	34278 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
BIS(2-ETHYLHEXYL) PHTHALATE UG/L	39100 GMS	<1.0	1.5	<1.0	<1.0	1.7	<1.0	5.3	<1.0
BIS(2-CHLOROISOPROPYL) ETHER UG/L	34283 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
4-BROMOPHENYLPHENYL ETHER UG/L	34636 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<2.0
2-CHLORONAPHTHALENE UG/L	34581 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-CHLOROPHENOL UG/L	34586 GMS	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.7	<1.0
4-CHLORO-3-METHYL PHENOL UG/L	34452 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.0
4-CHLOROPHENYLPHENYL ETHER UG/L	34641 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.5
CHRYSENE UG/L	34320 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
DIBENZ(A,H)ANTHRACENE UG/L	34556 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.5
DI-N-BUTYLPHTHALATE UG/L	39110 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,3,DICHLOROBENZENE UG/L	34566 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,2-DICHLOROBENZENE UG/L	34536 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
1,4-DICHLOROBENZENE UG/L	34571 GMS	<1.0	<1.0	<1.0	7.3	<1.0	<1.0	<1.0	<1.0
3,3'-DICHLOROBENZIDINE UG/L	34631 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5
2,4-DICHLOROPHENOL UG/L	34601 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
DIETHYLPHTHALATE UG/L	34336 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2,4-DIMETHYLPHENOL UG/L	34606 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4

RR-00039-03.13-04/01/88

PROJECT NUMBER 87468 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# R7GW01 RRPR7W 1	R7GW02 RRPR7W 2	R7GW03 RRPR7W 3	R7GW04 RRPR7W 4	R7GW05 RRPR7W 5	R7GW06 RRPR7W 6	R7GW07 RRPR7W 7	R7GW08 RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
DIMETHYLPTHALATE UG/L	34341 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2,4-DINITROPHENOL UG/L	34616 GMS	<30	<30	<30	<30	<30	<30	<30	<30
2,4-DINITROTOLUENE UG/L	34611 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2,6-DINITROTOLUENE UG/L	34626 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
DI-N-OCTYLPHTHALATE UG/L	34596 GMS	<1.0	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1	<1.1
FLUORANTHENE UG/L	34376 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
FLUORENE UG/L	34381 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
HEXACHLOROBENZENE UG/L	39700 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
HEXACHLOROBUTADIENE UG/L	34391 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.1
HEXACHLOROCYCLOPENTA DIENE UG/L	34386 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
HEXACHLOROETHANE UG/L	34396 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.5	<1.0
INDENO(1,2,3-CD) PYRENE UG/L	34403 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0	<2.0
ISOPHORONE UG/L	34408 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-METHYL-4,6-DINITRO PHENOL UG/L	34657 GMS	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
NAPHTHALENE UG/L	34696 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
NITROBENZENE UG/L	34447 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
2-NITROPHENOL UG/L	34591 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4	<1.4
4-NITROPHENOL UG/L	34646 GMS	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3	<3.3	<5.5
N-NITROSODIMETHAMINE UG/L	34438 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.5
N-NITROSODI-N-PROPYL AMINE UG/L	34428 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	SAMPLE ID/# R7GW01	R7GW02	R7GW03	R7GW04	R7GW05	R7GW06	R7GW07	R7GW08
UNITS	METHOD	RRPR7W 1	RRPR7W 2	RRPR7W 3	RRPR7W 4	RRPR7W 5	RRPR7W 6	RRPR7W 7	RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
N-NITROSODIPHE'AMINE	34433	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS								
PENTACHLOROPHENOL	39032	<10	<10	<10	<10	<10	<10	<10	<10
UG/L	GMS								
PHENANTHRENE	34461	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS								
PHENOL	34694	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.3	<1.0
UG/L	GMS								
PYRENE	34469	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS								
1,2,4-TRICH'BENZENE	34551	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS								
2,4,6-TRICHL'PHENOL	34621	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8	<1.8
UG/L	GMS								
ALDRIN	39330	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
BHC,A	39337	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
BHC,B	39338	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
BHC,D	34259	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
BHC,G(LINDANE)	39340	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
CHLORDANE	39350	<0.059	<0.006	<0.006	<0.059	<0.006	<0.059	<0.006	<0.006
UG/L	EC								
DDD,PP'	39310	<0.012	<0.012	<0.012	<0.118	<0.012	<0.118	<0.005	<0.005
UG/L	EC								
DDE,PP'	39320	<0.005	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
DDT,PP'	39300	<0.005	<0.005	<0.005	<0.118	<0.012	<0.118	<0.005	<0.005
UG/L	EC								
DIELDRIN	39380	<0.005	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
ENDOSULFAN,A	34361	<0.005	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
ENDOSULFAN,B	34356	<0.005	<0.005	<0.005	<0.118	<0.012	<0.118	<0.005	<0.005
UG/L	EC								
ENDOSULFAN SULFATE	34351	<0.029	<0.029	<0.029	<0.118	<0.012	<0.118	<0.009	<0.024
UG/L	EC								

RR-00039-03.13-04/01/88

PROJECT NUMBER 87466 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	R7GW01	R7GW02	R7GW03	R7GW04	R7GW05	R7GW06	R7GW07	R7GW08
		SAMPLE ID/#							
UNITS	METHOD	RRPR7W 1	RRPR7W 2	RRPR7W 3	RRPR7W 4	RRPR7W 5	RRPR7W 6	RRPR7W 7	RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
ENDRIN	39390	<0.005	<0.005	<0.005	<0.118	<0.012	<0.118	<0.005	<0.005
UG/L	EC								
ENDRIN ALDEHYDE	34366	<0.005	<0.005	<0.005	<0.118	<0.012	<0.118	<0.005	<0.005
UG/L	EC								
HEPTACHLOR	39410	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
HEPTACHLOR EPOXIDE	39420	<0.047	<0.005	<0.005	<0.047	<0.005	<0.047	<0.005	<0.005
UG/L	EC								
TOXAPHENE	39400	<0.600	<0.600	<0.600	<6.00	<0.600	<6.00	<0.600	<0.600
UG/L	EC								
PCB-1016	34671	<1.21	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
PCB-1221	39488	<1.21	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
PCB-1232	39492	<1.21	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
PCB-1242	39496	<1.21	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
PCB 1248	39500	<0.121	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
PCB-1254	39504	<0.121	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
PCB-1260	39508	<0.121	<0.121	<0.121	<1.21	<0.121	<1.21	<0.121	<0.121
UG/L	EC								
ANTIMONY,TOTAL	1097	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	1510	<18.0
UG/L	ICAP								
ARSENIC,TOTAL	1002	9.6	<1.6	2.2	20.9	<1.6	10.9	7.8	7.7
UG/L	GFAA								
BERYLLIUM, TOTAL	1012	<1.0	<1.0	<1.0	<1.0	<1.0	2.7	17.7	<0.7
UG/L	ICAP								
CADMIUM,TOTAL	1027	<2.4	<2.4	<2.4	<2.4	<2.4	<2.4	24.2	<0.9
UG/L	ICAP								
CHROMIUM,TOTAL	1034	3.6	5.3	6.1	15.5	<3.3	153	440	23.5
UG/L	ICAP								
COPPER,TOTAL	1042	6.3	33.6	14.9	14.8	47.0	47.7	1820	167
UG/L	ICAP								
LEAD,TOTAL	1051	<20.0	<20.0	<20.0	<20.0	<20.0	<20.0	<60.0	<21.0
UG/L	ICAP								
MERCURY,TOTAL	71900	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2
UG/L	CVAA								

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR7W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 7 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	R7GW01	R7GW02	R7GW03	R7GW04	R7GW05	R7GW06	R7GW07	R7GW08
		SAMPLE ID/#							
UNITS	METHOD	RRPR7W 1	RRPR7W 2	RRPR7W 3	RRPR7W 4	RRPR7W 5	RRPR7W 6	RRPR7W 7	RRPR7W 8
DATE		10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	10/28/87	12/03/87	02/02/88
TIME		14:10	13:00	11:30	10:20	08:00	09:05	08:50	12:30
NICKEL,TOTAL	1067	<8.6	<8.6	<8.6	<8.6	13.5	54.8	225	<20.0
UG/L	ICAP								
SELENIUM,TOTAL	1147	32.0	12.4	<1.8	15.6	26.4	34.4	<8.8	<3.6
UG/L	GFAA								
SILVER,TOTAL	1077	39.0	12.6	<3.6	40.2	39.7	<3.6	369	<2.5
UG/L	ICAP								
THALLIUM,TOTAL	1059	17.6	<3.4	<3.4	23.9	77.1	89.0	<38.0	58.5
UG/L	GFAA								
ZINC,TOTAL	1092	62.8	<1.8	5.0	5.4	<1.8	89.7	3510	41.5
UG/L	ICAP								
PHENOLS	32730	48	100	27	30	54	36	160	16
UG/L	1								
CHROMIUM,(+6)	1032	<10.0	<10.0	<10.0	<10.0	<10.0	<10.0	<10.0	<10.0
UG/L	1								

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR8W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 8 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	STORET #	8SW01	8SW02	8SW03	8SW04	8SW05
		RRPR8W	RRPR8W	RRPR8W	RRPR8W	RRPR8W
UNITS	METHOD	1	2	3	5	6
DATE		10/27/87	10/27/87	10/27/87	10/27/87	10/27/87
TIME		08:30	07:30	09:15	10:55	11:30
WATER TEMP	10	27.3	27.5	28.1	28.9	29.8
C	0					
PH,FIELD	400	7.20	7.20	7.60	8.70	8.80
STD UNITS	0					
SP.COND.,FIELD@25C	94	549	1120	1260	467	391
UMHOS/CM	0					
BENZENE	34030	1.1	<1.0	<1.0	<1.0	<1.0
UG/L	GMS					
BROMODICHLOROMETHANE	32101	<2.2	<2.2	<2.2	<2.2	<2.2
UG/L	GMS					
BROMOFORM	32104	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS					
BROMOMETHANE	34413	<5.8	<5.8	<5.8	<5.8	<5.8
UG/L	GMS					
CARBON TETRACHLORIDE	32102	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS					
CHLOROBENZENE	34301	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS					
CHLOROETHANE	34311	<8.2	<8.2	<8.2	<8.2	<8.2
UG/L	GMS					
2-CHLOROETHYLVINYL	34576	<15	<15	<15	<15	<15
ETHER UG/L	GMS					
CHLOROFORM	32106	<1.6	<1.6	<1.6	<1.6	<1.6
UG/L	GMS					
CHLOROMETHANE	34418	<4.3	<4.3	<4.3	<4.3	<4.3
UG/L	GMS					
DIBROMOCHLOROMETHANE	32105	<3.1	<3.1	<3.1	<3.1	<3.1
UG/L	GMS					
1,1-DICHLOROETHANE	34496	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS					
1,2-DICHLOROETHANE	34531	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS					
1,1-DICHLOROETHYLENE	34501	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS					
TRANS-1,2-DICHLORO	34546	<1.6	<1.6	<1.6	<1.6	<1.6
ETHENE UG/L	GMS					
1,2-DICHLOROPROPANE	34541	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS					
CIS-1,3-DICHLORO	34704	<5.0	<5.0	<5.0	<5.0	<5.0
PROPENE UG/L	GMS					

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR8W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 8 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	8SW01 RRPR8W 1	8SW02 RRPR8W 2	8SW03 RRPR8W 3	8SW04 RRPR8W 5	8SW05 RRPR8W 6
DATE		10/27/87	10/27/87	10/27/87	10/27/87	10/27/87
TIME		08:30	07:30	09:15	10:55	11:30
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	1.1	<1.0	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	3.6	<3.2	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0	<1.0	<1.0
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48	<48	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12	<12	<12	<12
M-XYLENE UG/L	98553 GMS	<12	<12	<12	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<12	<12	<12
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.010	<0.010	<0.010	<0.010	<0.010
LEAD,TOTAL UG/L	1051 GFAA	<1.9	<1.9	<1.9	<1.9	<1.9
OIL&GR,IR MG/L	560 1	<0.2	<0.2	<0.2	<0.2	<0.2

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR8S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 8 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8SE01 RRPR8S 1	8SE02 RRPR8S 2	8SE03 RRPR8S 3
DATE			10/27/87	10/27/87	10/27/87
TIME			08:45	07:45	09:30
MOISTURE		70320	31.1	21.9	48.5
	%WET WT	1			
OIL&GR,IR,SED		561	247	69	306
	UG/G- DRY	1			
BENZENE		34237	<320	<280	<430
	UG/KG-DRY	GMS			
BROMODICHLOROMETHANE		34330	<160	<140	<210
	UG/KG-DRY	GMS			
BROMOFORM		34290	<340	<300	<460
	UG/KG-DRY	GMS			
BROMOMETHANE		34416	<410	<360	<540
	UG/KG-DRY	GMS			
CARBON TETRACHLORIDE		34299	<200	<180	<270
	UG/KG-DRY	GMS			
CHLOROBENZENE		34304	<440	<380	<580
	UG/KG-DRY	GMS			
CHLOROETHANE		34314	<600	<520	<800
	UG/KG-DRY	GMS			
2-CHLOROETHYLVINYL		34579	<730	<640	<970
ETHER	UG/KG-DRY	GMS			
CHLOROFORM		34318	<120	<100	<160
	UG/KG-DRY	GMS			
CHLOROMETHANE		34421	<310	<280	<420
	UG/KG-DRY	GMS			
DIBROMOCHLOROMETHANE		34309	<220	<200	<300
	UG/KG-DRY	GMS			
1,1-DICHLOROETHANE		34499	<340	<300	<460
	UG/KG-DRY	GMS			
1,2-DICHLOROETHANE		34534	<200	<180	<270
	UG/KG-DRY	GMS			
1,1-DICHLOROETHYLENE		34504	<200	<180	<270
	UG/KG-DRY	GMS			
TRANS-1,2-DICHLORO		34549	<120	<100	<160
ETHENE	UG/KG-DRY	GMS			
1,2-DICHLOROPROPANE		34544	<440	<380	<580
	UG/KG-DRY	GMS			
CIS-1,3-DICHLORO		34702	<360	<320	<490
PROPENE	UG/KG-DRY	GMS			
TRANS-1,3-DICHLORO		34697	<460	<410	<620
PROPENE	UG/KG-DRY	GMS			

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RRPR8S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 8 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	8SE01 RRPR8S 1	8SE02 RRPR8S 2	8SE03 RRPR8S 3
DATE			10/27/87	10/27/87	10/27/87
TIME			08:45	07:45	09:30
ETHYLBENZENE	UG/KG-DRY	34374 GMS	<520	<460	<700
METHYLENE CHLORIDE	UG/KG-DRY	34426 GMS	<1500	<1300	<1900
1,1,2,2-TETRACHLORO ETHANE	UG/KG-DRY	34519 GMS	<300	<260	<400
TETRACHLOROETHENE	UG/KG-DRY	34478 GMS	<300	<260	<400
TOLUENE	UG/KG-DRY	34483 GMS	<440	<380	<580
1,1,1-TRICHL'ETHANE	UG/KG-DRY	34509 GMS	<280	<240	<370
1,1,2-TRICHL'ETHANE	UG/KG-DRY	34514 GMS	<360	<320	<490
TRICHLOROETHENE	UG/KG-DRY	34487 GMS	<140	<120	<180
TRICHLOROFLUOROMETHA NE	UG/KG-DRY	34491 GMS	<230	<200	<310
VINYL CHLORIDE	UG/KG-DRY	34495 GMS	<360	<310	<480
M-XYLENE	UG/KG-DRY	97016 GMS	<440	<380	<580
O,P-XYLENE	UG/KG-DRY	97017 GMS	<440	<380	<580
METHYL ETHYL KETONE	UG/KG-DRY	75078 GMS	<3500	<3100	<4700
METHYL ISOBUT'KETONE	UG/KG-DRY	75169 GMS	<870	<770	<1200
1,2-DIBROMOETHANE (EDB)	UG/KG-DRY	78756 EC	<0.246	<0.205	<0.344
LEAD,SED	UG/G-DRY	1052 GFAA	14.0	14.6	26.1

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/2 STATUS: FINAL PAGE 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR10W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 10GW01 RPR10W 1	10GW02 RPR10W 2	10GW03 RPR10W 3	10GW04 RPR10W 4	10GW05 RPR10W 5	10GW06 RPR10W 6	10GW07 RPR10W 7	10GW08 RPR10W 8	10GW06 RPR10W 9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
WATER TEMP	10	28.0	28.7	29.0	28.3	28.6	29.3	27.3	28.9	NRQ
C	0									
PH,FIELD	400	6.50	7.80	6.80	7.80	7.80	7.20	7.80	7.80	NRQ
STD UNITS	0									
SP.COND.,FIELD@25C	94	35200	2000	24000	2550	6950	12330	6750	43600	NRQ
UMHOS/CM	0									
BENZENE	34030	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	NRQ
UG/L	GMS									
BROMODICHLOROMETHANE	32101	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	NRQ
UG/L	GMS									
BROMOFORM	32104	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	NRQ
UG/L	GMS									
BROMOMETHANE	34413	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	NRQ
UG/L	GMS									
CARBON TETRACHLORIDE	32102	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	NRQ
UG/L	GMS									
CHLOROBENZENE	34301	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	NRQ
UG/L	GMS									
CHLOROETHANE	34311	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	NRQ
UG/L	GMS									
2-CHLOROETHYLVINYL	34576	<15	<15	<15	<15	<15	<15	<15	<15	NRQ
ETHER UG/L	GMS									
CHLOROFORM	32106	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	NRQ
UG/L	GMS									
CHLOROMETHANE	34418	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	NRQ
UG/L	GMS									
DIBROMOCHLOROMETHANE	32105	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	NRQ
UG/L	GMS									
1,1-DICHLOROETHANE	34496	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	NRQ
UG/L	GMS									
1,2-DICHLOROETHANE	34531	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	NRQ
UG/L	GMS									
1,1-DICHLOROETHYLENE	34501	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	NRQ
UG/L	GMS									
TRANS-1,2-DICHLORO	34546	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	NRQ
ETHENE UG/L	GMS									
1,2-DICHLOROPROPANE	34541	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	NRQ
UG/L	GMS									
CIS-1,3-DICHLORO	34704	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	NRQ
PROPENE UG/L	GMS									

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPRIOW PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 10GW01 RPRIOW 1	10GW02 RPRIOW 2	10GW03 RPRIOW 3	10GW04 RPRIOW 4	10GW05 RPRIOW 5	10GW06 RPRIOW 6	10GW07 RPRIOW 7	10GW08 RPRIOW 8	10GW06 RPRIOW 9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	NRQ
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	NRQ
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<50	<50	<50	<50	<50	<50	NRQ
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	NRQ
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	NRQ
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	NRQ
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	NRQ
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	NRQ
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	NRQ
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	NRQ
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	NRQ
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48	<48	<48	<48	<48	<48	<48	NRQ
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12	<12	<12	<12	<12	<12	<12	NRQ
M-XYLENE UG/L	98553 GMS	<12	<12	<12	<12	<12	<12	<12	<12	NRQ
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<12	<12	<12	<12	<12	<12	NRQ
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.010	<0.010	<0.010	<0.010	0.015	<0.010	<0.010	<0.010	NRQ
ACENAPHTHENE UG/L	34205 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
ACENAPHTHYLENE UG/L	34200 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
ANTHRACENE UG/L	34220 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
BENZIDINE UG/L	39120 GMS	<2.1	<2.1	<2.1	<2.1	<2.1	NA	<2.1	<2.1	<2.1

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR10W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 10GW01 RPR10W 1	10GW02 RPR10W 2	10GW03 RPR10W 3	10GW04 RPR10W 4	10GW05 RPR10W 5	10GW06 RPR10W 6	10GW07 RPR10W 7	10GW08 RPR10W 8	10GW06 RPR10W 9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
BENZO(A)ANTHRACENE UG/L	34526 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
BENZO(B)FLUORANTHENE UG/L	34230 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	NA	<1.5	<1.5	<1.5
BENZO(K)FLUORANTHENE UG/L	34242 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	NA	<1.5	<1.5	<1.5
BENZO(A)PYRENE UG/L	34247 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	NA	<1.5	<1.5	<1.5
BENZO(GHI)PERYLENE UG/L	34521 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	NA	<2.0	<2.0	<2.0
BUTYLBENZYLPHTHALATE UG/L	34292 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
BIS(2-CHLOROETHYL) ETHER UG/L	34273 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
BIS(2-CHLOROETHOXY) METHANE UG/L	34278 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
BIS(2-ETHYLHEXYL) PHTHALATE UG/L	39100 GMS	<1.0	1.5	1.8	4.2	1.1	NA	1.1	<1.0	<1.0
BIS(2-CHL'ISOPROPYL) ETHER UG/L	34283 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
4-BROMOPHENYLPHENYL ETHER UG/L	34636 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
2-CHLORONAPHTHALENE UG/L	34581 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
2-CHLOROPHENOL UG/L	34586 GMS	<1.7	<1.7	<1.7	<1.7	<1.7	NA	<1.7	<1.7	<1.7
4-CHLORO-3-METHYL PHENOL UG/L	34452 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	NA	<1.4	<1.4	<1.4
4-CHLOROPHENYLPHENYL ETHER UG/L	34641 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
CHRYSENE UG/L	34320 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
DIBEN'(A,H)ANTH'CENE UG/L	34556 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	NA	<2.0	<2.0	<2.0
DI-N-BUTYLPHTHALATE UG/L	39110 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
1,3,DICHLOROBENZENE UG/L	34566 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
1,2-DICHLOROBENZENE UG/L	34536 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR10W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	10GW01 RPR10W 1	10GW02 RPR10W 2	10GW03 RPR10W 3	10GW04 RPR10W 4	10GW05 RPR10W 5	10GW06 RPR10W 6	SAMPLE ID/# 10GW07 RPR10W 7	10GW08 RPR10W 8	10GW06 RPR10W 9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
1,4-DICHLOROBENZENE UG/L	34571 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
3,3'-DICHL'BENZIDINE UG/L	34631 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	NA	<1.5	<1.5	<1.5
2,4-DICHLOROPHENOL UG/L	34601 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	NA	<1.4	<1.4	<1.4
DIETHYLPHTHALATE UG/L	34336 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
2,4-DIMETHYLPHENOL UG/L	34606 GMS	<1.4	<1.4	<1.4	<1.4	<1.4	NA	<1.4	<1.4	<1.4
DIMETHYLPTHALATE UG/L	34341 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
2,4-DINITROPHENOL UG/L	34616 GMS	<30	<30	<30	<30	<30	NA	<30	<30	<30
2,4-DINITROTOLUENE UG/L	34611 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
2,6-DINITROTOLUENE UG/L	34626 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
DI-N-OCTYLPHTHALATE UG/L	34596 GMS	<1.1	<1.1	<1.1	<1.1	<1.1	NA	<1.1	<1.1	<1.1
FLUORANTHENE UG/L	34376 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
FLUORENE UG/L	34381 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
HEXACHLOROBENZENE UG/L	39700 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
HEXACHLOROBUTADIENE UG/L	34391 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
HEXACHLOROCYCLOPENTA DIENE UG/L	34386 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	NA	<2.0	<2.0	<2.0
HEXACHLOROETHANE UG/L	34396 GMS	<1.5	<1.5	<1.5	<1.5	<1.5	NA	<1.5	<1.5	<1.5
INDENO(1,2,3-CD) PYRENE UG/L	34403 GMS	<2.0	<2.0	<2.0	<2.0	<2.0	NA	<2.0	<2.0	<2.0
ISOPHORONE UG/L	34408 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
2-METHYL-4,6-DINITRO PHENOL UG/L	34657 GMS	<5.0	<5.0	<5.0	<5.0	<5.0	NA	<5.0	<5.0	<5.0
NAPHTHALENE UG/L	34696 GMS	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR10W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	10GW01	10GW02	10GW03	10GW04	10GW05	10GW06	10GW07	10GW08	10GW06
		SAMPLE ID/#								
		RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W
UNITS	METHOD	1	2	3	4	5	6	7	8	9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
NITROBENZENE	34447	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
UG/L	GMS									
2-NITROPHENOL	34591	<1.4	<1.4	<1.4	<1.4	<1.4	NA	<1.4	<1.4	<1.4
UG/L	GMS									
4-NITROPHENOL	34646	<3.3	<3.3	<3.3	<3.3	<3.3	NA	<3.3	<3.3	<3.3
UG/L	GMS									
N-NITROSODIMET'AMINE	34430	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
UG/L	GMS									
N-NITROSODI-N-PROPYL	34428	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
AMINE UG/L	GMS									
N-NITROSODIPHE'AMINE	34433	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
UG/L	GMS									
PENTACHLOROPHENOL	39032	<10	<10	<10	<10	<10	NA	<10	<10	<10
UG/L	GMS									
PHENANTHRENE	34461	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
UG/L	GMS									
PHENOL	34694	<1.3	<1.3	<1.3	<1.3	<1.3	NA	<1.3	<1.3	<1.3
UG/L	GMS									
PYRENE	34469	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
UG/L	GMS									
1,2,4-TRICH'BENZENE	34551	<1.0	<1.0	<1.0	<1.0	<1.0	NA	<1.0	<1.0	<1.0
UG/L	GMS									
2,4,6-TRICHL'PHENOL	34621	<1.8	<1.8	<1.8	<1.8	<1.8	NA	<1.8	<1.8	<1.8
UG/L	GMS									
ALDRIN	39330	<0.005	<0.005	<0.008	<0.008	<0.008	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
BHC,A	39337	<0.005	<0.005	<0.012	<0.012	<0.012	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
BHC,B	39338	<0.005	<0.005	<0.005	<0.005	<0.005	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
BHC,D.	34259	<0.005	<0.005	<0.008	<0.008	<0.008	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
BHC,G(LINDANE)	39340	<0.005	<0.005	<0.012	<0.012	<0.012	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
CHLORDANE	39350	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	<0.006	NRQ
UG/L	EC									
DDD,PP'	39310	<0.005	<0.005	<0.008	<0.008	<0.008	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
DDE,PP'	39320	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR10W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	10GW01	10GW02	10GW03	10GW04	10GW05	10GW06	10GW07	10GW08	10GW06
		SAMPLE ID/#								
		RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W
UNITS	METHOD	1	2	3	4	5	6	7	8	9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
DDT,PP'	39300	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
DIELDRIN	39380	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
ENDOSULFAN,A	34361	<0.005	<0.005	<0.005	<0.005	<0.005	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
ENDOSULFAN,B	34356	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
ENDOSULFAN SULFATE	34351	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
ENDRIN	39390	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
ENDRIN ALDEHYDE	34366	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	NRQ
UG/L	EC									
HEPTACHLOR	39410	<0.005	<0.005	<0.005	<0.005	<0.005	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
HEPTACHLOR EPOXIDE	39420	<0.005	<0.005	<0.005	<0.005	<0.005	<0.047	<0.005	<0.005	NRQ
UG/L	EC									
TOXAPHENE	39400	<0.600	<0.600	<0.600	<0.600	<0.600	<0.600	<0.600	<0.600	NRQ
UG/L	EC									
PCB-1016	34671	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
PCB-1221	39488	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
PCB-1232	39492	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
PCB-1242	39496	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
PCB 1248	39500	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
PCB-1254	39504	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
PCB-1260	39508	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	<0.121	NRQ
UG/L	EC									
ANTIMONY,TOTAL	1097	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	<21.0	NRQ
UG/L	ICAP									
ARSENIC,TOTAL	1002	<10.0	<1.0	<10.0	<10.0	4.4	<1.0	<1.0	<10.0	NRQ
UG/L	GFAA									
BERYLLIUM, TOTAL	1012	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	NRQ
UG/L	ICAP									

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR10W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 10 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	10GW01	10GW02	10GW03	10GW04	10GW05	10GW06	10GW07	10GW08	10GW06
		SAMPLE ID/#								
		RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W	RPR10W
UNITS	METHOD	1	2	3	4	5	6	7	8	9
DATE		10/14/87	10/14/87	10/13/87	10/13/87	10/13/87	10/14/87	10/14/87	10/14/87	11/02/87
TIME		10:55	11:55	13:25	13:45	14:45	07:35	09:50	08:50	13:15
CADMIUM,TOTAL	1027	<2.4	4.0	<2.4	16.8	<2.4	<2.4	<2.4	<2.4	NRQ
UG/L	ICAP									
CHROMIUM,TOTAL	1034	202	19.6	101	78.9	137	33.7	33.2	177	NRQ
UG/L	ICAP									
COPPER,TOTAL	1042	464	207	205	624	520	652	78.9	633	NRQ
UG/L	ICAP									
LEAD,TOTAL	1051	<400	<20.0	<400	45.1	<20.0	<400	<20.0	134	NRQ
UG/L	ICAP									
MERCURY,TOTAL	71900	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	NRQ
UG/L	CVAA									
NICKEL,TOTAL	1067	88.6	28.6	43.9	44.1	58.1	17.7	<8.6	57.9	NRQ
UG/L	ICAP									
SELENIUM,TOTAL	1147	154	9.0	95.1	16.4	80.5	69.1	82.4	132	NRQ
UG/L	GFAA									
SILVER,TOTAL	1077	24.3	6.2	26.5	8.0	10.8	33.8	37.3	45.9	NRQ
UG/L	ICAP									
THALLIUM,TOTAL	1059	5.8	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	63.3	NRQ
UG/L	GFAA									
ZINC,TOTAL	1092	541	90.3	285	401	489	94.9	45.1	557	NRQ
UG/L	ICAP									
PHENOLS	32730	270	5	470	9	52	42	9	85	NRQ
UG/L	1									
CHROMIUM,(+6)	1032	<10.0	<10.0	30.6	23.0	<10.0	<10.0	<10.0	<10.0	NRQ
UG/L	1									

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR12W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 12 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	12SW01 RPR12W 1	12GW01 RPR12W 2	12GW02 RPR12W 3	12GW03 RPR12W 4	12GW04 RPR12W 5	12GW05 RPR12W 6	SAMPLE ID/# 12GW06 RPR12W 7	12GW06-FPURCE-GC/FP RPR12W 8	RPR12W 9
DATE		10/08/87	10/21/87	10/21/87	10/21/87	10/22/87	10/21/87	10/22/87	11/17/87	11/17/87
TIME		08:45	12:00	14:15	10:17	08:30	10:40	10:10	10:30	11:15
WATER TEMP	10	32.8	28.2	26.8	28.7	28.4	27.0	29.2	NRQ	NRQ
C	0									
PH,FIELD	400	8.20	7.10	26.8	7.30	7.60	7.30	7.10	NRQ	NRQ
STD UNITS	0									
SP.COND.,FIELD@25C	94	42500	1400	3290	11500	1520	9500	11500	NRQ	NRQ
UMHOS/CM	0									
BENZENE	34030	<1.0	<1.0	4100	<1.0	<250	<1.0	<1.0	NRQ	NRQ
UG/L	GMS									
BROMODICHLOROMETHANE	32101	<2.2	<2.2	<220	<2.2	<550	<2.2	<2.2	NRQ	NRQ
UG/L	GMS									
BROMOFORM	32104	<4.7	<4.7	<470	<4.7	<1200	<4.7	<4.7	NRQ	NRQ
UG/L	GMS									
BROMOMETHANE	34413	<5.8	<5.8	<580	<5.8	<1500	<5.8	<5.8	NRQ	NRQ
UG/L	GMS									
CARBON TETRACHLORIDE	32102	<2.8	<2.8	<280	<2.8	<700	<2.8	<2.8	NRQ	NRQ
UG/L	GMS									
CHLOROBENZENE	34301	<6.0	<6.0	<600	<6.0	<1500	<6.0	<6.0	NRQ	NRQ
UG/L	GMS									
CHLOROETHANE	34311	<8.2	<8.2	<820	<8.2	<2100	<8.2	<8.2	NRQ	NRQ
UG/L	GMS									
2-CHLOROETHYLVINYL	34576	<15	<15	<1500	<15	<3800	<15	<15	NRQ	NRQ
ETHER UG/L	GMS									
CHLOROFORM	32106	<1.6	<1.6	<160	<1.6	<400	<1.6	<1.6	NRQ	NRQ
UG/L	GMS									
CHLOROMETHANE	34418	<4.3	<4.3	<430	<4.3	<1100	<4.3	<4.3	NRQ	NRQ
UG/L	GMS									
DIBROMOCHLOROMETHANE	32105	<3.1	<3.1	<310	<3.1	<780	<3.1	<3.1	NRQ	NRQ
UG/L	GMS									
1,1-DICHLOROETHANE	34496	<4.7	<4.7	<470	<4.7	<1200	<4.7	<4.7	NRQ	NRQ
UG/L	GMS									
1,2-DICHLOROETHANE	34531	<2.8	<2.8	<280	<2.8	<700	<2.8	<2.8	NRQ	NRQ
UG/L	GMS									
1,1-DICHLOROETHYLENE	34501	<2.8	<2.8	<280	<2.8	<700	<2.8	<2.8	NRQ	NRQ
UG/L	GMS									
TRANS-1,2-DICHLORO	34546	<1.6	<1.6	<160	<1.6	<400	<1.6	<1.6	NRQ	NRQ
ETHENE UG/L	GMS									
1,2-DICHLOROPROPANE	34541	<6.0	<6.0	<600	<6.0	<1500	<6.0	<6.0	NRQ	NRQ
UG/L	GMS									
CIS-1,3-DICHLORO	34704	<5.0	<5.0	<500	<5.0	<1300	<5.0	<5.0	NRQ	NRQ
PROPENE UG/L	GMS									

RR-00039-03.13-04/01/88

PROJECT NUMBER E7488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR12W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 12 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	12SW01 RPR12W 1	12GW01 RPR12W 2	12GW02 RPR12W 3	12GW03 RPR12W 4	12GW04 RPR12W 5	12GW05 RPR12W 6	SAMPLE ID/# 12GW06 RPR12W 7	12GW06-FPURGE RPR12W 8	-GC/FP RPR12W 9
DATE		10/08/87	10/21/87	10/21/87	10/21/87	10/22/87	10/21/87	10/22/87	11/17/87	11/17/87
TIME		08:45	12:00	14:15	10:17	08:30	10:40	10:10	10:30	11:15
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4	<640	<6.4	<1600	<6.4	<6.4	NRQ	NRQ
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2	<720	<7.2	<1800	<7.2	<7.2	NRQ	NRQ
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50	<5000	<50	<700	<50	<50	NRQ	NRQ
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1	<410	<4.1	<1000	<4.1	<4.1	NRQ	NRQ
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0	<200	<3.0	<750	<3.0	<3.0	NRQ	NRQ
TOLUENE UG/L	34010 GMS	<6.0	<6.0	<600	<6.0	<1500	<6.0	<6.0	NRQ	NRQ
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8	<380	<3.8	<950	<3.8	<3.8	NRQ	NRQ
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0	<500	<5.0	<1300	<5.0	<5.0	NRQ	NRQ
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0	<100	<1.0	<250	<1.0	<1.0	NRQ	NRQ
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2	<320	<3.2	<800	<3.2	<3.2	NRQ	NRQ
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0	<100	<1.0	<250	<1.0	<1.0	NRQ	NRQ
M-XYLENE UG/L	98553 GMS	<12	<12	<1200	<12	<3000	<12	<12	NRQ	NRQ
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12	<1200	<12	<3000	<12	<12	NRQ	NRQ
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.013	<0.010	0.016	<0.010	<0.010	<0.010	<0.010	NRQ	NRQ
OIL&GR,IR MG/L	560 I	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	NRQ	NRQ
LEAD,TOTAL UG/L	1051 GFAA	11.4	6.1	21.8	2.3	2.7	42.5	4.8	NRQ	NRQ

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR12S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 12 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	12SE01 RPR12S 1
DATE			10/08/87
TIME			08:45
MOISTURE		70320	22.0
	%WET WT	1	
PH,SOIL		99218	7.9
	STD UNITS	1	
BENZENE		34237	<280
	UG/KG-DRY	GMS	
BROMODICHLOROMETHANE		34330	<140
	UG/KG-DRY	GMS	
BROMOFORM		34290	<300
	UG/KG-DRY	GMS	
BROMOMETHANE		34416	<360
	UG/KG-DRY	GMS	
CARBON TETRACHLORIDE		34299	<180
	UG/KG-DRY	GMS	
CHLOROBENZENE		34304	<380
	UG/KG-DRY	GMS	
CHLOROETHANE		34314	<530
	UG/KG-DRY	GMS	
2-CHLOROETHYLVINYL		34579	<640
ETHER	UG/KG-DRY	GMS	
CHLOROFORM		34318	<100
	UG/KG-DRY	GMS	
CHLOROMETHANE		34421	<280
	UG/KG-DRY	GMS	
DIBROMOCHLOROMETHANE		34309	<200
	UG/KG-DRY	GMS	
1,1-DICHLOROETHANE		34499	<300
	UG/KG-DRY	GMS	
1,2-DICHLOROETHANE		34534	<180
	UG/KG-DRY	GMS	
1,1-DICHLOROETHYLENE		34504	<180
	UG/KG-DRY	GMS	
TRANS-1,2-DICHLORO		34549	<100
ETHENE	UG/KG-DRY	GMS	
1,2-DICHLOROPROPANE		34544	<380
	UG/KG-DRY	GMS	
CIS-1,3-DICHLORO		34702	<320
PROPENE	UG/KG-DRY	GMS	
TRANS-1,3-DICHLORO		34697	<410
PROPENE	UG/KG-DRY	GMS	

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR12S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 12 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	12SE01 RPR12S 1
DATE			10/08/87
TIME			08:45
ETHYLBENZENE	UG/KG-DRY	34374 GMS	<460
METHYLENE CHLORIDE	UG/KG-DRY	34426 GMS	<1300
1,1,2,2-TETRACHLORO ETHANE	UG/KG-DRY	34519 GMS	<260
TETRACHLOROETHENE	UG/KG-DRY	34478 GMS	<260
TOLUENE	UG/KG-DRY	34483 GMS	<380
1,1,1-TRICHL'ETHANE	UG/KG-DRY	34509 GMS	<240
1,1,2-TRICHL'ETHANE	UG/KG-DRY	34514 GMS	<320
TRICHLOROETHENE	UG/KG-DRY	34487 GMS	<120
TRICHLOROFLUOROMETHA NE	UG/KG-DRY	34491 GMS	<210
VINYL CHLORIDE	UG/KG-DRY	34495 GMS	<310
M-XYLENE	UG/KG-DRY	97016 GMS	<380
O,P-XYLENE	UG/KG-DRY	97017 GMS	<380
1,2-DIBROMOETHANE (EDB)	UG/KG-DRY	78756 EC	<0.364
LEAD,SED	UG/G-DRY	1052 GFAA	<0.597
OIL&GR,IR,SED	UG/G- DRY	561 I	<43

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR13W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 13 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	13GW01 RPR13W 1	13GW02 RPR13W 2	13GW03 RPR13W 3	13GW04 RPR13W 4	13GW05 RPR13W 5	13GW06 RPR13W 6	13GW07 RPR13W 7	13GW08 RPR13W 8	13GW09 RPR13W 9	13GW10 RPR13W 10	13GW11 RPR13W 11	13SW01 RPR13W 13	13SW02 RPR13W 14	13SW03 RPR13W 15	13SW04 RPR13W 16
		SAMPLE ID/#														
DATE		10/19/87	10/19/87	10/19/87	10/15/87	10/15/87	10/15/87	10/15/87	10/15/87	10/14/87	10/14/87	10/15/87	10/19/87	10/19/87	10/19/87	10/20/87
TIME		11:50	11:30	10:30	11:00	12:55	11:40	09:00	08:20	14:25	13:45	09:45	09:00	09:30	09:50	09:50
WATER TEMP	10	27.9	28.4	27.9	27.5	27.7	27.2	28.4	27.3	28.2	28.2	27.4	27.0	28.8	28.4	26.9
C	0															
PH,FIELD	400	7.20	7.00	7.30	6.70	7.40	6.90	7.00	7.70	7.80	7.50	7.60	8.00	7.40	7.70	7.80
STD UNITS	0															
SP.COND.,FIELD@25C	94	2830	7360	1990	23700	5390	27400	14800	1400	2470	3900	6090	1660	3740	3740	27000
UMHOS/CM	0															
BENZENE	34030	<100	1900	110	14	2100	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
UG/L	GMS															
BROMODICHLOROMETHANE	32101	<220	<2200	<220	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2	<2.2
UG/L	GMS															
BROMOFORM	32104	<470	<4700	<470	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS															
BROMOMETHANE	34413	<580	<5800	<580	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8	<5.8
UG/L	GMS															
CARBON TETRACHLORIDE	32102	<280	<2800	<280	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS															
CHLOROBENZENE	34301	<600	<6000	<600	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS															
CHLOROETHANE	34311	<820	<8200	<820	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2	<8.2
UG/L	GMS															
2-CHLOROETHYLVINYL	34576	<1500	<15000	<1500	<15	<15	<15	<15	<15	<15	<15	<15	<15	<15	<15	<15
ETHER UG/L	GMS															
CHLOROFORM	32106	<160	<1600	<160	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6
UG/L	GMS															
CHLOROMETHANE	34418	<430	<4300	<430	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3	<4.3
UG/L	GMS															
DIBROMOCHLOROMETHANE	32105	<310	<3100	<310	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1	<3.1
UG/L	GMS															
1,1-DICHLOROETHANE	34496	<470	<4700	<470	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7	<4.7
UG/L	GMS															
1,2-DICHLOROETHANE	34531	<280	<2800	<280	150	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS															
1,1-DICHLOROETHYLENE	34501	<280	<2800	<280	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8	<2.8
UG/L	GMS															
TRANS-1,2-DICHLORO	34546	<160	<1600	<160	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6	<1.6
ETHENE UG/L	GMS															
1,2-DICHLOROPROPANE	34541	<600	<6000	<600	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
UG/L	GMS															
CIS-1,3-DICHLORO	34704	<500	<5000	<500	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
PROPENE UG/L	GMS															

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/2 STATUS: FINAL PAGE# 2

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR13W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 13 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	13GW01 RPR13W 1	13GW02 RPR13W 2	13GW03 RPR13W 3	13GW04 RPR13W 4	13GW05 RPR13W 5	13GW06 RPR13W 6	13GW07 RPR13W 7	13GW08 RPR13W 8	13GW09 RPR13W 9	13GW10 RPR13W 10	13GW11 RPR13W 11	13SW01 RPR13W 13	13SW02 RPR13W 14	13SW03 RPR13W 15	13SW04 RPR13W 16
		SAMPLE ID/#														
DATE		10/19/87	10/19/87	10/19/87	10/15/87	10/15/87	10/15/87	10/15/87	10/15/87	10/14/87	10/14/87	10/15/87	10/19/87	10/19/87	10/19/87	10/20/87
TIME		11:50	11:30	10:30	11:00	12:55	11:40	09:00	08:20	14:25	13:45	09:45	09:00	09:30	09:50	09:50
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<640	<6400	<640	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<720	<7200	<720	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<5000	<2800	<5000	<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<410	<4100	<410	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<200	<2000	<200	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<600	7500	<600	<6.0	38	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<380	<3800	<380	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<500	<5000	<500	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<100	1500	<100	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<320	<3200	<320	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<100	<1000	<100	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0	<1.0
METHYL ETHYL KETONE UG/L	81595 GMS	<4800	<48000	<4800	<48	<48	<48	<48	<48	<48	<48	<48	<48	<48	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<1200	<12000	<1200	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12
M-XYLENE UG/L	98553 GMS	<1200	<12000	<1200	<12	21	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<1200	<12000	<1200	<12	260	<12	<12	<12	<12	<12	<12	<12	<12	<12	<12
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	0.039	0.022	<0.010	0.103	<0.010	0.106	0.068	<0.010	<0.010	0.138	<0.010	<0.010	<0.010	<0.010	<0.010
LEAD,TOTAL UG/L	1051 GFAA	12.2	150	2.9	8.6	4.7	7.6	5.5	<2.2	7.6	3.1	<2.2	18.7	<2.2	7.0	26.1
OIL&GR,IR MG/L	560 1	0.3	57	<0.2	12	4	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2	<0.2

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: PA 3

PROJECT NUMBER 67488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR13W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 12 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET #	METHOD	13SW05 RPR13W 17	13SW06 RPR13W 18
DATE				10/20/87	10/20/87
TIME				09:15	08:30
WATER TEMP	C	10	0	26.6	26.5
PH,FIELD	STD UNITS	400	0	7.80	7.70
SP.COND.,FIELD@25C	UMHOS/CM	94	0	27100	27100
BENZENE	UG/L	34030	GMS	<1.0	<1.0
BROMODICHLOROMETHANE	UG/L	32101	GMS	<2.2	<2.2
BROMOFORM	UG/L	32104	GMS	<4.7	<4.7
BROMOMETHANE	UG/L	34413	GMS	<5.8	<5.8
CARBON TETRACHLORIDE	UG/L	32102	GMS	<2.8	<2.8
CHLOROBENZENE	UG/L	34301	GMS	<6.0	<6.0
CHLOROETHANE	UG/L	34311	GMS	<8.2	<8.2
2-CHLOROETHYLVINYL ETHER	UG/L	34576	GMS	<15	<15
CHLOROFORM	UG/L	32106	GMS	<1.6	<1.6
CHLOROMETHANE	UG/L	34418	GMS	<4.3	<4.3
DIBROMOCHLOROMETHANE	UG/L	32105	GMS	<3.1	<3.1
1,1-DICHLOROETHANE	UG/L	34496	GMS	<4.7	<4.7
1,2-DICHLOROETHANE	UG/L	34531	GMS	<2.8	<2.8
1,1-DICHLOROETHYLENE	UG/L	34501	GMS	<2.8	<2.8
TRANS-1,2-DICHLORO ETHENE	UG/L	34546	GMS	<1.6	<1.6
1,2-DICHLOROPROPANE	UG/L	34541	GMS	<6.0	<6.0
CIS-1,3-DICHLORO PROPENE	UG/L	34704	GMS	<5.0	<5.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR13W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 13 WATERS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	13SW05 RPR13W 17	13SW06 RPR13W 18
DATE		10/20/87	10/20/87
TIME		09:15	08:30
TRANS-1,3-DICHLORO PROPENE UG/L	34699 GMS	<6.4	<6.4
ETHYLBENZENE UG/L	34371 GMS	<7.2	<7.2
METHYLENE CHLORIDE UG/L	34423 GMS	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	<3.0	<3.0
TOLUENE UG/L	34010 GMS	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	<1.0	<1.0
METHYL ETHYL KETONE UG/L	81595 GMS	<48	<48
METHYL ISOBUT'KETONE UG/L	81596 GMS	<12	<12
M-XYLENE UG/L	98553 GMS	<12	<12
O-AND/OR-P XYLENE UG/L	98554 GMS	<12	<12
1,2-DIBROMOETHANE (EDB) UG/L	77651 EC	<0.010	<0.010
LEAD,TOTAL UG/L	1051 GFAA	32.6	37.6
OIL&GR,IR MG/L	560 I	<0.2	<0.2

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE 1

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR13S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 13 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	13SE02 RPR13S 1	13SE02 RPR13S 2	13SE03 RPR13S 3	13SE04 RPR13S 4	13SE05 RPR13S 5	13SE06 RPR13S 6
DATE			10/19/87	10/19/87	10/19/87	10/20/87	10/20/87	10/20/87
TIME			10:30	10:45	11:00	10:00	09:20	08:50
MOISTURE		70320	67.7	71.5	67.4	54.8	65.8	52.3
	%WET WT	1						
PH,SOIL		99218	7.1	7.4	7.6	7.4	7.8	7.2
	STD UNITS	1						
OIL&GR,IR,SED		561	51800	2420	3490	179	202	144
	UG/G- DRY	1						
BENZENE		34237	<680	<770	<670	2500	2400	<460
	UG/KG-DRY	GMS						
BROMODICHLOROMETHANE		34330	<340	<390	<340	<240	<320	<230
	UG/KG-DRY	GMS						
BROMOFORM		34290	<730	<820	<720	<520	<690	<490
	UG/KG-DRY	GMS						
BROMOMETHANE		34416	<870	<980	<860	<620	<820	<590
	UG/KG-DRY	GMS						
CARBON TETRACHLORIDE		34299	<430	<490	<430	<310	<410	<290
	UG/KG-DRY	GMS						
CHLOROBENZENE		34304	<930	<1100	<920	2100	2100	<630
	UG/KG-DRY	GMS						
CHLOROETHANE		34314	<1300	<1400	<1300	<910	<1200	<860
	UG/KG-DRY	GMS						
2-CHLOROETHYLVINYL		34579	<1500	<1800	<1500	<1100	<1500	<1000
ETHER	UG/KG-DRY	GMS						
CHLOROFORM		34318	<250	<280	<250	<180	<230	<170
	UG/KG-DRY	GMS						
CHLOROMETHANE		34421	<670	<750	<660	<480	<630	<450
	UG/KG-DRY	GMS						
DIBROMOCHLOROMETHANE		34309	<480	<540	<480	<340	<450	<320
	UG/KG-DRY	GMS						
1,1-DICHLOROETHANE		34499	<730	<820	<720	<520	<690	<490
	UG/KG-DRY	GMS						
1,2-DICHLOROETHANE		34534	<430	<490	<430	<310	<410	<290
	UG/KG-DRY	GMS						
1,1-DICHLOROETHYLENE		34504	<430	<490	<430	<310	<410	<290
	UG/KG-DRY	GMS						
TRANS-1,2-DICHLORO		34549	<250	<280	<250	<180	<230	<170
ETHENE	UG/KG-DRY	GMS						
1,2-DICHLOROPROPANE		34544	<930	<1100	<920	<660	<880	<630
	UG/KG-DRY	GMS						
CIS-1,3-DICHLORO		34702	<770	<880	<770	<550	<730	<520
PROPENE	UG/KG-DRY	GMS						

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR13S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 13 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS UNITS	STORET # METHOD	13SE02 RPR13S 1	13SE02 RPR13S 2	13SE03 RPR13S 3	13SE04 RPR13S 4	13SE05 RPR13S 5	13SE06 RPR13S 6
DATE		10/19/87	10/19/87	10/19/87	10/20/87	10/20/87	10/20/87
TIME		10:30	10:45	11:00	10:00	09:20	08:50
TRANS-1,3-DICHLORO PROPENE UG/KG-DRY	34697 GMS	<990	<1100	<980	<710	<940	<670
ETHYLBENZENE UG/KG-DRY	34374 GMS	<1100	<1300	<1100	<800	<1100	<750
METHYLENE CHLORIDE UG/KG-DRY	34426 GMS	<3100	4400	<3100	<2200	<2900	3200
1,1,2,2-TETRACHLORO ETHANE UG/KG-DRY	34519 GMS	<630	<720	<630	<450	<600	<430
TETRACHLOROETHENE UG/KG-DRY	34478 GMS	<630	<720	<630	<450	<600	<430
TOLUENE UG/KG-DRY	34483 GMS	<930	<1100	<920	3000	<880	<630
1,1,1-TRICHL'ETHANE UG/KG-DRY	34509 GMS	<590	<670	<580	<420	<560	<400
1,1,2-TRICHL'ETHANE UG/KG-DRY	34514 GMS	<770	<880	<770	<550	<730	<520
TRICHLOROETHENE UG/KG-DRY	34487 GMS	<290	<330	<290	2500	<280	<200
TRICHLOROFLUOROMETHA NE UG/KG-DRY	34491 GMS	<500	<560	<490	<350	<470	<340
VINYL CHLORIDE UG/KG-DRY	34495 GMS	<760	<860	<750	<540	<720	<510
M-XYLENE UG/KG-DRY	97016 GMS	<930	<1100	<920	<660	<880	<630
O,P-XYLENE UG/KG-DRY	97017 GMS	<930	<1100	<920	<660	<880	<630
METHYL ETHYL KETONE UG/KG-DRY	75078 GMS	<7400	<8400	<7400	<5300	<7000	<5000
METHYL ISOBUT'KETONE UG/KG-DRY	75169 GMS	<1900	<2100	<1800	<1300	<1800	<1300
1,2-DIBROMOETHANE (EDB) UG/KG-DRY	78756 EC	<0.467	<0.527	<0.505	<0.320	<0.478	<0.373
LEAD,SED UG/G-DRY	1052 GFAA	189	13.8	4.67	5.15	9.16	10.9

RR-00039-03.13-04/01/88

ENVIRONMENTAL SCIENCE & ENGINEERING 02/26/88 STATUS: FINAL PAGE 1

PROJECT NUMBER 874BB 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR18W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 18 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	STORET #	18SW01 RPR18W 1	18SW02 RPR18W 2	18SW03 RPR18W 3	18SW04 RPR18W 4	18SW05 RPR18W 5	18SW06 RPR18W 6	18GW01 RPR18W 8	18GW02 RPR18W 9	18GW03 RPR18W 10
		SAMPLE ID/#								
UNITS	METHOD									
DATE		10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/26/87	10/26/87	10/26/87
TIME		08:15	08:45	09:10	09:20	09:45	10:10	00:00	00:00	11:15
WATER TEMP	10	26.4	27.8	27.7	27.4	27.6	26.5	27.3	24.7	23.2
C	0									
PH,FIELD	400	7.30	7.10	7.00	6.80	6.60	6.90	7.50	7.60	6.80
STD UNITS	0									
SP.COND.,FIELD@25C	94	1270	421	398	325	1500	678	6600	1500	43500
UMHOS/CM	0									
ALDRIN	39330	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.019	<0.005	<0.005
UG/L	EC									
BHC,A	39337	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.019	<0.005	<0.005
UG/L	EC									
BHC,B	39338	<0.007	<0.007	<0.007	<0.007	<0.007	<0.007	<0.019	<0.005	<0.005
UG/L	EC									
BHC,D	34259	<0.009	<0.009	<0.009	<0.009	<0.009	<0.009	<0.019	<0.005	<0.005
UG/L	EC									
BHC,G(LINDANE)	39340	<0.010	<0.010	<0.010	<0.010	<0.010	<0.010	<0.019	<0.005	<0.005
UG/L	EC									
CHLORDANE	39350	<0.006	0.170	0.145	<0.006	0.098	<0.006	<0.006	<0.006	<0.006
UG/L	EC									
DDD,PP'	39310	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.012	0.017	<0.012
UG/L	EC									
DDE,PP'	39320	<0.005	<0.005	0.007	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									
DDT,PP'	39300	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									
DIELDRIN	39380	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									
ENDOSULFAN,A	34361	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									
ENDOSULFAN,B	34356	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									
ENDOSULFAN SULFATE	34351	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.029	<0.029	<0.029
UG/L	EC									
ENDRIN	39390	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									
ENDRIN ALDEHYDE	34366	<0.012	<0.012	<0.012	<0.012	<0.012	<0.012	<0.005	<0.005	<0.005
UG/L	EC									
HEPTACHLOR	39410	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.019	<0.005	<0.005
UG/L	EC									
HEPTACHLOR EPOXIDE	39420	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005
UG/L	EC									

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR18W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 18 WATERS LAB COORDINATOR LISA BARE

PARAMETERS	UNITS	STORET # METHOD	18SW01 RPR18W 1	18SW02 RPR18W 2	18SW03 RPR18W 3	18SW04 RPR18W 4	18SW05 RPR18W 5	18SW06 RPR18W 6	SAMPLE ID/# 18GW01 RPR18W 8	18GW02 RPR18W 9	18GW03 RPR18W 10
DATE			10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/26/87	10/26/87	10/26/87
TIME			08:15	08:45	09:10	09:20	09:45	10:10	00:00	00:00	11:15
TOXAPHENE	UG/L	39400 EC	<0.618	<0.618	<0.618	<0.618	<0.618	<0.618	<0.600	<0.600	<0.600
BENZENE	UG/L	34030 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<1.0	<1.0	<1.0
BROMODICHLOROMETHANE	UG/L	32101 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<2.2	<2.2	<2.2
BROMOFORM	UG/L	32104 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<4.7	<4.7	<4.7
BROMOMETHANE	UG/L	34413 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<5.8	<5.8	<5.8
CARBON TETRACHLORIDE	UG/L	32102 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<2.8	<2.8	<2.8
CHLOROBENZENE	UG/L	34301 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<6.0	<6.0	<6.0
CHLOROETHANE	UG/L	34311 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<8.2	<8.2	<8.2
2-CHLOROETHYLVINYL ETHER	UG/L	34576 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<15	<15	<15
CHLOROFORM	UG/L	32106 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<1.6	<1.6	<1.6
CHLOROMETHANE	UG/L	34418 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<4.3	<4.3	<4.3
DIBROMOCHLOROMETHANE	UG/L	32105 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<3.1	<3.1	<3.1
1,1-DICHLOROETHANE	UG/L	34496 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<4.7	<4.7	<4.7
1,2-DICHLOROETHANE	UG/L	34531 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<2.8	<2.8	<2.8
1,1-DICHLOROETHYLENE	UG/L	34501 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<2.8	<2.8	<2.8
TRANS-1,2-DICHLORO ETHENE	UG/L	34546 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<1.6	<1.6	<1.6
1,2-DICHLOROPROPANE	UG/L	34541 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<6.0	<6.0	<6.0
CIS-1,3-DICHLORO PROPENE	UG/L	34704 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<5.0	<5.0	<5.0
TRANS-1,3-DICHLORO PROPENE	UG/L	34699 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<6.4	<6.4	<6.4
ETHYLBENZENE	UG/L	34371 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<7.2	<7.2	<7.2

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR18W PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 18 WATERS LAB COORDINATOR LISA BARE

PARAMETERS UNITS	STORET # METHOD	SAMPLE ID/# 18SW01 RPR18W 1	18SW02 RPR18W 2	18SW03 RPR18W 3	18SW04 RPR18W 4	18SW05 RPR18W 5	18SW06 RPR18W 6	18GW01 RPR18W 8	18GW02 RPR18W 9	18GW03 RPR18W 10
DATE		10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/26/87	10/26/87	10/26/87
TIME		08:15.	08:45	09:10	09:20	09:45	10:10	00:00	00:00	11:15
METHYLENE CHLORIDE UG/L	34423 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<50	<50	<50
1,1,2,2-TETRACHLORO ETHANE UG/L	34516 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<4.1	<4.1	<4.1
TETRACHLOROETHENE UG/L	34475 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<3.0	<3.0	<3.0
TOLUENE UG/L	34010 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<6.0	<6.0	<6.0
1,1,1-TRICHL'ETHANE UG/L	34506 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<3.8	<3.8	<3.8
1,1,2-TRICHL'ETHANE UG/L	34511 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<5.0	<5.0	<5.0
TRICHLOROETHENE UG/L	39180 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<1.0	<1.0	<1.0
TRICHLOROFLUORO-METHANE UG/L	34488 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<3.2	<3.2	<3.2
VINYL CHLORIDE UG/L	39175 GMS	NRQ	NRQ	NRQ	NRQ	NRQ	NRQ	<1.0	<1.0	<1.0

RR-00039-03.13-04/01/88

PROJECT NUMBER 87488 0000 PROJECT NAME PUERTO RICO - NAVSTA
FIELD GROUP RPR18S PROJECT MANAGER RUSS BOWEN
ROOSEVELT ROADS SITE 18 SOILS LAB COORDINATOR LISA BARE

SAMPLE ID/#

PARAMETERS	UNITS	STORET # METHOD	18SE01 RPR18S 1	18SE02 RPR18S 2	18SE03 RPR18S 3	18SE04 RPR18S 4	18SE05 RPR18S 5	18SE06 RPR18S 6
DATE			10/29/87	10/29/87	10/29/87	10/29/87	10/29/87	10/29/87
TIME			08:15	08:45	09:10	09:20	09:45	10:10
MOISTURE		70320	57.0	56.5	66.7	70.4	66.9	68.3
	%WET WT	1						
ALDRIN		39333	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
BHC,A		39076	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
BHC,B		34257	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
BHC,D		34262	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
BHC,G(LINDANE)		39783	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
CHLORDANE		39351	77.8	<23.0	78.4	<33.7	<30.2	<30.6
	UG/KG-DRY	EC						
DDD,PP'		39311	<45.7	75.6	<59.6	<67.4	<60.4	<61.1
	UG/KG-DRY	EC						
DDE,PP'		39321	310	82.0	79.8	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
DDT,PP'		39301	<45.7	<46.0	<59.6	<67.4	<60.4	<61.1
	UG/KG-DRY	EC						
DIELDRIN		39383	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
ENDOSULFAN,A		34364	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
ENDOSULFAN,B		34359	<45.7	<46.0	<59.6	<67.4	<60.4	<61.1
	UG/KG-DRY	EC						
ENDOSULFAN SULFATE		34354	<45.7	<46.0	<59.6	<67.4	<60.4	<61.1
	UG/KG-DRY	EC						
ENDRIN		39393	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
ENDRIN ALDEHYDE		34369	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
HEPTACHLOR		39413	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
HEPTACHLOR EPOXIDE		39423	<18.3	<18.4	<23.9	<27.0	<24.2	<24.5
	UG/KG-DRY	EC						
TOXAPHENE		39403	<2330	<2340	<3040	<3440	<3080	<3120
	UG/KG-DRY	EC						

RR-00039-03.13-04/01/88